



APPLICATION SITE



 - Various sizes

Hardworks



CONCRETE BLOCK PAVING - to junction/raised table
 (Newbold blocks supplied by Marshalls Ltd, concrete blocks)

CONCRETE BLOCK PAVING - to shared surface streets
'Keystroke' block paving by Marshall's Ltd. concrete block.

CONCRETE BLOCK PAVING - to seating areas 'Keyblock' block paving by Marshalls Ltd, concrete block, 200 x 100 x

PERCIOUS CONCRETE BLOCK PAVING - 10 private drives
'Priced' perious block paving by Marshalls Ltd, concrete

'Keyblok' block paving by Marshalls Ltd, concrete block, 200 x 100 x 60mm, with smooth finish, chamfered

 **CONCRETE PAVING SLABS** - to front paths
 (Double Clow 1000 x 1000 concrete paving slabs by Marshall's Ltd)

pea shingle laid to a depth of 100mm over non-biodegradable geotextile membrane. Finished level to be 20mm below

NB:- In some locations an upstand is specified on the drawing.

1800mm high, 215mm wide brick wall, brick on edge coping incorporating raising file, brick line to match adjacent

1500mm high close-boarded timber fence, treated softwood (min. 15yr life span), with 300mm timber trellis on-top.

BALL TOP RAILING -
4403mm high, steel reinforced base, 25mm wide, 100mm deep, 100mm wide

1700 High Steel Estate Railing in Black.

g REAR ACCESS GATE -
Treated softwood timber gate (min. 15yrs life span),

☐ Fencing Ltd or equal and approved.

Notes:-
1) All surface materials are to be installed as specified or equal or approved

3) All block paved shared surfaces/private drives to receive small kerb unit kerbs by Marshalls Ltd or similar; upstand to engineers details (nominally

6) For all Soft Landscape Proposals, refer to CSA/2038/124-133

--	--	--	--

B	18/03/21	SS	Updates to revised layout
A	03/02/21	SS	Updates to revised layout

FOR PLANNING

Ashwell, Hertfordshire SG7 5NT

Project Land North of Softer Road

Sheet 3 of 5

Date	July 2021	Checked	GC
------	-----------	---------	----

REFER TO
CSA/2038/137