




From: Fiona Fitzgerald <Fiona.Fitzgerald@arun.gov.uk>
Sent: 09 June 2022 14:20
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: David Easton <David.Easton@arun.gov.uk>
Subject: P/56/22/DOC

Dear Planning,

1. Environmental Health note that the noise survey relied on by the applicant is 6 years old (undertaken in July 2016). Please could the applicant advise whether or not they have carried out work to confirm whether or not there has been any significant change in the acoustic environment in the last 6 years.
2. It is also noted that the original survey was undertaken between a Wednesday to a Friday, and therefore did not cover a weekend. The dates also may or may not have covered the end of the school term in West Sussex, so it is uncertain whether or not the noise survey was undertaken during the school term or not. Please could the applicant confirm whether they are satisfied that the results are still valid taking into account these points?
3. Paragraph 3.1.2 – it appears that noise level measurements were only taken from one position (shown in the site plan 16/0383/R2/SP1). Please can the applicant confirm why only one monitoring position was chosen and explain whether or not there is any uncertainty around this decision.
4. Please could a colour copy of Figure 16/0383/R2/SP2 be provided?
5. It is noted on Figure 16/0383/R2/SP2 that in some areas the acoustic barrier is 2.5m in height. David, please could you confirm that Planning are happy for an acoustic barrier of this height?
6. Please could the applicant confirm whether or not the acoustic windows/vents mitigations mean that acoustic environments cannot be achieved with windows open?
7. In specification 16/0383/SPC2, section 2 Ventilation, there is a sentence as follows: “It is anticipated systems complying with the requirements of System 3 or System 4 as defined with the Building Regulations Approved Document F 2010 would be suitable” please could the applicant confirm whether the this means that System 3 or System 4 ventilation will be installed or not, as this sentence does not specifically confirm this, it just says it would be suitable.

Regards

Fiona Fitzgerald
Senior Environmental Health Officer
Environmental Health

T: 01903 737674

E: fiona.fitzgerald@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)

