

Pennicotts Window Schedule V3

Windows	Description		Type	Structural Opening	Opening	Material	Colour	Glazing	Glass Type	4- 28-4	4-16-4
Ground Floor											
	A - GW 01	Lounge Window	Sash - NEW	910 x 1540	tbc	Timber	White	Double Glazing	Clear		Yes
	A - GW 02	Front Porch	Casement - NEW	570 x 1050		Timber	White	Single Glazing	Clear		
	A - GW 03	Front Porch	Casement - NEW	570 x 1050		Timber	White	Single Glazing	Clear		
	A - GW 04	Dining	Sash - NEW	910 x 1540		Timber	White	Double Glazing	Clear		Yes
	A - GW 05	WC	Casement - REPAIR	540 x 1020		Timber	White	Single Glazing	Opaque		
	A - GW 06	WC	Casement - REPAIR	540 x 1020		Timber	White	Single Glazing	Opaque		
	A - GW 07	Corridor WC	Casement - REPAIR	540 x 1460		Timber	White	Single Glazing	Opaque		
	A - GW 08	Corridor WC	Casement - REPAIR	540 x1460		Timber	White	Single Glazing	Opaque		
	A - GW 09	Kitchen	Casement - NEW	1490 x 1580		Timber	White	Double Glazing	Clear	Yes	
First Floor											
	A - FW 01	Bed 2A	Sash - NEW	1950 x 1450		Timber	White	Double Glazing			Yes
	A - FW 02	Corridor	Sash - REPAIR	960 x 1540		Timber	White	Double Glazing - 2ndary	upvc int opening	Yes	
	A - FW 03	Bed 1A	Sash - NEW	910 x 1540		Timber	White	Double Glazing			Yes
	A - FW 04	Bed 3A	Sash - REPAIR	960 x 1540		Timber	White	Double Glazing - 2ndary	upvc int opening	Yes	
	A - FW 05	Bath A	Sash - REPAIR	560 x 1170		Timber	White	Single Glazing - 2ndary	Toughened - Single Sheet		
	A - FW 06	Bath A	Sash - REPAIR BOTTOM 1/2 casement	900 x 1650		Timber	White	Single Glazing - 2ndary	upvc int opening		
Ground Floor											
	B - GW 01	Hall B	Sash - REPAIR	900 x 1580		Timber	White	Single Glazing	Opaque		
	B - GW 02	Kitchen	Casement - REPAIR	540 x 780		Timber	White	Single Glazing - 2ndary	Toughened - Single Sheet		
	B - GW 03	Kitchen	Casement - REPAIR	540 x 780		Timber	White	Single Glazing - 2ndary	Toughened - Single Sheet		
	B - GW 04	Kitchen	Casement - NEW	780 x 1460		Timber	White	Double Glazing			
First Floor											
	B - FW 01	Bed 1B	Sash - NEW	1200 x 1540		Timber	White	Double Glazing			Yes
	B - FW 02	Bath B	Sash - NEW	900 x 1310		Timber	White	Double Glazing	Opaque		Yes
	B - FW 03	Bed 2B	Sash - NEW	900 x 1310		Timber	White	Double Glazing			Yes
	B - FW 04	Corridor	Sash - REPAIR	960 x 870		Timber	White	Single Glazing - 2ndary	Toughened - Single Sheet		
REPAIRS:		Glass (G), Repair Glass (RG), Sill (S), Epoxy resin Frame (ER), Reset Weights (W), Latches replacements (L), External Sill (ES), Internal Sill (IS), External Lintel Render (EL)									
Building Doctors											