

The Stilwell Partnership		Page 1
Satelliet House 2 Nexus Park Ash Vale GU12 5QE	Kings Beach Hotel Pagham Urban Creep Analysis	
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx	Designed by A Johnson Checked by D Brooke	
Micro Drainage Network 2016.1		

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	Add Flow / Climate Change (%)	0
M5-60 (mm)	20.000	Minimum Backdrop Height (m)	0.200
Ratio R	0.400	Maximum Backdrop Height (m)	1.500
Maximum Rainfall (mm/hr)	50	Min Design Depth for Optimisation (m)	0.450
Maximum Time of Concentration (mins)	30	Min Vel for Auto Design only (m/s)	1.00
Foul Sewage (l/s/ha)	0.000	Min Slope for Optimisation (1:X)	500
Volumetric Runoff Coeff.	0.750		

Designed with Level Soffits

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	18.455	0.425	43.4	0.008	5.00	0.0	0.600	o	100	Pipe/Conduit	
1.001	21.600	0.215	100.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
2.000	8.365	0.555	15.1	0.011	5.00	0.0	0.600	o	150	Pipe/Conduit	
1.002	26.000	0.260	100.0	0.010	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.003	5.000	0.050	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.26	4.400	0.008	0.0	0.0	0.0	1.17	9.2	1.1
1.001	50.00	5.62	3.925	0.008	0.0	0.0	0.0	1.00	17.7	1.1
2.000	50.00	5.05	4.265	0.011	0.0	0.0	0.0	2.61	46.1	1.5
1.002	50.00	6.05	3.710	0.029	0.0	0.0	0.0	1.00	17.8	3.9
1.003	50.00	6.14	3.450	0.029	0.0	0.0	0.0	1.00	17.8	3.9

©1982-2016 XP Solutions

The Stilwell Partnership										Page 2	
Satelliet House 2 Nexus Park Ash Vale GU12 5QE					Kings Beach Hotel Pagham Urban Creep Analysis						
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx					Designed by A Johnson Checked by D Brooke						
Micro Drainage					Network 2016.1						
<u>Manhole Schedules for Storm</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Backdrop (mm)
1	4.750	0.350	Open Manhole	450	1.000	4.400	100				
2	4.700	0.775	Open Manhole	450	1.001	3.925	150	1.000	3.975	100	
3	4.850	0.585	Open Manhole	450	2.000	4.265	150				
4	4.850	1.140	Open Manhole	450	1.002	3.710	150	1.001	3.710	150	
								2.000	3.710	150	
5	4.850	1.400	Open Manhole	1200	1.003	3.450	150	1.002	3.450	150	
	5.000	1.600	Open Manhole	0		OUTFALL		1.003	3.400	150	
<u>Simulation Criteria for Storm</u>											
Volumetric Runoff Coeff 0.750 Additional Flow - % of Total Flow 0.000 Areal Reduction Factor 1.000 MADD Factor * 10m³/ha Storage 2.000 Hot Start (mins) 0 Inlet Coefficient 0.800 Hot Start Level (mm) 0 Flow per Person per Day (l/per/day) 0.000 Manhole Headloss Coeff (Global) 0.500 Run Time (mins) 60 Foul Sewage per hectare (l/s) 0.000 Output Interval (mins) 1 Number of Input Hydrographs 0 Number of Storage Structures 1 Number of Online Controls 1 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0											
<u>Synthetic Rainfall Details</u>											
Rainfall Model FSR Profile Type Summer Return Period (years) 2 Cv (Summer) 0.750 Region England and Wales Cv (Winter) 0.840 M5-60 (mm) 20.000 Storm Duration (mins) 30 Ratio R 0.400											
©1982-2016 XP Solutions											

The Stilwell Partnership		Page 3
Satelliet House 2 Nexus Park Ash Vale GU12 5QE	Kings Beach Hotel Pagham Urban Creep Analysis	
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx	Designed by A Johnson Checked by D Brooke	
Micro Drainage Network 2016.1		

Online Controls for Storm

Hydro-Brake Optimum® Manhole: 5, DS/PN: 1.003, Volume (m³): 2.0

Unit Reference	MD-SHE-0067-2000-1000-2000
Design Head (m)	1.000
Design Flow (l/s)	2.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	67
Invert Level (m)	3.450
Minimum Outlet Pipe Diameter (mm)	100
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	2.0
Flush-Flo™	0.296	1.9
Kick-Flo®	0.599	1.6
Mean Flow over Head Range	-	1.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	1.6	1.200	2.2	3.000	3.3	7.000	4.9
0.200	1.9	1.400	2.3	3.500	3.5	7.500	5.1
0.300	1.9	1.600	2.5	4.000	3.8	8.000	5.2
0.400	1.9	1.800	2.6	4.500	4.0	8.500	5.4
0.500	1.8	2.000	2.7	5.000	4.2	9.000	5.5
0.600	1.6	2.200	2.9	5.500	4.4	9.500	5.7
0.800	1.8	2.400	3.0	6.000	4.6		
1.000	2.0	2.600	3.1	6.500	4.7		

©1982-2016 XP Solutions

The Stilwell Partnership				Page 5			
Satelliet House 2 Nexus Park Ash Vale GU12 5QE		Kings Beach Hotel Pagham Urban Creep Analysis					
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx		Designed by A Johnson Checked by D Brooke					
Micro Drainage		Network 2016.1					

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region England and Wales	Cv (Summer)		0.750
M5-60 (mm)	20.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	ON
Analysis Timestep	Fine	Inertia Status	ON
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

US/MH	Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Level
						Overflow	Act.
1.000	1 15	Winter	1	+0%	100/15	Summer	4.424
1.001	2 15	Winter	1	+0%	100/15	Summer	3.950
2.000	3 15	Winter	1	+0%	100/15	Summer	4.284
1.002	4 15	Winter	1	+0%	30/15	Summer	3.758
1.003	5 15	Winter	1	+0%	1/15	Winter	3.606

Surcharged Flooded				Pipe		Level	
US/MH	Depth	Volume	Flow /	Overflow	Flow	Status	Exceeded
PN	Name	(m)	(m³)	Cap.	(l/s)	(l/s)	
1.000	1	-0.076	0.000	0.12	1.1	OK	
1.001	2	-0.125	0.000	0.07	1.1	OK	
2.000	3	-0.131	0.000	0.04	1.5	OK	
1.002	4	-0.102	0.000	0.22	3.8	OK	
1.003	5	0.006	0.000	0.13	1.8	SURCHARGED	

©1982-2016 XP Solutions

The Stilwell Partnership		Page 6
Satelliet House 2 Nexus Park Ash Vale GU12 5QE	Kings Beach Hotel Pagham Urban Creep Analysis	
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx	Designed by A Johnson Checked by D Brooke	
Micro Drainage Network 2016.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region England and Wales	Cv (Summer)		0.750
M5-60 (mm)	20.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	ON
Analysis Timestep	Fine	Inertia Status	ON
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	30	+0%	100/15	Summer			4.438
1.001	2	30 Winter	30	+0%	100/15	Summer			3.994
2.000	3	15 Winter	30	+0%	100/15	Summer			4.296
1.002	4	30 Winter	30	+0%	30/15	Summer			3.991
1.003	5	30 Winter	30	+0%	1/15	Winter			3.982

PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	1	-0.062	0.000	0.31		2.7	OK	
1.001	2	-0.081	0.000	0.13		2.1	OK	
2.000	3	-0.119	0.000	0.09		3.8	OK	
1.002	4	0.131	0.000	0.44		7.4	SURCHARGED	
1.003	5	0.382	0.000	0.14		1.9	SURCHARGED	

©1982-2016 XP Solutions

The Stilwell Partnership		Page 7
Satelliet House 2 Nexus Park Ash Vale GU12 5QE	Kings Beach Hotel Pagham Urban Creep Analysis	
Date 10/12/2018 14:25 File UC Model 10.12.18.mdx	Designed by A Johnson Checked by D Brooke	
Micro Drainage Network 2016.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	1
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region England and Wales Cv (Summer)			0.750
M5-60 (mm)	20.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	ON
Analysis Timestep		Fine Inertia Status	ON
DTS Status			ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	30 Winter	100	+40%	100/15 Summer				4.739
1.001	2	60 Winter	100	+40%	100/15 Summer				4.698
2.000	3	30 Winter	100	+40%	100/15 Summer				4.772
1.002	4	30 Winter	100	+40%	30/15 Summer				4.761
1.003	5	30 Winter	100	+40%	1/15 Winter				4.748

PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	1	0.239	0.000	0.44		3.9	FLOOD RISK	
1.001	2	0.623	0.000	0.14		2.4	FLOOD RISK	
2.000	3	0.357	0.000	0.13		5.4	FLOOD RISK	
1.002	4	0.901	0.000	0.69		11.7	FLOOD RISK	
1.003	5	1.148	0.000	0.16		2.3	FLOOD RISK	

©1982-2016 XP Solutions