

Householder and other minor extensions in Flood Zones 2 and 3

Applications for planning permission should be accompanied by a completed form. An electronic version can be submitted by 'printing' it to a PDF writer.

This guidance is for domestic extensions and non-domestic extensions where the additional footprint created by the development does not exceed 250 sq. metres. It should NOT be applied if an additional dwelling is being created, e.g. a self contained annex.

We recommend that:

Planning Authorities:

- 1) Refer the applicant to the standing advice pages on the Environment Agency website or provide them with a copy of this page for them to include as part of the planning application submission.
- 2) Check the planning application to ensure that one or other of the mitigation measures from the table below has been incorporated.

Applicants:

Complete the table below and include it with the planning application submission. The table, together with the supporting evidence, will form the Flood Risk Assessment (FRA) and will act as an assurance to the Local Planning Authority (LPA) that flood risk issues have been adequately addressed.

Applicant to choose one or other of the flood mitigation measures below	Applicant to provide the LPA with the supporting information detailed below as part of their FRA	Applicant to indicate their choice in the box below. Enter 'yes' or 'no'
Either ; Floor levels within the proposed development will be set no lower than existing levels AND, flood proofing of the proposed development has been incorporated where appropriate.	Details of any flood proofing / resilience and resistance techniques, to be included in accordance with 'Improving the flood performance of new buildings' CLG (2007)	YES
Or; Floor levels within the extension will be set 300mm above the known or modelled 1 in 100 annual probability river flood (1%) or 1 in 200 annual probability sea flood (0.5%) in any year. This flood level is the extent of the Flood Zones	This must be demonstrated by a plan that shows finished floor levels relative to the known or modelled flood level. All levels should be stated in relation to Ordnance Datum ¹	NO

PLANNING APPLICATION FOR SINGLE STOREY EXTENSIONS 52 EAST FRONT ROAD, PAGHAM, BONOR REGIS, WEST SUSSEX PO21 4ST

The proposed FFL of the seaside extension is as existing at +5.31m AOD.

The proposed FFL of the garden extension is +4.80m AOD, compared to existing FFL of +4.15m AOD in the bedroom.

The proposed undercroft storage area under the garden extension is not designed or intended for habitable purposes. It will be used for the storage of boats, sailing equipment and bicycles. The only access is via an external staircase and there is no internal connecting staircase to the ground floor.

The extensions are designed using flood resilient and resistant construction methods whenever possible.

Sabine Kunze, 25th October 2011