


Coach Lanterns



Description

This range of Stainless Steel Lanterns are suitable for all environments, together with LED saving lamp range.

Features

- Available with LED lamps or without lamps
- Includes fixing screws and wall plugs
- 2-year guarantee (not including lamp)

PIR's

- PIR incorporates photocell
- Adjustable time and lux levels on PIR
- Manual override facility on PIR

Stainless Steel Lanterns

- High grade brushed stainless steel – grade 304 – suitable for use outdoors.

Range

Stainless Steel Lanterns

Lantern with PIR	L2863
Lantern with PIR, 9.5W LED lamp	L2863LED#

Where # is one of the following finishes:

- LED3 = Cool white lamp
- LED4 = Cool white lamp

Technical Specification

Voltage	230V
Lampholder	E27
IP Rating	IP44
Steel Grade	304
	Not suitable for coastal environments
LED lamp	Megaman
	9.5W 810lm
	2800K colour temperature
	4000K colour temperature

PIR Specification

Detection range & Angle	8 meters @ 90°
Time range	10 sec – 4 minutes
Lux level range	2 – 1000 lux
Sensitivity range	up to 8 meters
Manual override	Stainless Steel – Yes

Standards

- BS EN 60598-1
- BS EN 60598-2-1
- BS EN 55015
- BS EN 61547
- BS EN 61000-3-2
- BS EN 61000-3-3
- RoHS compliant