



John Maitland
Manor Cottage
Station rd
Rustington
BN16 3AS

August 4th 2015

WORK TO BE COMPLETED TO ABOVE ADDRESS:

To point existing flint work to west elevation of cottage and smaller isolated areas as discussed/ to rebuild areas of collapsed brickwork

Dear Mr Maitland

Further to our earlier telephone conversation please see below specification so that you can properly inform the council as to our schedule of works

1. To hand finish pointing of Flint work to cottage using traditional techniques relevant to the period.
2. Materials to be used will be:
 - a. 2mm and 4mm sussex aggregate
 - b. 3 parts coarse sharp washed sand
 - c. 1 part rock common building sand
 - d. 2 parts breathable hydrolic lime

If your contact at the council office would like to speak to us further regarding this matter please feel free to pass on the company contact info at the bottom of this correspondance.

Kindest regards

Paul Duvall
Director

Checkatrade.com
Where reputation matters



Tide Solutions Ltd: 8 Ferring Lane, Ferring, Worthing, West Sussex BN12 6QU