

BROKEN BEE

No.	Species	Tag No	Height	Trunk Dia.	Radial Crown Spread	Life Stage	Physiology	Structure	Comments	Risk Size	Risk Target	Re-Inspection Date	Works	Work Priority
T1	Ash (Fraxinus excelsior)		8m	400mm est	5m	Semi-mature	Good	Good	Crown low overhanging adjacent rd.	150-450mm	Intermittent	22/12/2020	Facilitative: CL: Above ground 5m over road	
T2	False acacia (Robinia pseudoacacia)		8m	400mm est	5m	Semi-mature	Good	Fair		150-450mm	Intermittent	22/12/2020	No Works	
T3	Common alder (Alnus glutinosa)		8m	400mm est	4m	Semi-mature	Good	Good	Slightly leaning trunk; risk close to road.	150-450mm	Frequent	22/12/2020	No Works	
T4	Flowering cherry (Prunus sp.)		7m	x4 stems 300mm est	N5m NE4m E3m SE3m S5m SW6m W3m NW4m	Semi-mature	Good	Fair	Multi-stemmed from base; crown overhangs adjacent road, low.	<150mm	Frequent	22/12/2020	6 Months Facilitative: CL 5: Above ground	6 Months
T5	Sugar maple (Acer saccharum)		7m	x2 stems 400mm est	N7m E2m SE3m S4m SW5m W5m	Semi-mature	Good	Poor	Tight compression forks with evidence of included bark; risk close to road; crown overhangs adjacent rd low; twin stemmed from base.	<150mm	Intermittent	22/12/2020	6 Months Facilitative: CL 5: Above ground	6 Months
T6	Holm oak (Quercus ilex)		10m	900mm est	N7m NE4m E4m SE6m S6m SW8m W8m NW9m	Mature	Good	Hazardous	Fungal fruiting bodies on trunk; cavity at base; cracking through crown; risk close to road; of high quality, amenity tree; high ecological value.	>750mm	Frequent	22/01/2016	FELL	Three months
T7	Sycamore (Acer pseudoplatanus)		8m	400mm est	N1m E4m S4m W3m	Semi-mature	Good	Good		150-450mm	Intermittent	22/12/2020	No Works	
T8	Sycamore (Acer pseudoplatanus)		8m	400mm	N1m E4m S1m W3m	Semi-mature	Good	Good		150-450mm	Intermittent	22/12/2020	No Works	
T9	Sycamore (Acer pseudoplatanus)		7m	x2 stems 340mm est	N2m E4m S2m W3m	Semi-mature	Good	Fair	Epicormic growths.	150-450mm	Intermittent	22/12/2020	No Works	
T10	Sycamore (Acer pseudoplatanus)		8m	440mm ivy est	N3m NE3m E5m SE6m S3m SW2m W2m NW3m	Semi-mature	Good	Good	Heavily ivy-covered.	150-450mm	Intermittent	22/06/2016	6 Months Facilitative: Ivy Sever/remove ivy 6 Months Facilitative: Re-inspect	6 Months
T11	Sycamore (Acer pseudoplatanus)		7m	400mm est	N4m E4m S2m W3m	Semi-mature	Good	Good	Slightly leaning trunk.	150-450mm	Intermittent	22/12/2020	No Works	
T12	Sycamore (Acer pseudoplatanus)		6m	300mm est	N1m E3m S3m W3m	Semi-mature	Good	Good		150-450mm	Intermittent	22/12/2020	No Works	
T13	Sycamore (Acer pseudoplatanus)		7m	300mm ivy est	2m	Semi-mature	Good	Good	Ivy-covered.	150-450mm	Intermittent	22/12/2020	6 Months Facilitative: Ivy Sever/remove ivy	6 Months
T14	Sycamore (Acer pseudoplatanus)		6m	303mm ivy est	N2m NE4m E4m SE5m S3m W0m	Semi-mature	Good	Fair	Tight compression fork with evidence of included bark at base; ivy-covered.	150-450mm	Intermittent	22/12/2020	6 Months Safety: RB included limb at base 6 Months Facilitative: CI	6 Months
T15	Sycamore (Acer pseudoplatanus)		7m	500mm est	N3m E5m S3m W1m	Semi-mature	Good	Fair	Crown has been heavily reduced in past; epicormic growths; minor dead wood.	150-450mm	Intermittent	22/12/2020	No Works	

T16	Sycamore (Acer pseudoplatanus)		5m	300mm est	N4.5m NE4m E3m S0m W3m	Semi-mature	Good	Poor	Tight compression fork with evidence of included bark; twin stemmed from base.	150-450mm	Intermittent	22/12/2020	6 Months Safety: Reduce faulted limbs/stems remove included stem at base	6 Months
T17	Sycamore (Acer pseudoplatanus)			440mm est	5m	Semi-mature	Good	Good	Multi-stemmed from base; much epicormic growth on trunk; small cavities forming at sites of previous pruning wounds.	150-450mm	Intermittent	22/12/2020	No Works	
T18	Common Hawthorn (Crataegus monogyna)		4m	300mm ivy est	N1m E2m SE3m S3m SW2m W2m	Semi-mature	Good	Fair		<150mm	Frequent	22/12/2020		
T19	Aspen (Populus tremula)		7m	x2 stems 400mm ivy est	N0m E3m SE5m S4m SW4m W3m	Semi-mature	Good	Hazardous	Twin stemmed from base; tight compression fork with evidence of included bark.	150-450mm	Intermittent	22/12/2020	6 Months Safety: RB fell southern stem	6 Months
T20	Aspen (Populus tremula)		6m	300mm est	2m	Young			Dead tree.	150-450mm	Intermittent	22/12/2015	3 Months Safety: Fell	3 Months
T21	Aspen (Populus tremula)		9m	400mm ivy est	N3m E0m S0m SW4m W4m	Semi-mature	Good		Ivy in crown; slightly leaning trunk.	150-450mm	Intermittent	22/06/2016	6 Months Safety: CI 6 Months Safety: Re-inspect	6 Months
T22	Aspen (Populus tremula)		14m	x2 stems 600mm ivy est	N4m NE7m E7m SE7m S5m W0m	Mature	Good	Poor	Tight compression fork with evidence of included bark; slightly leaning trunk; ivy-covered.	150-450mm	Intermittent	22/12/2020	6 Months Safety: Reduce faulted limbs/stems reduce included eastern stem to 5m 6 Months Safety: Ivy Sever/remove ivy	6 Months
T23	Aspen (Populus tremula)		12m	600mm ivy est	N4m E2m S4m SW6m W6m NW6m	Mature	Good		Ivy-covered; asymmetrical crown as suppressed by adjacent specimens; shading adjacent allotment.		Intermittent	22/06/2016	6 Months Facilitative: Reduce crown(s) to boundary 6 Months Safety: Re-inspect 6 Months Safety: Ivy Sever/remove ivy	6 Months
T24	Aspen (Populus tremula)		17m	540mm ivy est	N4m NE10m E4m S0m W0m	Mature	Good	Fair	Protruding and wind-exposed branch with excessive end weight, at risk of failure; ivy-covered.	150-450mm	Intermittent	22/12/2020	6 Months Safety: Reduce faulted limbs/stems remove n east limb to origin 6 Months Safety: CI	6 Months
T25	Aspen (Populus tremula)		17m	600mm ivy est	N6m NE4m E3m S0m W2m NW5m	Mature	Good	Fair	Ivy-covered; slightly leaning trunk.				No Works	
T26	Aspen (Populus tremula)		14m	700mm ivy est	N12m E8m S0m W4m	Mature	Good	Poor	Heavily leaning trunk; ivy-covered; protruding and wind-exposed branch with excessive end weight, at risk of failure.	150-450mm	Intermittent	22/12/2020	6 Months Safety: CR 5: From trunk 4 to 5m	6 Months
T27	Sycamore (Acer pseudoplatanus)		5m	300mm est	N3m E3m S0m W3m	Semi-mature	Good	Good	Ivy-covered.	150-450mm	Intermittent	22/12/2020	6 Months Safety: Ivy Sever/remove ivy	6 Months
T28	Sycamore (Acer pseudoplatanus)		7.5m	400mm est	4m	Semi-mature	Good	Hazardous	Tight compression forks with evidence of included bark.	450-750mm	Intermittent		6 Months Safety: Fell	6 Months
T29	Flowering cherry (Prunus sp.)		5m	x4 stems 300mm est	3m	Semi-mature	Good	Poor	Multi-stemmed from base; risk close to road; tight compression fork with evidence of included bark at base.	150-450mm	Frequent	22/12/2020	No Works	

T30	Common Hawthorn (Crataegus monogyna)		3m	300mm est	2m	Semi-mature	Good	Good		150-450mm	Intermittent	22/12/2020	No Works	
T31	Flowering cherry (Prunus sp.)		3m	x4 stems 200mm est	2m	Young	Good	Good	Multi-stemmed from base; risk close to road; tight compression fork with evidence of included bark; mechanical wounding at base, probably caused by mowers or strimmers.	150-450mm	Frequent	22/12/2020	No Works	
T32	Lawson cypress (Chamaecyparis lawsoniana)		4m	300mm est	1.5m	Semi-mature	Good	Good		150-450mm	Frequent	22/12/2020	No Works	
T33	Ash (Fraxinus excelsior)		6m	300mm est	2m	Semi-mature	Good	Good		150-450mm	Frequent	22/12/2020	No Works	
T34	Ash (Fraxinus excelsior)		7m	400mm est	2.5m	Semi-mature	Good	Good		150-450mm	Frequent	22/12/2020	No Works	
T35	Ash (Fraxinus excelsior)		5m	300mm est	1.5m	Semi-mature	Good	Good	Drawn-up and mutually suppressed.	150-450mm	Intermittent	22/12/2020	No Works	
T36	Ash (Fraxinus excelsior)		6m	460mm est	3m	Semi-mature	Good	Good	Minor dead wood.	<150mm	Intermittent	22/12/2020	No Works	
T37	Ash (Fraxinus excelsior)		5m	340mm est	N3m NE3m E1m S2m W3m	Semi-mature	Good	Good		150-450mm	Frequent	22/12/2020	No Works	
T38	Downy birch (Betula pubescens)		4m	340mm est	1.5m	Semi-mature	Poor	Poor	Multiple columns of decay; good ecological value.	150-450mm	Occasional	22/12/2020	No Works	
T39	Ash (Fraxinus excelsior)		6m	400mm est	3m	Semi-mature	Good	Hazardous	Tight compression fork with evidence of included bark.	150-450mm	Frequent		6 Months Safety: CR 2: From trunk reduce west side 2m	6 Months
G1	Aspen (Populus tremula)		Up to 0m	Up to 0mm ivy	0m	Semi-mature	Good		Ivy-covered; slightly leaning trunk.	150-450mm	Intermittent	22/06/2016	6 Months Facilitative: Re-inspect 6 Months Safety: No action	6 Months
G2	Aspen (Populus tremula)				N7m NE6m E10m S7m W4m	Mature	Good	Hazardous	Group of drawn-up, mutually suppressed specimens; tight compression fork with evidence of included bark at base; recently pruned; ivy-covered; protruding and wind-exposed branch with excessive end weight, at risk of failure north east crown.	450-750mm	Intermittent	22/12/2020	6 Months Safety: Fell: Ground level heavily included stem north of group 6 Months Safety: CI 6 Months Arboricultural: Reduce faulted limbs/stems reduce n east limb to main stem	6 Months

3.

