

PARKLANDS / COWDRAY DRIVE

No.	Species	Height	Trunk Dia.	Radial Crown Spread	Life Stage	Physiology	Structure	Comments	Failure Potential	Risk Size	Risk Target	Re-Inspection Date	Works	Work Priority
T1	Common lime (Tilia x europaea)	8m	440mm est	N0m NE0m E4m SE4m S4m SW4m W0m NW0m	Semi-mature	Good	Fair	Crown has been heavily reduced or "topped" in past; epicormic growth at base; risk close to road.	Low	150-450mm	Frequent	17/12/2020	6 Months Facilitative: REG	6 Months
T2	Common lime (Tilia x europaea)	8m	300mm	N2m NE0m E0m SE0m S4m SW4m W4m NW3m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; epicormic growth at base; risk close to road.	Low	150-450mm	Frequent	17/12/2020	6 Months Facilitative: REG	6 Months
T3	Sycamore (Acer pseudoplatanus)	7m	360mm est	N3m E5m SE5m S5m SW4m W2m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; many pruning wounds on trunk, some occluding.	Low	150-450mm	Intermittent	17/12/2020	no works	
T4	Sycamore (Acer pseudoplatanus)	8m	400mm est	N5m NE5m E5.5m SE5m S4m SW2m W2m NW1m	Semi-mature	Good	Fair	Crown has been heavily reduced or "topped" in past; minor dead wood.	Low	150-450mm	Intermittent	17/12/2020	no works	
T5	Aspen (Populus tremula)	10m	300mm est	2.5m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; high crown; damage to buttress roots; minor dead wood.	Low	150-450mm	Intermittent	17/12/2020	no works	
T6	Sycamore (Acer pseudoplatanus)	10m	500mm est	N2m E4m SE4m S5m W2m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; squirrel damage in crown; slightly leaning trunk to south.	Low	150-450mm	Intermittent	17/12/2020	6 Months Safety: Reduce faulted limbs/stems squirrel damaged	6 Months
T7	Sycamore (Acer pseudoplatanus)	8m	540mm est	4m	Semi-mature	Good	Poor	Squirrel damage in crown. Occluding; crown has been heavily reduced or "topped" in past.	Low	<150mm	Intermittent	17/12/2020	6 Months Safety: Reduce faulted limbs/stems with squirrel damage	6 Months
T8	Sycamore (Acer pseudoplatanus)	9m	540mm est	N4.5m NE4m E4.5m SE0m S0m SW0m W3m NW4m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past.	Low	450-750mm	Constant	17/12/2020	no works	
T9	Sycamore (Acer pseudoplatanus)	10m	x4 stems 400mm est	N3m NE4m E3m SE3m S4m SW3m W3m NW3m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; significant dieback at previous pruning sites; retain dieback as habitat.	Low	450-750mm	Constant	17/12/2020	no works	
T10	Aspen (Populus tremula)	10m	x2 stems 500mm est	N4m E4m SE6m S7m SW6m W0m NW0m	Semi-mature	Good	Poor	Crown has been heavily reduced or "topped" in past; tight compression fork with evidence of included bark at base; twin stemmed from base; risk close to road.	Low	450-750mm	Frequent	17/12/2020	no works	
T11	Aspen (Populus tremula)	10m	600mm est	N0m E2m SE5m S6m SW6m W5m	Semi-mature	Good	Fair	Asymmetrical crown as suppressed by adjacent specimens; risk close to road; shrouding street light; many occluded pruning wounds on trunk; branch rubbing on adjacent tree.	Low	450-750mm	Frequent	17/12/2020	6 Months Arboricultural: Reduce faulted limbs/stems rubbing branch 6 Months Facilitative: Reduce crown(s) by 3m away from light	6 Months
T12	Sycamore (Acer pseudoplatanus)	10m	560mm est	N3m E2m S3m W3m	Semi-mature	Good	Poor	Tight compression fork with evidence of included bark; crown has been heavily reduced or "topped" in past.	Low	450-750mm	Frequent	17/12/2020	no works	
T13	Sycamore (Acer pseudoplatanus)	10m	360mm est	N2m S2.5m W2m	Semi-mature	Average	Fair	Crown has been heavily reduced or "topped" in past; high crown; risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T14	Sycamore (Acer pseudoplatanus)	10m	x5 stems 420mm est	N3m E3m S3m W2m	Semi-mature	Good	Fair	Multi-stemmed from base; risk close to road.	Low	450-750mm	Frequent	17/12/2020	no works	
T15	Sycamore (Acer pseudoplatanus)	100m	460mm	N3m E0m S3m W3m	Semi-mature	Good	Poor	Ivy-covered; cavity at base. Probed to 20cm.	Low	450-750mm	Occasional	17/12/2020	no works	
T16	Sycamore (Acer pseudoplatanus)	7m	540mm est	N6m NE5m E3m S0m W3m NW5m	Semi-mature	Good	Good	Slightly leaning trunk; crossing branches.	Low	<150mm	Occasional	17/12/2020	6 Months Arboricultural: Reduce faulted limbs/stems crossing limbs	6 Months
T17	Sycamore (Acer pseudoplatanus)	11m	540mm est	N5m E5m S0m W2m	Semi-mature	Good	Good	Slightly leaning trunk; risk close to road.	Low	450-750mm	Frequent	17/12/2020	no works	
T18	Sycamore (Acer pseudoplatanus)	11m	360mm est	2m	Semi-mature	Good	Good	High crown; risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T19	Sycamore (Acer pseudoplatanus)	10m	400mm est	N3m NE4m E5m SE0m S0m SW0m W0m NW0m	Semi-mature	Good	Good	Slightly leaning trunk; risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T20	Sycamore (Acer pseudoplatanus)	14m	520mm est	N4m E2m S1m W1m	Semi-mature	Good	Fair	Stems touching; drawn-up and mutually suppressed; risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T21	Sycamore (Acer pseudoplatanus)	4.5m	300mm est	2m	Semi-mature	Poor	Poor	Above average dead wood in crown; retain as habitat.	Medium	150-450mm	Frequent	17/12/2020	no works	
T22	Sycamore (Acer pseudoplatanus)	13m	560mm est	N3m NE3m E4m SE0m S0m SW0m W0m	Semi-mature	Good	Good	Risk close to road; asymmetrical crown as suppressed by adjacent specimens; drawn-up and mutually suppressed.	Low	450-750mm	Frequent	17/12/2020	no works	

No.	Species	Height	Trunk Dia.	Radial Crown Spread	Life Stage	Physiology	Structure	Comments	Failure Potential	Risk Size	Risk Target	Re-Inspection Date	Works	Work Priority
T23	Sycamore (Acer pseudoplatanus)	13m	540mm est	N0m E3m SE3m S2m W0m	Semi-mature	Good	Good	Risk close to road; drawn-up and mutually suppressed; asymmetrical crown as suppressed by adjacent specimens.	Low	450-750mm	Frequent	17/12/2020	no works	
T24	Sycamore (Acer pseudoplatanus)	10m	360mm est	N1m E3m S3m W2m	Semi-mature	Good	Good	Risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T25	Sycamore (Acer pseudoplatanus)	13m	460mm est	N2m E3.5m SE3m S1m W2m	Semi-mature	Good	Good	Risk close to road; drawn-up and mutually suppressed; asymmetrical crown as suppressed by adjacent specimens.	Low	150-450mm	Frequent		no works	
T26	Common Hawthorn (Crataegus monogyna)	3m	x2 stems 300mm est	3m	Semi-mature	Good	Fair	Multi-stemmed from base.	Low	150-450mm	Occasional	17/12/2020	no works	
T27	Sycamore (Acer pseudoplatanus)	13m	600mm est	N0m E5m SE5m S5m W0m	Semi-mature	Good	Good	Risk close to road; asymmetrical crown as suppressed by adjacent specimens; drawn-up and mutually suppressed.	Low	450-750mm	Frequent	17/12/2020	no works	
T28	Sycamore (Acer pseudoplatanus)	14m	500mm	E3m SE4m S3m W2m NW2m	Semi-mature	Good	Good	High crown; risk close to road; drawn-up and mutually suppressed.	Low	450-750mm	Frequent	17/12/2020	no works	
T29	Aspen (Populus tremula)	10m	500mm est	N0m E4m SE8m S6m SW0m W0m	Semi-mature	Good	Poor	Risk close to road; drawn-up and mutually suppressed; protruding and wind-exposed branch with excessive end weight, at risk of failure.	Medium	150-450mm	Frequent	17/12/2020	6 Months Safety: Reduce crown(s) laterals 3m. Height 2m reduction.	6 Months
T30	Sycamore (Acer pseudoplatanus)	12m	420mm est	N0m E2m SE3m S4m W1m	Semi-mature	Good	Good	Risk close to road; drawn-up and mutually suppressed; mechanical wounding on trunk.	Low	150-450mm	Frequent	17/12/2020	no works	
T31	Sycamore (Acer pseudoplatanus)	12m	400mm est	N2m SE3m S4m SW2m	Semi-mature	Good	Good	Risk close to road; drawn-up and mutually suppressed.	Low	150-450mm	Frequent	17/12/2023	no works	
T32	Aspen (Populus tremula)	12m	440mm est	N0m E0m S6m SW7m W6m	Semi-mature	Average	Poor	Phototropic growth to south toward rd; stem flattening and rib formation along southern stem.	High	150-450mm	Frequent	17/12/2020	3 Months Safety: Reduce crown(s) reduce southern crown by 2 to 3m	3 Months
T33	Sycamore (Acer pseudoplatanus)	12m	400mm est	N0m E3m S4m W1m	Semi-mature	Good	Good	Drawn-up and mutually suppressed; risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T34	Beech (Fagus sylvatica)	5m	340mm est	N0m E2m SE5m S4m SW4m W2m	Semi-mature	Good	Fair	Risk close to road; squirrel damage in crown.	Low	<150mm	Frequent	17/12/2020	6 Months Safety: Reduce faulted limbs/stems remove squirrel damaged lateral branches	6 Months
T35	Sweet chestnut (Castanea sativa)	14m	x2 stems 440mm est	N3m E2m S3m W2m	Semi-mature	Good	Hazardous	Twin stemmed from base; tight compression fork with evidence of included bark at base; cavity at base; drawn-up and mutually suppressed.	Medium	150-450mm	Frequent	17/12/2020	6 Months Safety: Fell southern stem	6 Months
T36	Sweet chestnut (Castanea sativa)	10m	x7 stems 360mm Ivy est	N2m E4m S5m W4m	Semi-mature	Good	Fair	Risk close to road; minor dead wood.	Low	150-450mm	Frequent	17/12/2020	6 Months Safety: DW remove loose deadwood. Retain well anchored dead as habitat	6 Months
T37	Common Yew (Taxus baccata)	6m	300mm est	N2m E2m S3m W1.5m	Semi-mature	Good	Good	Risk close to road.	Low	150-450mm	Frequent	17/12/2020	no works	
T38	Common Yew (Taxus baccata)	7m	400mm est	N4m E4m S4m W2.5m	Semi-mature	Good	Good	Risk close to road; crossing limbs, typical for sp; particularly good example of species.	Low	150-450mm	Frequent		no works	
T39	Sycamore (Acer pseudoplatanus)	10m	460mm est	N1m E4m SE5m S6m SW5m W3m	Semi-mature	Good	Good	Risk close to road; minor dead wood.	Low	150-450mm	Frequent	17/12/2020	6 Months Safety: DW	6 Months
T40	Sycamore (Acer pseudoplatanus)	9m	500mm est	N2m NE0m E0m SE3m S4m SW4m W5m NW2m	Semi-mature	Good	Good	Risk close to road; asymmetrical crown as suppressed by adjacent specimens.	Low	150-450mm	Frequent	17/12/2020	no works	
T41	Sycamore (Acer pseudoplatanus)	9m	340mm est	N0m E3m S2m W1m	Semi-mature	Good	Good	Ivy-covered; minor dead wood; high crown; drawn-up and mutually suppressed.	Low	150-450mm	Frequent	17/12/2020	no works	
T42	Sycamore (Acer pseudoplatanus)	14m	x2 stems 450mm est	2.5m	Semi-mature	Good	Hazardous	Drawn-up and mutually suppressed; tight compression fork with evidence of included bark; twin stemmed from base; cavity at base; slightly leaning eastern stem.	Medium	150-450mm	Occasional	17/12/2020	6 Months Safety: Fell eastern stem	6 Months
T43	Sycamore (Acer pseudoplatanus)	10m	420mm est	N0m NE0m E0m SE0m S0m SW0m W6m NW7m	Semi-mature	Good	Good	Heavily leaning trunk.	Low	150-450mm	Intermittent	17/12/2020	6 Months Safety: CR: From trunk remove leaning stem	6 Months
T44	Sycamore (Acer pseudoplatanus)	12m	500mm est	N3m S1m SW3m W5m	Semi-mature	Good	Hazardous	Twin-stemmed from 1m; tight compression fork with evidence of included bark; slightly leaning trunk.	Medium	450-750mm	Intermittent		6 Months Safety: Fell	6 Months
T45	Sycamore (Acer pseudoplatanus)	11m	500mm est	N3m E0m S1m SW6m W7m NW6m	Semi-mature	Good	Good	Minor dead wood; slightly leaning trunk; asymmetrical crown as suppressed by adjacent specimens.	Low	450-750mm	Occasional	21/12/2020	no works	

No.	Species	Height	Trunk Dia.	Radial Crown Spread	Life Stage	Physiology	Structure	Comments	Failure Potential	Risk Size	Risk Target	Re-Inspection Date	Works	Work Priority
T46	Sycamore (Acer pseudoplatanus)	11m	420mm est	N4m E2m S3m W3m	Semi-mature	Below average	Good	Cavity at base; fungal fruiting bodies decaying below cavity; polyporus squamous, Dryads saddle.	Low	450-750mm	Occasional		6 Months Safety: Fell	6 Months
T47	Sycamore (Acer pseudoplatanus)	13m	400mm est	N3m E3m S1m W2m	Semi-mature	Good	Good	Slightly leaning trunk.	Low	150-450mm	Frequent	21/12/2020	no works	
T48	Sycamore (Acer pseudoplatanus)	12m	x2 stems 380mm est	N3m E3m S3m W0m	Semi-mature	Good	Good	Twin stemmed from base; slightly leaning trunk.	Low	150-450mm	Frequent	21/12/2020	no works	
T49	Ash (Fraxinus excelsior)	14m	380mm est	N2m E4m S3m SW2m W3m	Semi-mature	Good	Good	High crown; drawn-up and mutually suppressed; drawn-up and mutually suppressed.	Medium	450-750mm	Frequent	21/12/2020	no works	
T50	Sycamore (Acer pseudoplatanus)	14m	x3 stems 500mm	NE3m S3m NW3m	Semi-mature	Good	Fair	Multi-stemmed from base.	Low	150-450mm	Frequent	21/12/2020	no works	
T51	Scots pine (Pinus sylvestris)	5m	300mm est	N5m E3m S3m W3m	Young	Good	Good	Mechanical wounding at base, probably caused by mowers or strimmers; many surface roots, damaged on upper sides, probably by mowers.	Low	150-450mm	Frequent	21/12/2020	no works	
T52	Common alder (Alnus glutinosa)	6m	320mm est	3m	Semi-mature	Good	Fair	Tight compression fork with evidence of included bark.	Low	150-450mm	Occasional	21/12/2020	no works	
T53	London plane (Platanus X acerifolia)	9m	440mm est	5m	Semi-mature	Good	Good		Low	450-750mm	Occasional	21/12/2020	no works	
T54	Common Yew (Taxus baccata)	5m	440mm est	3m	Semi-mature	Good	Good	Particularly good example of species.	Low	150-450mm	Occasional	21/12/2020	no works	
T55	Portuguese laurel (Prunus lusitanica)	5m	x3 stems 400mm est	5m	Mature	Good	Poor	Tight compression forks with evidence of included bark; barbed wire around stems becoming included into and suppressing growth of cambium ; crown touching adjacent building; three stemmed from base; crossing stems.	Low	<150mm	Occasional	21/12/2020	6 Months Facilitative: Reduce crown(s) away from property, retaining form 6 Months Arboricultural: See Comment cut and remove where poss wire	6 Months
T56	Grey poplar (Populus canescens)	7m	300mm est	2.5m	Semi-mature	Good	Good		Low	150-450mm	Frequent	21/12/2020	no works	
T57	Grey poplar (Populus canescens)	7m	300mm est	2.5m	Semi-mature	Good	Good		Low	150-450mm	Frequent	21/12/2020	no works	
T58	London plane (Platanus X acerifolia)	8m	440mm est	N5m NE7m E5m S5m W5m NW6m	Semi-mature	Good	Good	Risk close to road; low over rd and pavement.	Low	150-450mm	Frequent	21/12/2020	6 Months Facilitative: Raise low canopy 5m over rd	6 Months
T59	False acacia (Robinia pseudoacacia)	7m	400mm est	5m	Semi-mature	Average	Fair	Minor dead wood.	Low	150-450mm	Intermittent	21/12/2020	no works	
T60	Common Horse Chestnut (Aesculus hippocastanum)	2.5m	200mm est	2m	Young	Poor	Poor		Low	150-450mm	Occasional	21/12/2020	no works	
T61	Sycamore (Acer pseudoplatanus)	6m	300mm est	3m	Semi-mature	Good	Good		Low	150-450mm	Occasional	21/12/2020	no works	
T62	Ash (Fraxinus excelsior)	6m	420mm est	4m	Semi-mature	Good	Good		Low	150-450mm	Occasional	21/12/2020	no works	
T63	London plane (Platanus X acerifolia)	8m	440mm est	7m	Semi-mature	Good	Good	Slightly leaning trunk; risk close to road.	Low	150-450mm	Frequent	21/12/2020	no works	
G1	Common Yew (Taxus baccata)	Up to 6m	Up to x2 stems Max 400mm est	N5m NE6m E5m SE3m S4m SW3m W3m NW2m	Semi-mature	Good	Fair	Slightly leaning trunk.	Low	150-450mm	Intermittent	17/12/2020	no works	
G2	Sweet chestnut (Castanea sativa)	Up to 0m	Up to Max 400mm	N5m E6m S6m W0m	Semi-mature	Poor	Fair	dieback in crown. Previously shortened. Regrowth good; epicormic growth at base; ivy-covered; risk close to road.	Medium	150-450mm	Frequent	17/12/2020	no works	

No.	Species	Height	Trunk Dia.	Radial Crown Spread	Life Stage	Physiology	Structure	Comments	Failure Potential	Risk Size	Risk Target	Re-Inspection Date	Works	Work Priority
G3	Silver birch (Betula pendula)	Up to 4m		0m	Semi-mature	Good	Good		Low	150-450mm	Occasional	21/12/2020	no works	
G4	Sycamore, Aspen, Sweet Chestnut	15m Average			Semi-mature	Good		Ring of approximately 25 trees. All inspected with no major defects. Low risk - infrequently populated. Any trees within group with defects individually plotted on map, with recommended works.					no works	