



Woodland strip from Foxes Close (North) to Hutchinson Close (South). Focusing on tree frontage/trees east side of ditch-line only. In addition to our quotation provided on the 7th May 2020.

(Foxes Close)

-T1/2 1x Oak/1x Beech (North), reduce entire crown to shape by 2m. Crown lift to give a height clearance 5m from ground level over drive-way. Crown thin by 5%. Remove all substantial deadwood throughout crown. Estimated starting height 16m.

-T3 1x Oak (small), crown lift to give a height clearance of 5m from ground level over drive-way. Reduce east lateral growth by 1m, grading into top section of crown. Estimated starting height 8m.

-T4 1x Beech, reduce entire crown to remove die-back by up to 2m. Remove all substantial deadwood throughout crown. Estimated starting height 20m.

-T5 1x Elder, fell to ground level.

-T6/7 2x Cherry, crown lift to give a height clearance of 4m from ground level over drive-way. Reduce lateral growth east side of crown by 1.5-2m. Estimated starting height 5-6m.

-G1 Lime (group), reduce to shape by 1.5-2m. Crown lift to give a height clearance of 4m over drive-way. Estimated starting height 5-7m.

-T8 1x Oak, reduce entire crown to shape by 2m and crown lift to give a height clearance of 4m from ground level over drive-way. Remove all substantial deadwood throughout crown. Estimated starting height 14m.

-T9 1x Sycamore, reduce entire crown to shape by 1.5-2m. Crown lift to give a height clearance of 4m from ground level over drive-way. Estimated starting height 16m.

-T10 1x Beech (029), reduce entire crown to shape by 2-2.5m. Reduce 1x over-extended lateral limb (east at 7m) by 4m back to suitable growth point. Remove all substantial deadwood throughout crown. Estimated starting height 22m, lateral spread 12-14m.

(Pinch point between ~~Hamilton Drive & Columbine Way~~)