



- Sycamore saplings, crown lift to give a height clearance of 4m over drive-way.
- T23 1x Cherry, reduce entire crown to shape by up to 2.5m. Estimated starting height 12.5m.
- T24/25/26 3x Sweet Chestnut, reduce all three trees as one crown by up to 2m. Crown lift to give a height clearance of 4m over drive-way. Remove all substantial deadwood throughout crown. Estimated starting height 16m.
- T27 1x Oak (small), reduce entire crown to shape by 1m. Remove all substantial deadwood throughout crown. Estimated starting height 8m.
- T28 1x Oak (large), reduce entire crown to shape by 2m. Crown lift to give a height clearance of 4m over drive-way. Remove all substantial deadwood throughout crown. Estimated starting height 18m.
- T29 1x Cherry, crown lift to give a height clearance of 4m over drive-way. Estimated starting height 5m.
- T30 Sycamore trees adjacent to parking bay, reduce by 1.5m and crown lift to give a height clearance of 4m from ground level. Estimated starting height 8m.
- T31 1x Sycamore (large), reduce entire crown to shape by 2m. Remove all substantial deadwood throughout crown. Estimated starting height 22m.
- T32 1x Sycamore (large tree in terminal decline), fell leaving 2m high monolith. Estimated starting height 18m.
- G2 Sycamore trees (group opposite number 7), reduce by 1.5m. Crown lift to give a height clearance of 4m over driveway. Estimated starting height 10-12m.
- T33/34/35 3x Field Maple (opposite number 8), reduce entire crown to shape by up to 1.5m. Crown lift to give a height clearance of 4m from ground level. Remove all substantial deadwood throughout. Estimated starting height 7m.
- T36 1x Ash (in between 2x Field Maple in decline), fell to ground level. Estimated starting height 7m.

*(Windsor Drive turn round point)*

- T37/38 2x Ash (adjacent to number 42), reduce entire crown to shape by up to 1.5m. Estimated starting height 7-