



*(Hutchinson Close)*

-T44 1x Ash, crown lift to give a height clearance of 4m from ground level, reduce remaining crown to shape by up to 2m. Estimated starting height 16m.

- Sweet Chestnut saplings, crown lift to give a height clearance of 4m from ground level. Estimated starting height 8m.

-T45-51 7x Sycamore, reduce entire crown to shape by 2-2.5m. Crown lift to give a height clearance of 4m from ground level. Remove all substantial deadwood throughout crown. Remove basal growth. Estimated starting heights 16-18m

-T52 1x Ash (opposite number 9), reduce entire crown to shape by 1.5-2m. Crown lift to give a height clearance of 4m from ground level. Remove all substantial deadwood throughout crown. Estimated starting height 16m.

-T53 1x Sycamore (opposite number 9), reduce entire crown to shape by 1.5m. Remove all substantial deadwood throughout crown. Estimated starting height 16m

-T54 1x Sweet Chestnut (opposite number 9), reduce entire crown to shape by 1.5m. Crown lift to give a height clearance of 4m from ground level. Remove all substantial deadwood throughout crown. Estimated starting height 18m.

-T55 1x Sycamore (large), reduce entire crown to shape by 2-2.5m. Remove all substantial deadwood throughout crown. Estimated starting height 22m.

- Sycamore saplings (group), cut back from Orchard Park static home.

--

Josh Steere (Managing Director)

Tom Cave (Managing Director)



Business address:

TTC- Total Tree Care Ltd