

Drainage Statement

**Site: Booker Hall, Rustington Hall
Nursing Home, Station Road,
Rustington, BN16 3AY**

**Proposal: Demolition of existing community hall
and associated storage buildings, and
construction of replacement
community hall.**

August 2021

1. **Introduction**

This surface water and foul drainage statement has been prepared to address the impacts of the proposed development on the existing drainage infrastructure.

The proposal comprises a submission for the demolition of the existing community hall, and the associated outbuildings to the North. Thereafter, a replacement community building will be constructed, which also includes provision for office space at ground and first floor.

2. **Existing Drainage**

The site is currently occupied by existing buildings, which includes an existing Hall and ancillary space. Waste water generated within the site is currently drained to existing public sewers.

3. **Planning Policy Considerations**

Local Plan policies are contained in Arun Local Plan 2011-2031 (2018) and Rustington Neighbourhood Plan (2014). The Local Plan and Neighbourhood Plan provides guidance on the approach to development within the district.

With specific regard to drainage, Policy W DM3 of the Local Plan is of most relevance as it relates to sustainable drainage systems. The policy states:

To increase the levels of water capture and storage and improve water quality, all development must identify opportunities to incorporate a range of Sustainable Urban Drainage Systems (SUDS), appropriate to the size of development, at an early stage of the design process.

Proposals for both major and minor development proposals must incorporate SUDS within the private areas of the development in order to provide source control features to the overall SUDS design. These features include:

- *Green roofs*
- *Permeable driveways and parking*
- *Soakaways*
- *Water harvesting and storage features including water butts.*

Given the form of development to redevelop the existing site and that the site is largely covered by hard standing, a comprehensive SuDS strategy is not considered to be required and can be appropriately secured via condition.

Notwithstanding the absence of a detailed drainage scheme, the site has been subject to some early ground investigation work which confirms that infiltration drainage for surface water could be achieved on site. Further works will be required, but this is considered sufficient to demonstrate the principle of such a drainage arrangement. A copy of the ground investigation results are included at Appendix 1.

Built development can lead to increased surface water run-off; therefore new development is encouraged to incorporate mitigation techniques in its design, such as permeable surfaces and Sustainable Drainage Systems (SuDS). This can be included in the final detailed design

and following further ground investigation works, which can take place over the 2021 / 2022 winter period.

4. Proposed Surface Water Drainage

The proposed development will provide a new hall and office space. The proposed building will be located in place of existing buildings and hard standing.

Surface water drainage will either be provided via newly constructed soakaways or directed in to the existing surface water drainage sewer serving the existing buildings. Any soakaway would likely be proposed below the upgraded areas of soft landscaping to the east side of the proposed hall and office buildings.

Given the existing built form and hard standing, it is not considered that the proposal would result in any increased surface water run-off from the site.

5. Proposed Foul Drainage

The proposed development would be connected in to the existing foul sewage network serving the building. Whilst the proposal does result in a small increase in residential properties on the site, the proposed development would not have a significantly greater impact upon the existing foul drainage network.

Appendix 1: Site investigation report

FACTUAL SITE INVESTIGATION REPORT

At

Oakhurst Gardens,
Rustington

On behalf of

Studio Scott Taylor

PROJECT REFERENCE: 21.1045.A

April 2021

constructiveevaluation
site investigation • building pathology



Factual Site Investigation Report

by

Constructive Evaluation Ltd

Units 15-16 Ford Lane Business Park, Ford, Arundel BN18 0UZ



Report Author(s)		
Jocelyn Middleton MGeol FGS (Senior Geo-Environmental Consultant)		Date: 6/4/2021
Report Checked & Approved by		
David Meredith MSc BSc FGS (Senior Engineering Geologist)		Date: 6/4/2021

	Version 1	Version 2	Version 3
History			
Issued to			
Date			

Foreword

This report has been prepared by Constructive Evaluation Limited (CE) with all reasonable skill, care and diligence within the terms of the contract with the Client and should not be used in a different context. Unless specifically assigned or transferred within the terms of the agreement, CE asserts and retains all Copyright, and other intellectual Property Rights in and over the Report and its contents.



CONTENTS

1.0	Introduction	6
1.1	Site Proposal	6
1.2	Summary of Site Investigation.....	6
2.0	Site Background	7
2.1	Published Geology	7
2.2	Physical Site Setting	7
3.0	Field Work	8
4.0	Ground Conditions	9
4.1	Observed Stratigraphical Units	9
4.2	Groundwater	9
4.3	Field Evidence of Contamination	9
5.0	Statutory Consultees	10

FIGURES

Figure 1 – Site Location Plan

Figure 2 – Site Investigation Plan

Figure 3 – Proposed Site Plan

APPENDICES

Appendix A – Stratigraphic Logs

Appendix B - Site Investigation Photographs

Appendix C – Groundwater Monitoring Results

Appendix D – Report Terms and Conditions

1.0 Introduction

In March 2021 Constructive Evaluation (CE) Limited was commissioned by Studio Scott Taylor to carry out a Site Investigation at Oakhurst Gardens, Rustington Hall, Station Road, Rustington, West Sussex, BN16 3AW, hereafter referred to as the “site”.

The purpose of this investigation and report is to provide winter groundwater monitoring data and to carry out infiltration testing. However, it should be noted that only the first monitoring round has been carried out to date with the outstanding works to be completed within the winter months.

Attention is drawn to the fact that whilst every effort has been made to ensure the accuracy of the data supplied and any analysis derived from it, there is a potential for variations in ground and groundwater conditions between and beyond the specific locations investigated. No liability can be accepted for any such variations. Furthermore, any recommendations are specific to the Client’s requirements as detailed herein and no liability will be accepted should these be used by third parties without prior consultation with Constructive Evaluation Ltd.

A desk study as outlined in BS5930 “Code of practice for site investigations” was not requested and therefore has not been carried out.

1.1 Site Proposal

There are three areas currently under development. It is understood that Area 1 will have renewed parking, with Area 2 and Area 3 being demolished with the construction of two further buildings.

The Proposed Site Plan is presented as **Figure 3**.

1.2 Summary of Site Investigation

An outline of the intrusive works instructed are summarised below:

- 3no. windowless sampler boreholes to a maximum depth of 6mbgl/refusal.
- 3no. standpipe installations for future winter groundwater monitoring.
- 3no. infiltration tests within mechanically excavated trial pits.

2.0 Site Background

2.1 Published Geology

Reference to the publications of the British Geological Survey (BGS), indicate the site is underlain by bedrock of the New Pit Chalk Formation. Superficial deposits for the area are recorded as River Terrace Deposits.

River Terrace Deposits – sand and gravel, locally with lenses of clay, silt or peat. Superficial deposits formed up to 3 million years ago in the Quaternary Period.

New Pit Chalk Formation – Chalk. Sedimentary bedrock formed approximately 90 to 94 million years ago in the Cretaceous Period. Principally blocky, white firm to moderately hard chalk with numerous marls or paired marl seams. Flint occurs sporadically in the upper part in the deeper basin areas of the Southern Province. In some localities flint, in seams, occurs towards the base of the formation most notable over structural highs, towards the margins of the outcrop and within the "Transitional" Province.

2.2 Physical Site Setting

Based on Ordnance Survey 1:25000 maps of the area, the subject site is within a residential area of Rustington, surrounded by mixed residential properties and a school. The general area is flat with no water courses noted. The Site Location Plan is presented in **Figure 1**.

At the time of investigation, the site comprised three small areas of development. The three areas are all located behind Rustington Hall, just north of Station Road. Descriptions of the areas are as follows:

Area 1: Asphalt car parking with additional parking to east surfaced with construction stone for temporary works at Rustington hall – access via Station Road;

Area 2: Existing Booker Hall with additional small out-buildings to north, with a few trees, access via Station Road;

Area 3: Existing Laundry building with one out-building, with a concrete drying area to south – access via Oakhurst Gardens

The site has an approximate grid reference of TQ 06180 02586, with the three areas totalling approximately 1,258m².

The site comprises a mixture of one and two storey buildings and flats, with small designated car parking areas and grassed communal areas.

3.0 Field Work

The following intrusive works were carried out over two days on 26th and 29th March 2021, supervised by an Engineering Geologist from CE:

- 3no. windowless sampler boreholes (WLS1-WLS3) to a maximum depth of 6mbgl;
- 3no. groundwater standpipe installations to a maximum depth of 5.55mbgl.

The Site Investigation Plan showing the final exploratory positions is provided in **Figure 2**.

The ground investigation was undertaken in accordance with the scope of works agreed with our Client and in relation to statutory guidance including BS5930: 1999 Code of Practice for Site Investigations (Amendment 3: 2015) and BS10175: 2011+A1: 2013 Investigation of Potentially Contaminated Sites: Code of Practice.

All intrusive locations were logged, with visual and/or olfactory evidence of contamination noted.

4.0 Ground Conditions

4.1 Observed Stratigraphical Units

The following anthropogenic (made ground) strata were encountered during the intrusive works:

The surface cover identified included grass at WLS1 and WLS2 with concrete surfacing at WLS3.

Beneath the surface cover, a slightly sandy slightly gravelly clayey topsoil with flint was noted in WLS2 to 0.2mbgl; with further anthropogenic soils identified with slightly sandy slightly gravelly clay with flint and asphalt fragments overlying a concrete slab in WLS1 to 0.20mbgl; with subbase at WLS3 to 0.2mbgl.

Beneath the made ground material, the natural stratigraphic sequence was interbedded layers as follows:

Firm orange-brown to brown slightly sandy slightly gravelly CLAY

Brown clayey gravelly SAND

Brown sandy GRAVEL / gravelly SAND

These interbedded layers were proven to 6mbgl at all locations, and are considered to be the superficial River Terrace Deposits. The New Pit Chalk Formation was not encountered, however chalk gravels were noted in the base of WLS2 between 5m-6mbgl.

The Stratigraphic Logs are provided in **Appendix A**, with Site Investigation Photographs presented in **Appendix B**.

4.2 Groundwater

Groundwater was not encountered during the site works however, it should be noted that any groundwater would not necessarily be readily observed due to the short timescale and areas of relatively impermeable clays. Furthermore, groundwater levels may vary both seasonally and in the long-term.

Groundwater monitoring standpipes, with a diameter of 19mm were installed in WLS1, WLS2 and WLS3 to depths of between 4.55m and 5.55mbgl. The sides at the base of the boreholes collapsed onto the installations.

Groundwater was monitored on 31st March as part of the winter groundwater monitoring. The future monitoring will be continued on a monthly basis from October 2021. Infiltration testing at the three areas of site will also be scheduled at this time. Groundwater Monitoring Results are presented in **Appendix C**.

4.3 Field Evidence of Contamination

No visual or olfactory evidence of contamination was observed during the site investigation. Anthropogenic materials were observed to 0.2mbgl in boreholes WLS1 and WLS3.

5.0 Statutory Consultees

Following completion of all the site works and monitoring we would recommend that this report be forwarded to the relevant Statutory Consultees including the Local Council's Environmental Health and Planning Department to seek their comments and subsequent approval prior to works commencing on site.

The Statutory Authorities may require a Validation and/or closure report providing documentation/audit trail for the importation/removal/reuse of material on site and any other remedial works completed on site.

FIGURES

Figure 1 – Site Location Plan

Figure 2 – Site Investigation Plan

Figure 3 – Proposed Site Plan



Notes:

1. Do not scale from this drawing.
2. All dimensions must be checked on site prior to commencement of work.
3. Where applicable this drawing is to be read in conjunction with other consultants drawings.
4. This drawing is the copyright of Constructive Evaluation Ltd.

KEY

Drawing Title:

Figure 1: Site Location
Plan

Project Reference:

21.1045

Site Name:


Oakhurst Gardens,
Rustington

Revision: 0

Drawn by: JM

Scale: Not to Scale

 **constructiveevaluation**
site investigation • building pathology





Notes:

1. Do not scale from this drawing.
2. All dimensions must be checked on site prior to commencement of work.
3. Where applicable this drawing is to be read in conjunction with other consultants drawings.
4. This drawing is the copyright of Constructive Evaluation Ltd.

KEY



WLS

Borehole



Development
Areas

Drawing Title:

Figure 2: Site
Investigation Plan

Project Reference:

21.1045

Site Name:

Oakhurst Gardens,
Rustington

Revision: 0


Drawn by: JM

Scale: Not to Scale



constructiveevaluation
site investigation • building pathology





Notes:

1. Do not scale from this drawing.
2. All dimensions must be checked on site prior to commencement of work.
3. Where applicable this drawing is to be read in conjunction with other consultants drawings.
4. This drawing is the copyright of Constructive Evaluation Ltd.

KEY



Development Areas

Drawing Title:

Figure 3: Proposed Site Plan

Project Reference:

21.1045


Site Name:

Oakhurst Gardens,
Rustington

Revision: 0

Drawn by: JM

Scale: Not to Scale



APPENDICES

Appendix A – Stratigraphic Logs

Appendix B – Site Investigation Photographs


Appendix C – Groundwater Monitoring Results

Appendix D – Report Terms and Conditions

APPENDIX A



Stratigraphic Logs

 constructiveevaluation site investigation • building pathology				Borehole Log			Borehole No. WLS1 Sheet 1 of 1		
Project Name: Oakhurst Gardens				Project No. 21.1045		Co-ords: 506198E - 102557N		Hole Type WLS	
Location: Rustington				Level:		Scale 1:50			
Client: Studio Scott Taylor				Dates: 29/03/2021		Logged By IB			

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m AOD)	Legend	Stratum Description	
		Depth (m)	Type	Results					
					0.10		Grass over firm greyish brown slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is angular to sub-rounded fine to coarse of flint and asphalt.		
					0.20		(MADE GROUND) Concrete Slab.		
					1.10		Firm orangish brown mottled grey slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is sub-angular to rounded fine to coarse of flint. Brown clayey gravelly SAND. Sand is fine to coarse. Gravel is angular to sub-rounded fine to coarse of flint.	1	
					1.85		Orangish brown sandy GRAVEL. Sand is fine to coarse. Gravel is angular to rounded fine to coarse of flint.	2	
					2.80		Yellowish brown gravelly SAND. Sand is fine to coarse. Gravel is sub-angular to rounded fine to coarse of flint.	3	
					3.30		Soft becoming firm with depth orangish brown mottled grey slightly sandy CLAY. Sand is fine and medium.		
					3.90		<i>Firm dark grey slightly sandy CLAY. Sand is fine and medium.</i>		
					3.90		Firm orangish brown mottled grey slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is sub-angular to rounded fine to coarse of flint.	4	
					4.95		Brown clayey gravelly SAND. Sand is fine to coarse. Gravel is angular to rounded fine to coarse of flint.	5	
					5.45		Brown SAND. Sand is fine to coarse.		
				6.00		End of Borehole at 6.000m	6		
								7	
								8	
								9	
								10	


Remarks 1. Excavation area scanned using CAT and Genny prior to any excavation, repeated every 300mm in service pit to 1.2mbgl. 2. Borehole installed with 19mm groundwater monitoring standpipe to a depth of 5.55mbgl. 3. Borehole collapsed at the base on installation of monitoring well.		
---	--	---

 constructiveevaluation site investigation • building pathology				Borehole Log			Borehole No. WLS2 Sheet 1 of 1		
Project Name: Oakhurst Gardens				Project No. 21.1045		Co-ords: 506187E - 102604N		Hole Type WLS	
Location: Rustington				Level:				Scale 1:50	
Client: Studio Scott Taylor				Dates: 26/03/2021				Logged By IB	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m AOD)	Legend	Stratum Description	
		Depth (m)	Type	Results					
					0.20		 Grass over soft dark brown slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is sub-angular to rounded fine to coarse of flint. (TOPSOIL)  Firm orangish brown mottled grey slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is sub-angular to rounded fine and medium of flint.	1	
					1.90		 Firm grey mottled orangish grey slightly sandy slightly gravelly CLAY.	2	
					2.10		 Brown clayey sandy GRAVEL. Sand is fine to coarse. Gravel is angular to sub-rounded fine to coarse of flint.		
					2.40		 Brown gravelly SAND. Sand is fine to coarse. Gravel is angular to rounded fine and medium of flint.		
					2.95		 <i>Band of firm grey sandy CLAY. Sand is fine to coarse.</i>	3	
							 Grey slightly gravelly SAND. Sand is fine to coarse. Gravel is sub-angular to rounded fine and medium of flint.		
					3.55		 Soft becoming firm with depth orangish brown mottled grey slightly sandy CLAY. Sand is fine and medium.	4	
							 <i>Firm dark grey slightly sandy CLAY. Sand is fine and medium.</i>		
					5.00		 Yellowish brown gravelly SAND. Sand is fine to coarse. Gravel is sub-angular to rounded fine to coarse of flint and occasional weak low density white chalk.	5	
					6.00		 End of Borehole at 6.000m	6	
							7		
							8		
							9		
							10		

Remarks 1. Excavation area scanned using CAT and Genny prior to any excavation, repeated every 300mm in service pit to 1.2mbgl. 2. Borehole installed with 19mm groundwater monitoring standpipe to a depth of 4.55mbgl. 3. Borehole collapsed at the base on installation of monitoring well.		
---	--	---

 constructiveevaluation site investigation • building pathology				Borehole Log				Borehole No. WLS3 Sheet 1 of 1	
Project Name: Oakhurst Gardens				Project No. 21.1045		Co-ords: 506177E - 102638N		Hole Type WLS	
Location: Rustington				Level:		Scale 1:50		Logged By IB	
Client: Studio Scott Taylor				Dates: 26/03/2021					

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m AOD)	Legend	Stratum Description	
		Depth (m)	Type	Results					
					0.10		CONCRETE		
					0.20		SUBBASE		
							Firm brown mottled grey slightly sandy CLAY. Sand is fine and medium.	1	
								2	
					2.60		Brown gravelly SAND. Sand is fine to coarse. Gravel is angular to rounded fine and medium of flint.	3	
					3.45		Soft becoming firm with depth orangish brown mottled grey slightly sandy CLAY. Sand is fine and medium. <i>Firm dark grey slightly sandy CLAY. Sand is fine and medium.</i>	4	
					4.50		Brown gravelly SAND. Sand is fine to coarse. Gravel is angular to rounded fine to coarse of flint.		
					4.90		<i>Band of firm brown slightly sandy CLAY. Sand is fine and medium.</i> Firm brown slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is angular to rounded fine to coarse of flint. Occasional pockets of orangish brown fine and medium Sand.	5	
					6.00		End of Borehole at 6.000m	6	
								7	
							8		
							9		
							10		

Remarks 1. Excavation area scanned using CAT and Genny prior to any excavation, repeated every 300mm in service pit to 1.2mbgl. 2. Borehole installed with 19mm groundwater monitoring standpipe to a depth of 5.45mbgl. 3. Borehole collapsed at the base on installation of monitoring well.								
---	--	--	--	--	--	--	--	---

APPENDIX B

Site Investigation Photographs

Investigation Photographs


Project Ref: 21.1045

Site Name: Oakhurst Gardens, Rustington


1.



2.



3.



4.



- 1) WLS1 general area
- 2) WLS1 reinstatement
- 3) WLS2 reinstatement
- 4) WLS2 general area

Investigation Photographs


Project Ref: 21.1045

Site Name: Oakhurst Gardens, Rustington

5.



6.



- 5) WLS3 reinstatement
- 6) WLS3 general area

APPENDIX C

Groundwater Monitoring Results

Results of Monitoring Visits

Date of Monitoring Visit	Time of Visit	Weather Conditions	Depth to Water (mbgl)			Depth to Base (mbgl)		
			WLS1	WLS2	WLS3	WLS1	WLS2	WLS3
31/03/2021	08:00	Clear ~10°C	3.77	3.53	4.10	5.55	4.56	5.48

APPENDIX D

Report Terms and Conditions

Trading Terms

Unless specifically stated within the tender/quotation or unless identified within the introduction to this report it is confirmed that this report has been compiled wholly in accord with Constructive Evaluation Limited's terms of engagement. This report is provided for sole use by the Client and is confidential to them. No responsibility whatsoever for the contents of the report will be accepted to anyone other than the Client.

Copyright

Copyright of this report subsists with the originator. Prior written permission must be obtained for any third party to reproduce, store in a retrieval system or transmit in any form of by any means whatsoever, all or part of this report. The copyright of written materials supplied shall remain the property of Constructive Evaluation Limited but with a royalty-free perpetual licence, granted to the Client on payment in full of any outstanding monies.

Context

This report is written in the context of an agreed scope of work between Constructive Evaluation Limited and the Client and should not be used in a different context. In light of additional information becoming available, improved practices and changes in legislation amendment or re-interpretation of the report in whole or part may be necessary after its original submission.

Professional Interpretation

The recommendations made and opinions expressed in the report are based on the conditions revealed by the site works together with an assessment of the data from the insitu and laboratory testing or in respect of the desktop reports. No responsibility can be accepted for conditions that have not been revealed by the research, site works and testing.

The Client is advised that the conditions observed on site by Constructive Evaluation Limited at the time of any site survey may be subject to change. Certain indicators of the presence of hazardous substances may have been latent at the time of the most recent site reconnaissance and they may subsequently have become evident. It is not possible to assess areas which are inaccessible or where access is not granted and CE accept no liability for risks subsequently identified therein.

The conceptual model, Risk assessment and sampling regime has been formulated in accordance with current UK guidance at time of production based upon the relevant information gained from Phase 1 and Phase 2 investigations. While the model and assessment offer opinions and interpretations of these guidelines, the comments made are for guidance only and no liability can be accepted for their accuracy. It is possible that aspects of desktop study may need to be altered to conform to the requirements of the statutory regulatory bodies.

Intrusive Field Operations

The data collected through direct operations in the production of this report has been so obtained, unless directly otherwise stated, in accordance with current UK guidance, law or accepted industry practice, including but not limited to: BS.5930: 1990 Code of Practice for Site Investigations (Amendment 2: 2010), BS 10175:2011+A1:2013 Investigations into Potentially Contaminated Sites, and BS.8576:2013 Guidance on Investigations for Ground Gas – Permanent Gases and Volatile Organic Compounds. Exact exploratory locations will depend upon access conditions, site use and plant capability, CE do not accept liability for issues arising from material identified between or outside of the area of exploratory locations.

Laboratory Testing

Unless stated otherwise within the text, all geotechnical and material laboratory tests have been performed in accordance with the relevant British Standard Documents. Laboratory testing for contaminated land assessment is completed under the UKAS / MCERTS accreditation schemes, unless identified as otherwise in the report.

Human Health Risk Assessment Criteria

The Environment Agency has recently undertaken revision of the Soil Guideline Values (SGVs) which are partially complete. Where standards are available using the "new" approach, these have been utilised for correlative purposes. Where standards have not yet been revised, guidance following the "old" approach has been utilised. Please note that upon release of the remaining guidelines, the standards contained within this report may be subject to change. In addition, the second edition of the LQM CIEH guidance has now been released and will be utilised in favour of previously published guideline values.

Third Parties

The findings and opinions conveyed in this report are based on information obtained from a variety of sources, including that from previous Site investigations and chemical testing laboratories. Constructive Evaluation Limited has assumed that such information is correct. Constructive Evaluation Limited cannot and does not guarantee the authenticity or reliability of the information it has relied upon and can accept no responsibility for inaccuracies with the data supplied by other parties.

The accuracy of the historical map extracts supplied cannot be guaranteed and it should be noted that different conditions may have existed between mapping sheet editions. Therefore, there can be no certainty that all areas of contamination have been identified during the Phase 1 investigation.

Definitions

Reference to the word "contamination" in this report does not relate to the statutory definition of contaminated land under 1990 Environmental Protection Act unless otherwise stated. The definition used in this report is: "Land that contains substances that, when present in sufficient quantities or concentrations, are likely to cause harm, directly or indirectly, to man, to the environment, or on occasion to other targets" (NATO CCMS, 1985).

CE Ltd 2014