

Planting Schedule – to be read in conjunction with Landscape Plan 18071/01R1

Species	Total Quantity	Planting Size (pot size)	Size when mature	Planting Season	Planting density
Rhododendron	5(woodland area) 5 Individual	5Lts	2-3m	Spring/Autumn	1-2 per sqm See Dwg for location Individual plans
Camellia	5	5Lts	2-3m	Spring/Autumn	1-2 per sqm
Skimmia japonica	6	4Lts	1.5m	Spring/Autumn	1 per sqm
Ilex aquifolium variegata	3	2Lts	4-5m	Spring/Autumn	1 per 2 sqm
Cordyline australis 'Torbray Dazzler'/'Sundance'	5-7	2Lts	2-3m	Autumn	See Dwg for location
Deschampsia 'Goldtau'	See Dwg. Approx 20	1.5 Lts	0.5m	Autumn	See Dwg for location
Verbena banariensis	14-18	2Lts	1.5m	Spring/Autumn	See Dwg for location
Hakonechloa 'Aureola'	See Dwg. Approx 15	2Lts	.5m	Autumn	See Dwg for location
Euphorbia amygdaloides	3	2Lts	1m	Spring/Autumn	See Dwg for location
lavender	10-14	1Lts	.75m	Spring/Autumn	See Dwg for location
Hebes	7-9	2Lts	1m	Spring/Autumn	See Dwg for location
Eleagnus	6	2Lts	2-2.5m	Spring/Autumn	See Dwg for location
Phormium 'Evening Glow'	1	2Lts	1.5m	Autumn	See Dwg for location
Cotoneaster dammeri	1	2Lts	1.5m	Spring/Autumn	See Dwg for location
Fatsia Japonica	2	5Lts	3m	Spring/Autumn	See Dwg for location
Acer palmatum 'Blood Good'	1 Standard Tree	30Lts	5m	Spring/Autumn	See Dwg for location

Notes

- It is expected that the site will undergo twice yearly maintenance during Spring and Autumn.
- All bulbs to be planted in a naturalistic way towards the front of borders.
- Bark mulch to be laid to all bare earth surrounding planting to a depth of 2 in.

Planting of Acer

Dig a hole as deep as the pot/rootball and approximately 2x as wide, loosen soil in bottom of pit.

Remove the pot and place the tree in the hole so that it is upright and the surface of the compost is flush with, or slightly raised above, the soil level of your site. If your soil is poor it may be advisable to sprinkle fertiliser around the rootball, to improve establishment.

Back fill the soil into the hole, firming gently but firmly.

Place a stake at angle to tree so as to miss the root ball, and knock in until stable, tie the tree to the stake using suitable tie that can be loosed with growth. Check tie yearly.