

SEA ESTATE RUSTINGTON – PROPOSED TPO WORK – 2021/22 (TABLE A) (Issue 2) – Revised 9 November 2021

NO	ROAD NAME	HOUSE NUMBER/ NAME	TREE TYPE	COMMENTS/PROPOSED WORK
1A	Sea Avenue	5	Lime	Crown reduction: reduce height by 15% (3m) and spread by 11% (1m); proposed height and spread measurement post reduction – 17m height/8.5m spread. Work to include removal of crossing branches
2A	Sea Avenue	7	Lime	Crown reduction: reduce height by 15% (3m) and spread by 11% (1m); proposed height and spread measurement post reduction – 17m height/8.5m spread. Work to include removal of crossing branches
3A	Sea Avenue	11	Lime x 2	Thin crown by 20% and remove epicormic growth
4A	Sea Avenue	15	Lime	Thin crown by 20% and remove epicormic growth
5A	Sea Avenue	17	Lime	Thin crown by 20% and remove 1.5m of overhang on east side
6A	Sea Avenue	62	Austrian/Black Pine	Remove lowest SE-facing branch over road, above fork, to reduce weight on left-hand limb (concern over structure of tree – note compression damage to main trunk) & dead wood
7A	The Parkway	26	Corsican Pine	Reduce all N-facing branches by 1.5m to re-balance tree
8A	The Parkway	47	Corsican Pine	Remove lowest S-facing branch (to re-balance tree) & crossing branches, dead wood & crown thin
9A	Bushby Avenue	26	Scots Pine	Remove crossing branches & three lowest E-facing branches off major limb (max 150mm dia) to re-balance tree
10A	Preston Avenue	Opp Marbuk (16)	Silver Birch	Fell & stump grind; tree in poor condition and evidence of fungus
11A	Thatchway	Foxwood	Monterey Cypress/ Macrocarpa	Crown reduction: reduce height by 10% (2m) and spread by 12% (2m) back to live growth on branches no larger than 50mm diameter and remove dead wood. Proposed height and spread measurement post reduction: 18m height/15m spread. (This level of work was approved on the Macrocarpa on the junction of Sea Ave and Thatchway in 2018); the tree has lost several limbs during recent winters due to high winds, and residents are concerned for their personal safety.
12A	Thatchway	Lynwood	Monterey Cypress/ Macrocarpa	Crown reduction: reduce height by 10% (2m) and spread by 13% (2m) back to live growth on branches no larger than 50mm diameter and remove dead wood. Proposed height and spread measurement post reduction: 18m height/14m spread. (This level of work was approved on the Macrocarpa on the junction of Sea Ave and Thatchway in 2018); the tree has lost several limbs during recent winters due to high winds, and residents are concerned for their personal safety.