




**Existing Tree**
Existing tree to be retained within the development proposals

**Proposed Tree Planting**
Proposed tree planting to be 14 – 16 cm Girth Size / 4.25 – 6.0m height / 1.75-2.0m Clear Stem / Standard Extra Heavy Stock.


**Proposed Ornamental Planting Areas**
Proposed ornamental planting areas to feature shrub / herbaceous planting. Planting area to be 300mm depth (minimum) subsoil overlain with 450mm (minimum) multi purpose topsoil to BS3882: 2007 'Specification for Topsoil and Requirements for Use'.


**Proposed Hedgerow Planting**
Proposed hedgerow to frontage. Hedgerow planting areas to be 300mm depth (minimum) subsoil overlain with 450mm (minimum) multi purpose topsoil to BS3882: 2007 'Specification for Topsoil and Requirements for Use'.

**Proposed Grass Seeded / Turfed Areas**
Proposed grass seeded / turfed areas to be 300mm depth (minimum) subsoil overlain with 150mm depth (minimum) of multi purpose topsoil to BS3882:2007 'Specification for Topsoil and Requirements for Use'.

**Proposed Resin Bonded Aggregate**
Proposed resin bonded aggregate surface treatment to car parking area and pedestrian path to frontage.

**Rear Garden Patio Areas and Paths**
Patio areas and paths to have sandstone paving.

**Proposed Brick Wall**
Proposed brick wall to frontage (1.2m high) and car parking area (1.8m high).

**Existing Boundary Fencing**
Existing 1.8m high, timber Fencing to be retained to western and northern boundaries.

**Proposed 1.8m high Boundary Fencing**
Proposed 1.8m high, timber fencing.

**Proposed 1.2m high Fencing**
Proposed 1.2m high, timber picket fencing to pedestrian path to frontage.

NOTES
Refer to RCo140 / 02 / Detailed Planting Plan and RCo140 / Detailed Plant Schedule and Specification for further details.

REV	DESCRIPTION	DATE	INITIALS
00	Preliminary Draft Layout	19-11-14	AR
01	Preliminary Draft Layout Updated	19-11-14	AR
02	Planning Layout	23-11-14	AR



The Studio, 68 Cuckfield Road, Hurstpierpoint, West Sussex, BN6 9SB
T: 01273 834 198 M: 07973 770047 E: landscape@ramsayan.co.uk

Project Title:
The Tiled Barn, Station Road, Rustington
Globe Estates (southern) Ltd
Drawing Title:
Planting Layout

Scale: 1:100@A1	Drawn: AR	Date: 19-11-14
Drawing Number: RCo 140 / 01	Revision:	Revision: 02

APR 2015 DISTRICT COUNCIL

