

TQ 00 SW 3/7

Rustington Convalescent Home Sea Road

II

2. Convalescent Home. 1897 by F Wheeler in a neo-Caroline style. Brown brick with red dressings and some stone enrichment. Slate hipped roof with single and paired segment headed dormers. 2 storeys with attics and 1 storey and attic wing to east. Central square 4-storey tower with stone dressings surmounted by clock stage and octagonal open cupola over. 13 bay central block, with sash windows in pairs, and half-hipped aprons below glazing bars only in broken upper leaves. Central stone segmental pedimented entrance in tower. 3-bay east wing, windows very closely spaced in centre with balcony over ground floor. 3-bay west wing projecting pediment gable over and with windows closely spaced in centre and 2-storey octagonal corner turret with octagonal conical roof over at south-west corner. West front 3-bays with south-west corner turret. Central 1-bar projection with pediment over and stone segmental-pedimented entrance Interior: Contemporary wooden 5-flight rectangular open well staircase with ramped handrail, closed strings and spiral balusters. Decorative stained glass in octagonal bay lighting stair-well.

Listing NGR: TQ0432401456

National Grid Reference: TQ 04324 01456

AND

TQ 00 SW 3/8 Ancillary Building at Rustington Convalescent Home Sea Road

II

2. Staff quarters block for Rustington Convalescent Home. 1897 by F Wheeler in a neo-Caroline style. Brown brick with red dressings. Wooden eaves cornice. Parallel ridge slate roof with central gable pediment to south, containing thermal window, over slight central projection. Octagonal ogee-domed cupola in central roof-valley. 2 storeys; 7 bays, with central 1 bay projection, wider with

coupled windows in single opening. Sashes with glazing bars in upper blade and with slight segment heads on 1st floor and with rubbed brick arches and prominent rubbed brick keystones on ground-floor. 2 storey 1 bay extension to left with parapetted roof, topped by globes. Irregular fenestration. Brick chimney to rear with upper stone moulded cornice decoration above blank brick arched panels.

Listing NGR: TQ0434801577

National Grid Reference: TQ 04348 01577