



01. Planting Plan

Key

- Retained Trees
- Tree Protection Areas (RPA's)
- Proposed Trees
- Hedges - proposed
- Soft planted areas
- Amenity lawn
- Phase 1 boundary
- Site boundary

02. Planting Schedule

Ref.	Species	Common Name	No.	Girth (cm) or Size (L)	Density /Lm	Clear stem height (m)	Notes
T1	<i>Trees</i>						<i>UK grown stock</i>
T2	<i>Betula pendula</i>	silver birch	3	12-14		2	Strong central leader, balanced, well branched even canopy. Planted in close stand.
	<i>Quercus ilex</i>	holm oak	1	20-25		2	Strong central leader, balanced, well branched even canopy. To be trimmed into
H1	<i>Formal hedge 35Lm</i>						
	<i>Escallonia rubra</i> 'Crimson Spire'	escallonia	140	5L	4		40-60cm high stock. Branched, min. 6 breaks. Supplied as bushy hedging plants. Plant in double staggered row 45cm apart, at 50cm centres. To be trimmed into shape in-situ. Mature hedge height: 1.2m.

03. Planting Schedule

Ref.	Species	Common Name	Size (L)	% mix	Density /m²	No	Habit / Minimum number of breaks	Notes
P3	<i>Shrubs / Herbaceous Planting 163sqm</i>							
	<i>Aucuba japonica</i> 'Rozannie'	Japanese laurel	3L	4%	4	26	Bushy, min. 5 breaks	
	<i>Anemathela lessoniana</i>	New Zealand wind grass	2L	9%	5	73		
	<i>Brachyglottis</i> (Dunedin Group) 'Sunshine'	ragwort	3L	4%	4	26	Branched, min. 3 breaks	
	<i>Bupleurum fruticosum</i>	shrubby hare's ear	2L	5%	3	24	Bushy, min. 3 breaks	
	<i>Cistus x purpureus</i>	purple-flowered rock rose	3L	9%	3	44	Bushy, min. 4 breaks	
	<i>Cytisus x spachianus</i>	sweet broom	3L	9%	3	44	Bushy, min. 4 breaks	
	<i>Euonymus japonicus</i>	Japanese spindle	3L	4%	3	20	Branched, min. 4 breaks	
	<i>Euphorbia characias</i>	spurge	2L	4%	4	26		
	<i>Fuchsia magellanica</i>	lady's eardrops	3L	4%	4	26	Bushy, min. 5 breaks	
	<i>Hebe rakaiensis</i>	Rakai hebe	3L	9%	5	73	Bushy, min. 5 breaks	
	<i>Hebe x franciscana</i> 'Blue Gem'	hebe	3L	9%	5	73	Bushy, min. 5 breaks	
	<i>Laurus nobilis</i>	bay tree	3L	3%	1	5	Bushy, min. 5 breaks	
	<i>Lavandula angustifolia</i> 'Hidcot'	English lavender	2L	10%	6	98	Bushy, min. 5 breaks	
	<i>Phlomis russelliana</i>	Turkish sage	2L	4%	4	26		
	<i>Rosmarinus officinalis</i>	rosemary	3L	9%	3	44	Bushy, min. 4 breaks	
	<i>Tamarix ramosissima</i>	tamarisk	3L	4%	4	26	Branched, min. 4 breaks	
AL	<i>Amenity lawn 252sqm</i>							
	<i>Festuca rubra</i>	red fescue		30%				
	<i>Festuca rubra</i> subsp. <i>litoralis</i>	slender red fescue		25%	50 g/m² sowing rate			Low Maintenance Grass Seed Mix
	<i>Festuca rubra</i> subsp. <i>commutata</i>	Chewing's fescue		25%				
	<i>Poa pratensis</i>	smooth-stalked meadow grass		15%				
	<i>Agrostis castellana</i>	Highland bent		5%				

Do not scale drawings. All dimensions to be checked on site.
Errors to be reported immediately to landscape architect.
To be read in conjunction with all relevant architects, Services and engineers drawings.

Revision Tracker
01 - Planning Issue for Condition 7

06.02.2018

Churchman Landscape Architects

London
3.04 Chester House, Kennington Park,
1-3 Brixton Rd, SW9 6DE

Bristol
S4 Bristol & Exeter House,
Lower Approach Road, BS1 6QS

+44(0)20 3727 6780
mail@churchmanla.co.uk

Date
Scale
Drawn
23.01.2018
1:250/A1
CP/ADK

Location
Client
Littlehampton, West Sussex
The Carpenters' Company

Rustington Convalescent Home
Planting Plan

494-CLA-XX-0F-DR-L-0501



REV
01