



01. Landscape Materials Plan

Materials schedule

- Retained Trees
- Tree Protection Areas (RPA's)
- Proposed Trees
- Hedges - proposed
- Soft planted areas
- Amenity lawn
- Phase 1 boundary
- Site boundary

Hard materials

- Coloured asphalt - ULTICOLOUR, Colour: Buff
- Resin bound paving, gravel finish
Addagrip, Addaset, 6mm 'Maple Gold' aggregate finish
- Granite Cobble Edging 300mm, Granite Setts, 100 x 100 x 100 mm,
Colour: Mid Grey
- Clay Brick Pavers - Wienerberger, Padova DF, 200 x 64 x 85 mm,
Colour: Eindhoven Mixed Red, Herringbone Bond
- Clay Stable Block - Wienerberger, Smooth Stable Blue (Square pattern),
200 x 100 x 65 mm
- Granite raised kerb, 150 x 1000 x 300 mm,
Colour: Mid Grey, Finish: Fine picked
- Granite dropped kerb, 150 x 1000 x 300/150 mm,
Colour: Mid Grey, Finish: Flamed/Fine picked
- Granite flush kerb, 150 x 1000 x 300 mm,
Colour: Mid Grey, Finish: Flamed/Fine picked
- Precast Concrete pin kerb (Flat top), 50 x 914 x 150 mm,
Colour: Grey
- Permeable clay paving - Wienerberger, Aquata clay paver, 200 x 64 x 80 mm,
Colour: Doris (brown multi), Stretcher Bond
- Brick Wall 1.8m high - English Garden Bond, to match Carpenter's House facing brickwork
- Close Board Timber Fence 1.8m high - Horizontal Ship Lap Panels,
- Timber Gate 1.8 x 0.9 m to match fencing

Do not scale drawings. All dimensions to be checked on site.
Errors to be reported immediately to landscape architect.
To be read in conjunction with all relevant architects, Services and engineers drawings.

Revision Tracker
01 - Planning Issue for Condition 7

06.02.2018

Churchman Landscape Architects

London
3.04 Chester House, Kennington Park,
1-3 Brixton Rd, SW9 6DE

Bristol
S4 Bristol & Exeter House,
Lower Approach Road, BS1 6QS

+44(0)20 3727 6780
mail@churchmanla.co.uk

Date
Scale
Drawn

23.01.2018
1:250/A1
CP/ADK

Location
Client

Littlehampton, West Sussex
The Carpenters' Company

Rustington Convalescent Home
Landscape Materials Plan

494-CLA-XX-0F-DR-L-0101



REV
01