TREE SCHEDULE

TREE NO.	SPECIES	DIA.(m)	HT.(m)Estd
1	Cherry	0.18/0.14	5
2	Bay	0.15/3x13	6
3	Beech	0.50/0.29	14
4	Beech	0.35	15
5	Beech	0.46	15
6	Beech	M/Bole	11
7	Poplar	0.50	19
8	Eucalyptus	0.18/0.10	9
9	Palm	0.37	4
10	Eucalyptus	0.24	11.5
11	Holly	0.10/10/2x0.13	5(L)
12	W/Willow	0.17	6
13	Poplar	1.20	19
14	Willow	0.19/17/15/12	8
15	S/Birch	0.41	15
16	S/Birch	0.34	16
17	W/Willow	0.22	7
18	Hazel	M/Bole	6
19	Fir	0.46	12
20	Pine	0.24	9
21	Poplar	0.65/0.33	19
22	Maple	0.25	6(L)
23	Poplar	0.42	20
24	W/Willow	0.19	5
25	Cherry	0.31	8
26	Poplar	0.42/0.38	18
27	Poplar	0.34	18
28	Fir	0.15	9
29	Fir	0.15	9
30	Fir	0.33	16
31	Sycamore	2x0.19	13
32	Sycamore	0.26	13
33	Ash	0.24	10
34	Fruit	0.14	4
35	Elder	M/Bole	4
36	Elder	M/Bole	4
37	Hazel	M/Bole	6
38	Poplar	0.47/0.46	18
39	Hazel	M/Bole	7
40	Poplar	0.35	15
41	Hazel	M/Bole	6
42	Oak	0.12	6
43	Poplar	0.41/34/28	18
44	Poplar	0.40	17
45	Sycamore	0.41	14
46	Sycamore	0.31	15
47	Sycamore	0.38	15
48	Sycamore	0.40	17
49	H/Chestnut	0.29	15
50	Poplar	0.85	17

TREE NO.	SPECIES	DIA.(m)	HT.(m)Estd
51	Poplar	0.50/0.45	17
52	Poplar	0.61	17
53	Hazel	M/Bole	7
54	Yew	0.11	3
55	Hazel	M/Bole	5
56	Cherry	0.16	7
57	Cherry	0.15	7
58	Cherry	0.14/0.10	7
59	Yew	0.22	7
60	Cherry	0.40	7
61	Cherry	0.20	9
62	Cherry	0.22	9
63	Fruit	0.22	6
64	Dead	0.14	6
65	Cherry	M/Bole	12
66	Beech	0.40/30/27	14
67	Beech	M/Bole	14
68	Beech	M/Bole	4
69	Beech	0.23/0.17	14
70	Beech	0.26/0.13	14
71	Beech	0.24/0.22	14
72	Beech	M/Bole	14
73	Beech	0.45/0.11	14
74	Beech	M/Bole	13
75	Fir	M/Bole	11
76	Oak	0.14	8
77	Beech	M/Bole	14
78	–	–	–
79	–	–	–
80	–	–	–
81	–	–	–
82	–	–	–
83	–	–	–
84	–	–	–
85	–	–	–
86	–	–	–
87	–	–	–
88	–	–	–
89	–	–	–
90	–	–	–
91	–	–	–
92	–	–	–
93	–	–	–
94	–	–	–
95	–	–	–
96	–	–	–
97	–	–	–
98	–	–	–
99	–	–	–
100	–	–	–

Legend

AV	Air Valve	FH	Fire Hydrant	LP	Lamp Post	SI	Step
Bol	Bollard	FL	Floor Level	MH	Manhole	SV	Stop Valve
OSBM	Bench Mark	FLP	Flag Pole	Mkr	Marker	TCB	Telephone Call Box
BS	Bus Stop	G	Gulley	MS	Mile Stone	TIC	Telecom IC
CATV	Cable TV Cover	GIC	Gas IC	NB	Notice Board	THL	Threshold Level
CL	Cover Level	GV	Gas Valve	P	Post	TL	Traffic Light
CP	Catch Pit	Ht	Height	RE	Rodding Eye	TP	Telegraph Pole
Cul	Culvert	Hyd	Hydrant	RH	Ridge Height	VP	Vent Pipe
D	Door	IC	Inspection Cover	RNB	Road Name Board	WM	Water Meter
Dr	Drain	IL	Invert Level	RWP	Rain Water Pipe	WO	Water Outlet
DP	Down Pipe	Irr/IC	Irrigation Valve	RP	Reflector Post	–	–
EH	Eave Height	JB	Junction Box	RS	Road Sign	ø	Diameter
EIC	Electricity IC	Kb	Kerb	S/A	Soakaway	⊻	Level
EP	Electricity Pole	KO	Kerb Outlet	SL	Sump Level	(CH)	Floor to Ceiling
ER	Earth Rod	LB	Letter Box	SP	Sign Post		Joist Direction

Fence & Wall Details

BA	Barrier	IRF	Iron Railings	PRF	Post & Rail	RW	Retaining Wall
BWF	Barbed Wire	INT	Interwoven	PRP	Post & Rope	W	Wall
CBF	Close Board	LLF	Larch lap	PTF	Post & Tube	–	–
CIF	Corrugated Iron	OL	Over-lap	PWF	Post & Wire	–	–
CLF	Chain Link	Pal	Paling	PWM	Post & Wire Mesh	–	–
CPF	Chestnut Paling	PCF	Post & Chain				

Drainage

CL	Cover Level
IL	Invert Level
ø	Diameter of Pipe
(SP)	Sealed Pipe Below
Depth	Depth to Silt

Slope — Bushes and Hedges — Gate

NOTES :Drainage Information has been gained by visual inspection only.All possible care has been taken to ensure correct information but TJK Land Surveyors can not accept responsibility for costs arrising from errors or omissions.

All tree heights are estimated.

Indicative

T.J.K. LAND SURVEYORS
LAND, BUILDING AND ENGINEERING SURVEYS
9 HAWTHORNE ROAD,TOTTON,SOUTHAMPTON,SO40 3HH
TEL/FAX 023 8086 4140
MOBILE (07711)680769
E Mail: trevor@tjkland.freeserve.co.uk

© COPYRIGHT

CLIENT	SOUTHCOTT HOMES LTD
TITLE	GREEN OAKS BARNHAM ROAD—BARNHAM
JOB NO.	TJK1463
SHEET	SHEET 1 OF 1
DATE	JULY 2009
DRAWN BY	T.J.K.
CHECKED BY	S.K.
SCALE	1:200 (A0) Rotation 0
LEVEL DATUM	OSBM. PILLAR AT THE MOW—HAY Value 11.53m

ARUN DISTRICT COUNCIL R/51/11/