



Heritage Clay Tiles Ltd

Head Office Denton Wharf Business Park, Unit 1 Mark Lane, Gravesend, Kent, DA12 2QD t: 01474 560278 f: 01474 560318

Regional Office Unit 18 Maybrook Business Park, Maybrook Road, Minworth, West Midlands B76 1AL t: 01213131939 f: 0121 3516552

E: enquiries@heritageclaytiles.co.uk

Burbia is a blue grey slate with a smooth surface which may contain some non- active metal particles. Hand spit to a thickness of 5-6mm and is a popular choice on housing developments and commercial projects. It comes with a 30 year guarantee and conforms to all aspects of BSEN12326 with A1,T1, S1 performance ratings.

ORIGIN:

Abejera de Tabara , Spain..

PRODUCTION:

15.000 Tons / year.

FORMATS:

Rectangular,

SIZES: (cm)

UK: 40x20, 40x25 ,50x25 & 60x30 including slate and a half to suit

Note: If you are interested in other formats please contact our sales team on 0121 313 1939.



WATER ABSORPTION	< 0,4%
SPECIFIC WEIGHT	2,7 (GR/CM3)
LONGITUDINAL RESISTANCE	> 70 MPA
CARBON CONTENT	<1.4%
THICKNESS	5.6mm – 6mm

Grading

All natural slate should be graded into at least 3 thicknesses prior to being loaded on the roof. To minimize the effect of any variation in shade, slate should be selected from at least 2 crates at a time. As with any natural product, slate is subject to variance and any slates that are identified at the time of grading as potentially problematic should be cut and used as either undereaves or at the ridge.

For further information on fixing specifications please contact our Sales team



Heritage Clay Tiles Ltd

Head Office Denton Wharf Business Park, Unit 1 Mark Lane, Gravesend, Kent, DA12 2QD t: 01474 560278 f: 01474 560318

Regional Office Unit 18 Maybrook Business Park, Maybrook Road, Minworth, West Midlands B76 1AL t: 01213131939 f: 0121 3516552

E: enquiries@heritageclaytiles.co.uk