



Cupa Natural Slate

n55Plus



Cupa Heavy 3 Slates

By Cupa Natural Slate

Detailed description

Natural blue/ black Spanish slates with rough surface, available in five sizes.

Features:

- A heavily textured slate associated with a typical Scottish Highland slate and widely used in conservation projects.
- The slates conform to the requirements of BS EN 12326-1, have a high non-ferrous crystalline pyrites content and are certified for resistance to freeze/ thaw.
- All slates are resistant to common atmospheric chemical and biological agents, and common and extreme (i.e. coastal) pollution.

Product guidance - As Standard

Carbonate content:

0.3%.

Density:

2810 kg/m³.

Thickness:

7–9 mm.

Options

Headlap:

Consult with Cupa Pizarras for details of headlaps in exposed areas and at shallow pitches.

Product specification

Manufacturer

- Name:	Cupa Natural Slate
- Web:	www.cupanaturalslate.co.uk
- Email:	uk.cupa@cupagroup.com
- Tel:	+44 (0)131 225 3111

- Fax: +44 (0)131 220 5463

- Address: CUPA PIZARRAS SA,45 Moray Place,Edinburgh,Scotland EH3 6BQ

Product reference Cupa Heavy 3 Slates

Size
300 x 200 mm
350 x 200 mm
400 x 200 mm
400 x 250 mm
500 x 250 mm

Headlap (minimum)
75 mm
____ mm