

Reuby & Stagg Ltd		Page 1
Dewey House 55 High Street Ringwood BH24 1AE	Rustington Convalescent... Block B1-B4 Reuby & Stagg 10379	
Date 01/10/2018 File 10379 Block B1-B4...	Designed By PJ Checked By	
Micro Drainage		Source Control W.12.4

Summary of Results for 100 year Return Period (+40%)

Half Drain Time : 517 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	3.615	0.165	0.2	6.9	O K
30 min Summer	3.669	0.219	0.2	9.1	O K
60 min Summer	3.725	0.275	0.3	11.5	O K
120 min Summer	3.777	0.327	0.3	13.7	O K
180 min Summer	3.801	0.351	0.3	14.7	O K
240 min Summer	3.812	0.362	0.3	15.1	O K
360 min Summer	3.819	0.369	0.3	15.4	O K
480 min Summer	3.822	0.372	0.3	15.5	O K
600 min Summer	3.822	0.372	0.3	15.6	O K
720 min Summer	3.821	0.371	0.3	15.5	O K
960 min Summer	3.816	0.366	0.3	15.3	O K
1440 min Summer	3.800	0.350	0.3	14.6	O K
2160 min Summer	3.773	0.323	0.3	13.5	O K
2880 min Summer	3.747	0.297	0.3	12.4	O K
4320 min Summer	3.703	0.253	0.3	10.6	O K
5760 min Summer	3.667	0.217	0.2	9.1	O K
7200 min Summer	3.638	0.188	0.2	7.9	O K
8640 min Summer	3.615	0.165	0.2	6.9	O K

Storm Event	Rain (mm/hr)	Time-Peak (mins)
15 min Summer	124.633	19
30 min Summer	83.789	33
60 min Summer	53.779	64
120 min Summer	33.337	122
180 min Summer	24.832	182
240 min Summer	20.006	240
360 min Summer	14.706	338
480 min Summer	11.818	394
600 min Summer	9.966	454
720 min Summer	8.665	520
960 min Summer	6.943	656
1440 min Summer	5.071	936
2160 min Summer	3.696	1344
2880 min Summer	2.949	1756
4320 min Summer	2.142	2512
5760 min Summer	1.705	3288
7200 min Summer	1.427	4032
8640 min Summer	1.235	4760

©1982-2010 Micro Drainage Ltd

Reuby & Stagg Ltd			Page 2		
Dewey House 55 High Street Ringwood BH24 1AE		Rustington Convalesent... Block B1-B4 Reuby & Stagg 10379			
Date 01/10/2018 File 10379 Block B1-B4...		Designed By PJ Checked By			
Micro Drainage		Source Control W.12.4			
Summary of Results for 100 year Return Period (+40%)					
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
10080 min Summer	3.594	0.144	0.2	6.0	O K
15 min Winter	3.634	0.184	0.2	7.7	O K
30 min Winter	3.695	0.245	0.2	10.3	O K
60 min Winter	3.759	0.309	0.3	12.9	O K
120 min Winter	3.818	0.368	0.3	15.4	O K
180 min Winter	3.846	0.396	0.3	16.6	O K
240 min Winter	3.862	0.412	0.3	17.2	O K
360 min Winter	3.880	0.430	0.4	17.6	O K
480 min Winter	3.882	0.432	0.4	17.7	O K
600 min Winter	3.880	0.430	0.4	17.6	O K
720 min Winter	3.876	0.426	0.3	17.6	O K
960 min Winter	3.863	0.413	0.3	17.2	O K
1440 min Winter	3.836	0.386	0.3	16.1	O K
2160 min Winter	3.796	0.346	0.3	14.4	O K
2880 min Winter	3.759	0.309	0.3	12.9	O K
4320 min Winter	3.698	0.248	0.2	10.4	O K
5760 min Winter	3.651	0.201	0.2	8.4	O K
7200 min Winter	3.615	0.165	0.2	6.9	O K
8640 min Winter	3.585	0.135	0.2	5.7	O K
Storm Event	Rain (mm/hr)		Time-Peak (mins)		
10080 min Summer	1.093		5544		
15 min Winter	124.633		19		
30 min Winter	83.789		33		
60 min Winter	53.779		62		
120 min Winter	33.337		120		
180 min Winter	24.832		178		
240 min Winter	20.006		234		
360 min Winter	14.706		344		
480 min Winter	11.818		442		
600 min Winter	9.966		476		
720 min Winter	8.665		550		
960 min Winter	6.943		704		
1440 min Winter	5.071		1008		
2160 min Winter	3.696		1444		
2880 min Winter	2.949		1848		
4320 min Winter	2.142		2676		
5760 min Winter	1.705		3456		
7200 min Winter	1.427		4184		
8640 min Winter	1.235		4936		
©1982-2010 Micro Drainage Ltd					

Reuby & Stagg Ltd		Page 3			
Dewey House 55 High Street Ringwood BH24 1AE	Rustington Convalescent... Block B1-B4 Reuby & Stagg 10379				
Date 01/10/2018 File 10379 Block B1-B4...	Designed By PJ Checked By				
Micro Drainage		Source Control W.12.4			
<u>Summary of Results for 100 year Return Period (+40%)</u>					
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
10080 min Winter	3.562	0.112	0.2	4.7	O K
Storm Event		Rain (mm/hr)	Time-Peak (mins)		
10080 min Winter		1.093	5656		
©1982-2010 Micro Drainage Ltd					

Reuby & Stagg Ltd		Page 4
Dewey House 55 High Street Ringwood BH24 1AE	Rustington Convalescent... Block B1-B4 Reuby & Stagg 10379	
Date 01/10/2018 File 10379 Block B1-B4...	Designed By PJ Checked By	
Micro Drainage	Source Control W.12.4	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.000	Shortest Storm (mins)	15
Ratio R	0.350	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time / Area Diagram

Total Area (ha) 0.000

Time (mins)	Area (ha)
0-4	0.000

©1982-2010 Micro Drainage Ltd

Reuby & Stagg Ltd		Page 5
Dewey House 55 High Street Ringwood BH24 1AE	Rustington Convalescent... Block B1-B4 Reuby & Stagg 10379	
Date 01/10/2018 File 10379 Block B1-B4...	Designed By PJ Checked By	
Micro Drainage	Source Control W.12.4	

Model Details

Storage is Online Cover Level (m) 4.550

Cellular Storage Structure

Invert Level (m) 3.450 Safety Factor 2.0
Infiltration Coefficient Base (m/hr) 0.01662 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.16620

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	44.0	43.0	1.300	0.0	54.8
0.100	44.0	45.6	1.400	0.0	54.8
0.200	44.0	48.2	1.500	0.0	54.8
0.300	44.0	50.9	1.600	0.0	54.8
0.400	44.0	53.5	1.700	0.0	54.8
0.500	0.0	54.8	1.800	0.0	54.8
0.600	0.0	54.8	1.900	0.0	54.8
0.700	0.0	54.8	2.000	0.0	54.8
0.800	0.0	54.8	2.100	0.0	54.8
0.900	0.0	54.8	2.200	0.0	54.8
1.000	0.0	54.8	2.300	0.0	54.8
1.100	0.0	54.8	2.400	0.0	54.8
1.200	0.0	54.8	2.500	0.0	54.8

©1982-2010 Micro Drainage Ltd