

**SMUGGLERS STEPS, THE STREET, WALBERTON,  
ARUNDEL, WEST SUSSEX BN18 0PQ**



---

**RE: PLANNING APPLICATION REF WA/54/13/L;**  
**DECISION DATE 27 JANUARY 2014**

**APPLICATION FOR APPROVAL OF DETAILS**  
**RESERVED BY CONDITION**

1. The section of wall to be rebuilt is in four stepped sections of different heights, and it will be rebuilt to the same heights. Details are shown on the attached photograph.
2. The foundations will be 600mm wide, 250mm deep (concrete strip) with an A393 reinforcing mesh installed.
3. All flints that can be salvaged from the existing wall will be reused; any additional flints required will be supplied by Kevin Hughes of East Dean and will be a mixture of 3-4 inch cobbles and knapped flints.
4. All bricks that can be salvaged from the existing wall will be reused; any additional bricks required (sand-faced, like the existing bricks) will be supplied by Covers.
5. The brick copings on the existing wall will be salvaged and reused.
6. The pointing on the flintwork will be scratched off and brushed to reveal grit to the joints.
7. A one metre square sample panel is now available on site for inspection.

Thank you.

7 April 2014.