


Arch Associates Limited		Page 1
Town House St Geroge's Square Bishops Waltham Southampton SO32 1AF	DEANS YARD, ORCHARD WAY FONTWELL, ARUNDEL, WEST SUSSEX PERMEABLE PAVING 0.25M DEPTH	
Date 18/04/2018	Designed by SH	
File AAL057 - PERMEABLE PAVI...	Checked by AWR	
XP Solutions		Source Control 2016.1


Summary of Results for 100 year Return Period (+40%)

Half Drain Time : 431 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
15 min Summer	32.522	0.072	0.1	1.8	O K
30 min Summer	32.552	0.102	0.1	2.6	O K
60 min Summer	32.583	0.133	0.1	3.5	O K
120 min Summer	32.612	0.162	0.1	4.3	O K
180 min Summer	32.625	0.175	0.1	4.6	O K
240 min Summer	32.631	0.181	0.1	4.8	O K
360 min Summer	32.636	0.186	0.1	4.9	O K
480 min Summer	32.638	0.188	0.1	5.0	O K
600 min Summer	32.638	0.188	0.1	4.9	O K
720 min Summer	32.636	0.186	0.1	4.9	O K
960 min Summer	32.632	0.182	0.1	4.8	O K
1440 min Summer	32.618	0.168	0.1	4.4	O K
2160 min Summer	32.595	0.145	0.1	3.8	O K
2880 min Summer	32.574	0.124	0.1	3.2	O K
4320 min Summer	32.539	0.089	0.1	2.3	O K
5760 min Summer	32.514	0.064	0.1	1.6	O K
7200 min Summer	32.501	0.051	0.1	1.2	O K
8640 min Summer	32.495	0.045	0.1	1.1	O K
10080 min Summer	32.490	0.040	0.1	1.0	O K
15 min Winter	32.533	0.083	0.1	2.1	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
15 min Summer	125.402	0.0	18
30 min Summer	85.647	0.0	33
60 min Summer	55.837	0.0	62
120 min Summer	35.054	0.0	122
180 min Summer	26.228	0.0	182
240 min Summer	21.215	0.0	240
360 min Summer	15.744	0.0	338
480 min Summer	12.718	0.0	394
600 min Summer	10.766	0.0	458
720 min Summer	9.390	0.0	520
960 min Summer	7.559	0.0	656
1440 min Summer	5.556	0.0	926
2160 min Summer	4.073	0.0	1324
2880 min Summer	3.263	0.0	1704
4320 min Summer	2.381	0.0	2424
5760 min Summer	1.907	0.0	3112
7200 min Summer	1.606	0.0	3744
8640 min Summer	1.395	0.0	4416
10080 min Summer	1.239	0.0	5152
15 min Winter	125.402	0.0	18

©1982-2016 XP Solutions

Arch Associates Limited				Page 2	
Town House St Geroge's Square		DEANS YARD, ORCHARD WAY			
Bishops Waltham		FONTWELL, ARUNDEL, WEST SUSSEX			
Southampton SO32 1AF		PERMEABLE PAVING 0.25M DEPTH			
Date 18/04/2018		Designed by SH			
File AAL057 - PERMEABLE PAVI...		Checked by AWR			
XP Solutions		Source Control 2016.1			
Summary of Results for 100 year Return Period (+40%)					
Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
30 min Winter	32.566	0.116	0.1	3.0	O K
60 min Winter	32.601	0.151	0.1	4.0	O K
120 min Winter	32.635	0.185	0.1	4.9	O K
180 min Winter	32.650	0.200	0.1	5.3	O K
240 min Winter	32.658	0.208	0.1	5.5	O K
360 min Winter	32.666	0.216	0.1	5.7	O K
480 min Winter	32.667	0.217	0.1	5.8	O K
600 min Winter	32.665	0.215	0.1	5.7	O K
720 min Winter	32.663	0.213	0.1	5.6	O K
960 min Winter	32.655	0.205	0.1	5.4	O K
1440 min Winter	32.634	0.184	0.1	4.9	O K
2160 min Winter	32.599	0.149	0.1	3.9	O K
2880 min Winter	32.566	0.116	0.1	3.0	O K
4320 min Winter	32.516	0.066	0.1	1.7	O K
5760 min Winter	32.496	0.046	0.1	1.1	O K
7200 min Winter	32.489	0.039	0.1	0.9	O K
8640 min Winter	32.484	0.034	0.1	0.8	O K
10080 min Winter	32.481	0.031	0.1	0.7	O K
Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)		
30 min Winter	85.647	0.0	33		
60 min Winter	55.837	0.0	62		
120 min Winter	35.054	0.0	120		
180 min Winter	26.228	0.0	178		
240 min Winter	21.215	0.0	234		
360 min Winter	15.744	0.0	346		
480 min Winter	12.718	0.0	450		
600 min Winter	10.766	0.0	490		
720 min Winter	9.390	0.0	562		
960 min Winter	7.559	0.0	714		
1440 min Winter	5.556	0.0	1012		
2160 min Winter	4.073	0.0	1428		
2880 min Winter	3.263	0.0	1816		
4320 min Winter	2.381	0.0	2468		
5760 min Winter	1.907	0.0	3056		
7200 min Winter	1.606	0.0	3752		
8640 min Winter	1.395	0.0	4496		
10080 min Winter	1.239	0.0	5248		
©1982-2016 XP Solutions					

Arch Associates Limited		Page 3
Town House St Geroge's Square Bishops Waltham Southampton SO32 1AF	DEANS YARD, ORCHARD WAY FONTWELL, ARUNDEL, WEST SUSSEX PERMEABLE PAVING 0.25M DEPTH	
Date 18/04/2018	Designed by SH	
File AAL057 - PERMEABLE PAVI...	Checked by AWR	
XP Solutions		Source Control 2016.1

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.700	Shortest Storm (mins)	15
Ratio R	0.318	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time Area Diagram

Total Area (ha) 0.010

Time (mins)	Area
From: To:	(ha)

0	4	0.010
---	---	-------

Arch Associates Limited		Page 4
Town House St Geroge's Square Bishops Waltham Southampton SO32 1AF	DEANS YARD, ORCHARD WAY FONTWELL, ARUNDEL, WEST SUSSEX PERMEABLE PAVING 0.25M DEPTH	
Date 18/04/2018	Designed by SH	
File AAL057 - PERMEABLE PAVI...	Checked by AWR	
XP Solutions	Source Control 2016.1	

Model Details

Storage is Online Cover Level (m) 33.000

Porous Car Park Structure

Infiltration Coefficient Base (m/hr)	0.00900	Width (m)	9.5
Membrane Percolation (mm/hr)	1000	Length (m)	9.5
Max Percolation (l/s)	25.1	Slope (1:X)	1000.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	32.450	Cap Volume Depth (m)	0.250