

Summary of Results for 100 year Return Period (+50%)

Half Drain Time : 1417 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
15 min Summer	26.753	0.353	0.5	33.9	0 K
30 min Summer	26.866	0.466	0.5	45.3	0 K
60 min Summer	26.987	0.587	0.6	57.6	0 K
120 min Summer	27.109	0.709	0.6	70.0	0 K
180 min Summer	27.176	0.776	0.6	76.7	0 K
240 min Summer	27.217	0.817	0.6	80.8	0 K
360 min Summer	27.270	0.870	0.7	86.2	0 K
480 min Summer	27.301	0.901	0.7	89.3	0 K
600 min Summer	27.318	0.918	0.7	91.1	0 K
720 min Summer	27.328	0.928	0.7	92.1	0 K
960 min Summer	27.330	0.930	0.7	92.3	0 K
1440 min Summer	27.313	0.913	0.7	90.5	0 K
2160 min Summer	27.277	0.877	0.7	87.0	0 K
2880 min Summer	27.240	0.840	0.6	83.2	0 K
4320 min Summer	27.172	0.772	0.6	76.3	0 K
5760 min Summer	27.110	0.710	0.6	70.0	0 K
7200 min Summer	27.051	0.651	0.6	64.1	0 K
8640 min Summer	26.999	0.599	0.6	58.8	0 K
10080 min Summer	26.949	0.549	0.6	53.8	0 K
15 min Winter	26.793	0.393	0.5	38.0	0 K
30 min Winter	26.920	0.520	0.5	50.9	0 K
60 min Winter	27.057	0.657	0.6	64.7	0 K
120 min Winter	27.196	0.796	0.6	78.8	0 K
180 min Winter	27.273	0.873	0.7	86.5	0 K
240 min Winter	27.321	0.921	0.7	91.3	0 K
360 min Winter	27.384	0.984	0.7	97.7	0 K
480 min Winter	27.423	1.023	0.7	101.7	0 K
600 min Winter	27.447	1.047	0.7	104.1	0 K
720 min Winter	27.462	1.062	0.7	105.6	0 K
960 min Winter	27.474	1.074	0.7	106.8	0 K
1440 min Winter	27.459	1.059	0.7	105.3	0 K
2160 min Winter	27.416	1.016	0.7	101.0	0 K
2880 min Winter	27.367	0.967	0.7	96.0	0 K
4320 min Winter	27.268	0.868	0.6	86.0	0 K
5760 min Winter	27.175	0.775	0.6	76.6	0 K
7200 min Winter	27.089	0.689	0.6	68.0	0 K
8640 min Winter	27.012	0.612	0.6	60.1	0 K
10080 min Winter	26.941	0.541	0.6	52.9	0 K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
15 min Summer	135.580	0.0	19
30 min Summer	91.216	0.0	34
60 min Summer	58.567	0.0	64
120 min Summer	36.294	0.0	124
180 min Summer	27.017	0.0	182
240 min Summer	21.749	0.0	242
360 min Summer	16.006	0.0	362
480 min Summer	12.864	0.0	482
600 min Summer	10.849	0.0	602
720 min Summer	9.435	0.0	720
960 min Summer	7.561	0.0	960
1440 min Summer	5.523	0.0	1196
2160 min Summer	4.026	0.0	1576
2880 min Summer	3.213	0.0	1988
4320 min Summer	2.333	0.0	2812
5760 min Summer	1.857	0.0	3632
7200 min Summer	1.555	0.0	4464
8640 min Summer	1.347	0.0	5264
10080 min Summer	1.192	0.0	6048
15 min Winter	135.580	0.0	19
30 min Winter	91.216	0.0	33
60 min Winter	58.567	0.0	64
120 min Winter	36.294	0.0	122
180 min Winter	27.017	0.0	180
240 min Winter	21.749	0.0	240
360 min Winter	16.006	0.0	356
480 min Winter	12.864	0.0	472
600 min Winter	10.849	0.0	588
720 min Winter	9.435	0.0	700
960 min Winter	7.561	0.0	924
1440 min Winter	5.523	0.0	1340
2160 min Winter	4.026	0.0	1668
2880 min Winter	3.213	0.0	2132
4320 min Winter	2.333	0.0	3028
5760 min Winter	1.857	0.0	3920
7200 min Winter	1.555	0.0	4760
8640 min Winter	1.347	0.0	5616
10080 min Winter	1.192	0.0	6448

Rainfall Details

Rainfall Model	FSR	Ratio R	0.348	Cv (Winter)	0.840
Return Period (years)	100	Summer Storms	Yes	Shortest Storm (mins)	15
Region	England and Wales	Winter Storms	Yes	Longest Storm (mins)	10080
M5-60 (mm)	19.300	Cv (Summer)	0.750	Climate Change %	+50

Time Area Diagram

Total Area (ha) 0.135

Time (mins)		Area
From:	To:	(ha)
0	4	0.135

Rogers Cory Ptn Ltd		Page 3
The Old School Old School Road Hook RG27 9NJ	Fontwell Eastergate Area 18 Soakaway	
Date 20/08/2020 16:27 File AREA 18.SRCX	Designed by Terry Seymour Checked by Terry Seymour	
Micro Drainage	Source Control 2017.1.2	

Model Details

Storage is Online Cover Level (m) 28.000

Trench Soakaway Structure

Infiltration Coefficient Base (m/hr)	0.13600	Invert Level (m)	26.400	Cap Volume Depth (m)	1.200
Infiltration Coefficient Side (m/hr)	0.13600	Trench Width (m)	3.0	Cap Infiltration Depth (m)	1.200
Safety Factor	10.0	Trench Length (m)	35.5		
Porosity	0.95	Slope (1:X)	1000.0		