

Summary of Results for 10 year Return Period (+50%)

Half Drain Time : 1223 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
15 min Summer	26.122	0.272	0.3	18.9	0 K
30 min Summer	26.208	0.358	0.3	24.8	0 K
60 min Summer	26.299	0.449	0.3	31.2	0 K
120 min Summer	26.395	0.545	0.4	37.8	0 K
180 min Summer	26.452	0.602	0.4	41.7	0 K
240 min Summer	26.490	0.640	0.4	44.4	0 K
360 min Summer	26.540	0.690	0.4	47.8	0 K
480 min Summer	26.570	0.720	0.4	49.9	0 K
600 min Summer	26.589	0.739	0.4	51.2	0 K
720 min Summer	26.600	0.750	0.4	52.0	0 K
960 min Summer	26.610	0.760	0.5	52.7	0 K
1440 min Summer	26.618	0.768	0.5	53.3	0 K
2160 min Summer	26.613	0.763	0.5	52.9	0 K
2880 min Summer	26.598	0.748	0.4	51.9	0 K
4320 min Summer	26.559	0.709	0.4	49.1	0 K
5760 min Summer	26.518	0.668	0.4	46.3	0 K
7200 min Summer	26.480	0.630	0.4	43.7	0 K
8640 min Summer	26.444	0.594	0.4	41.2	0 K
10080 min Summer	26.411	0.561	0.4	38.9	0 K
15 min Winter	26.155	0.305	0.3	21.2	0 K
30 min Winter	26.251	0.401	0.3	27.8	0 K
60 min Winter	26.354	0.504	0.4	35.0	0 K
120 min Winter	26.463	0.613	0.4	42.5	0 K
180 min Winter	26.527	0.677	0.4	47.0	0 K
240 min Winter	26.571	0.721	0.4	50.0	0 K
360 min Winter	26.630	0.780	0.5	54.1	0 K
480 min Winter	26.666	0.816	0.5	56.6	0 K
600 min Winter	26.691	0.841	0.5	58.3	0 K
720 min Winter	26.706	0.856	0.5	59.4	0 K
960 min Winter	26.722	0.872	0.5	60.5	0 K
1440 min Winter	26.727	0.877	0.5	60.8	0 K
2160 min Winter	26.718	0.868	0.5	60.2	0 K
2880 min Winter	26.693	0.843	0.5	58.5	0 K
4320 min Winter	26.631	0.781	0.5	54.2	0 K
5760 min Winter	26.568	0.718	0.4	49.8	0 K
7200 min Winter	26.510	0.660	0.4	45.8	0 K
8640 min Winter	26.457	0.607	0.4	42.1	0 K
10080 min Winter	26.408	0.558	0.4	38.7	0 K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
15 min Summer	82.824	0.0	19
30 min Summer	54.698	0.0	34
60 min Summer	34.733	0.0	64
120 min Summer	21.518	0.0	124
180 min Summer	16.130	0.0	182
240 min Summer	13.106	0.0	242
360 min Summer	9.767	0.0	362
480 min Summer	7.922	0.0	482
600 min Summer	6.730	0.0	600
720 min Summer	5.890	0.0	720
960 min Summer	4.770	0.0	860
1440 min Summer	3.540	0.0	1110
2160 min Summer	2.625	0.0	1512
2880 min Summer	2.123	0.0	1928
4320 min Summer	1.572	0.0	2764
5760 min Summer	1.270	0.0	3576
7200 min Summer	1.076	0.0	4392
8640 min Summer	0.940	0.0	5184
10080 min Summer	0.839	0.0	5952
15 min Winter	82.824	0.0	19
30 min Winter	54.698	0.0	33
60 min Winter	34.733	0.0	62
120 min Winter	21.518	0.0	122
180 min Winter	16.130	0.0	180
240 min Winter	13.106	0.0	238
360 min Winter	9.767	0.0	354
480 min Winter	7.922	0.0	470
600 min Winter	6.730	0.0	584
720 min Winter	5.890	0.0	694
960 min Winter	4.770	0.0	912
1440 min Winter	3.540	0.0	1152
2160 min Winter	2.625	0.0	1604
2880 min Winter	2.123	0.0	2076
4320 min Winter	1.572	0.0	2980
5760 min Winter	1.270	0.0	3856
7200 min Winter	1.076	0.0	4680
8640 min Winter	0.940	0.0	5528
10080 min Winter	0.839	0.0	6344

Rogers Cory Ptn Ltd		Page 2
The Old School Old School Road Hook RG27 9NJ	Fontwell Eastergate Area 22 Soakaway	
Date 03/08/2020 22:00 File AREA 22.SRCX	Designed by Terry Seymour Checked by Terry Seymor	
Micro Drainage	Source Control 2017.1.2	

Rainfall Details

Rainfall Model	FSR	Ratio R	0.348	Cv (Winter)	0.840
Return Period (years)	10	Summer Storms	Yes	Shortest Storm (mins)	15
Region	England and Wales	Winter Storms	Yes	Longest Storm (mins)	10080
M5-60 (mm)	19.300	Cv (Summer)	0.750	Climate Change %	+50

Time Area Diagram

Total Area (ha) 0.123

Time (mins)		Area
From:	To:	(ha)
0	4	0.123

Model Details

Storage is Online Cover Level (m) 27.750

Complex Structure

Cellular Storage

Invert Level (m) 25.850 Infiltration Coefficient Side (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	50.0	0.0	1.600	50.0	0.0	1.601	0.0	0.0

Trench Soakaway

Infiltration Coefficient Base (m/hr) 0.27400 Invert Level (m) 25.850 Cap Volume Depth (m) 1.600
Infiltration Coefficient Side (m/hr) 0.27400 Trench Width (m) 1.0 Cap Infiltration Depth (m) 1.600
Safety Factor 10.0 Trench Length (m) 23.0
Porosity 0.95 Slope (1:X) 0.0