



DO NOT SCALE OFF THIS DRAWING

GENERAL NOTES:

- All dimensions to be checked on site. All details and dimensions relating to sub-Contractors work must be checked and agreed between the sub-Contractor or supplier and the general Contractor
- This drawing is to be read in conjunction with all relevant Architects and Engineer's drawings and specification.
- The main Contractor is responsible for ensuring the stability of the structure whilst the works are in progress.
- Any information given regarding existing underground services is given in good faith after consultation with the relevant authority. No liability is accepted by the Consultant and the main Contractor is responsible for obtaining and checking all information and taking due care and attention whilst undertaking the work.

CDM 2015 RESIDUAL RISKS

- All areas of live traffic and pedestrian movements shall be subject to appropriate traffic management barriers and signs.
- Access points onto live public highway.
- Unauthorised access to the site must be prevented at all times
- Existing road drainage to be maintained.
- Be aware of possible live drainage flows and foul effluent during construction. The Contractor shall assess and implement a safe working system and equipment (PPE) as necessary.

The above residual risks are for non-standard hazards. It is assumed that a competent contractor familiar with the construction of this type of work will be appointed who will be aware of the standard hazards.

DRAINAGE KEY

- Site Boundary
- Self Serving Permeable Paving with 300mm Deep 30% Voided Subbase
- Self Serving Permeable Paving with 300mm Deep 30% Voided Subbase - Unfilled to Allow Soaking to Ground - Invert of Subbase more than 1 m from Highest Recorded GW Level
- Attenuation Basin - NTS
- Rain Gardens with Fully Perforated Pipe Running at Invert
- Rain Gardens with Fully Perforated Pipe Running at Invert/unfilled to Allow Soaking to Ground - Invert of Rain Garden more than 1 m from Highest Recorded GW Level
- Proposed Gradient and Base level at Invert of Permeable Paving
- Location of Soakage Testing
- Location of Groundwater Monitoring

P01 ISSUED FOR INFORMATION	MH	MK	SB	07/08/2026	
P02 ISOAKAGE TESTING ADDED	MH	MK	SB	14/08/2026	
Rev	Comment	By	Chkd	Appr	Date
Revision History					

INFORMATION

BELLWAY WESSEX

robert west
proesgroup

1 Paris Garden
London
SE1 1ND
t: 0203 773 7880
www.robertwest.co.uk

Project
**WANDLEYS LANE
FONTWELL**

Drawing Title
**SKETCH
GROUNDWATER LEVELS**

RWCL Internal Register reference: 5988-005 Scales @ A1

5988-005-SK03-P02

© Robert West Consulting 2019. All rights reserved.