



Specialising in flint work
(new works and repairs)

Paul Grantham
12 Dairy lane
Walberton
Arundel
West Sussex
BN18 0PT

Ken Tooth
Little Croft
Walberton

Estimate date: 19th June 2013
Email address: PMGflintwork@googlemail.com

Description of work:

To take down approximately 12 meters of flint and brick garden wall. The wall runs approximately 1.2 meters high for 3.5 meters in length.

Then is raised to 2.1 meters high for the remaining 8.5 meters of wall.

All brick copings will be salvaged from wall. All flints will be salvaged for reuse on wall. More flints will be supplied to replace sections of brickwork added to existing wall.

The existing footings will be dug out and a new concrete footing with reinforcing put in place.

The wall will be rebuilt in coursed flintwork with brick quoins either end and in the middle of the wall.

The wall will be rebuilt independent of the garage.

It will be finished with a brick band course capped with a brick coping.

The wall will be rebuilt to match as close as possible to the existing flintwall.

All work will be carried out using lime mortar.

All rubble will be removed from site and left tidy.

Total Labour and Materials

£8100

Tarmac drive repairs to neighbours property

Total labour and materials

£480

Paul Grantham Contact

