

Attenuation tanks

Isolating valve

Filter

Upper orifice plate

Lower orifice plate

To North outfall

Upper OP height (h)

Lower orifice plate details:-
Diameter 23mm
Throughput 1.0 l/s

Upper orifice plate details:-
Diameter 39mm
Throughput 3.8 l/s
Height (h) 1.9m

Fleurie Nursery Lake Lane Barnham North Orifice Plate
Date: 28.01.26 Scale NTS Drawn AM Revisions
Hennock International Ltd Church Road Hennock Newton Abbot Devon TQ13 9QE