

Plants are to be carefully packaged and transported in accordance with the JCLI plant handling code. All bare root plants are to be root dipped in hydrated polyacrylamide gel, e.g. Broadleaf P4 to manufacturers recommendations immediately after lifting and transported to the site with the gel intact. The use of the gel does not excuse the landscape contractor from complying with the handling code.

Planting beds shall be prepared by cultivation to a minimum depth of 150mm. All weed or plant debris to be removed. Planting pits are to be dug within the prepared soil to accommodate all roots with minimum 50 mm spare capacity to allow for backfilling with soil. Backfill shall be settled around the plants to avoid air pockets and then well firmed. All plants are to be planted to their original depth, as indicated by nursery marks on the main stem and the finished levels shall marry in with the rest of the bed.

Hedges to consist of random mix of species to be planted in staggered rows 500 mm apart at spacing of 500 mm

All beds and hedging to be finished with 50 mm settled depth of composted wood chip mulch after completion of planting.

Feathered trees to be supported by 1.8M 50mm square treated softwood stake to height above ground and tied with toms belling and block.


Standard trees to be supported in similar manner using 75mm round stake to 1.2M height.

All planting areas are to be kept weed free prior to practical completion, and during the 12 months maintenance period. Weeding shall be undertaken with glyphosate or such other herbicide approved by the landscape architect as appropriate for the task. Applications of herbicide shall be undertaken on calm dry days with a shielded sprayer nozzle and application is to be made with great care so that no herbicide is allowed to come into contact with non weed species. Application rates are to be to the manufacturers recommendations.

The developer is to ensure that ongoing maintenance and replacement of any plant failures continues for a period of 5 years after planting, such that the plant numbers shown on this drawing are present for inspection at that time.

Planting of **bare root plants** is a seasonal activity which is subject to suitable weather conditions, and is to take place between November and March in the season immediately following the completion of the development.

H Schwegler woodcrete hedgehog dome
B BR Bat access brick see NHBS ref 197697
colour to suit. On south elevations
NB 2F Schwegler Bat Box (General Purpose)
NB 1N Schwegler Deep Nest Box
Installed in accordance with manufacturers recommendations
LP Log piles min 2x2M2



Metres

0 1 2 3 4 5 6 7 8 9 10



DAVID HARES
LANDSCAPE ARCHITECTURE