


From: Sue Howell <Sue.Howell@arun.gov.uk>
Sent: 03 December 2020 16:12
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Anita Gardner <Anita.Gardner@arun.gov.uk>
Subject: RE: Planning Consultation on: WA/68/20/OUT

Response to Planning Application

From: Arun District Council Leisure & Greenspace

Date: 03/12/2020

Application ref: WA/68/20/OUT

Description: Outline application with all matters reserved, other than means of access, for the construction of up to 155 No. dwellings (30% affordable homes) & amendment to boundary of garden land to serve adjoining property. This application affects the character & appearance of the Walberton Village Conservation Area, may affect the setting of listed buildings & is a Departure from the Development Plan.

Location: Land west of Tye Lane Walberton

Determining Authority: Arun DC

Summary recommendation: I would have no landscape objection to the outline proposals as presented based on the Concept Masterplan submitted with this application. A landscape led development in this location would be advised in order to blend this development proposal into the character of this local area.

Comments

Relevant landscape designations

This proposed development site is agricultural, located north west of Walberton, west of Tye Lane.

There are no Conservation areas or Listed Buildings, Special Protection Area (SPA), Ramsar or Site of Specific Scientific Interest immediately associated with this site, however this application affects the character & appearance of the Walberton Village Conservation Area, may affect the setting of listed buildings.

South Downs National Park to the north

Response

This proposal for this site is for residential development of up to 155no dwellings.

The site is largely a rectangular shaped plot with existing residential to the south and west and proposed residential to the east of the adjacent Tye Lane.

The information provided within Concept Masterplan 01 Dwg CMP- Rev P4 indicates a well-spaced site with good areas of POS both centrally and surrounding the areas of housing and a larger open area indicated to the south of the site. The indicative location of the areas of POS would appear to cater for the existing trees and hedges along the watercourse and those located within the site. Excluding the existing trees to the periphery of the site there would not appear to be a significant canopy cover in general with the exception of a few intermittent trees worthy of retention which must be protected and retained.

As there are trees, areas of hedgerow and vegetation associated both within and adjoining this site, consultation would need to be made with Arun District Councils Tree Officer re any works in conjunction with these.

A watercourse is noted which runs through the site, following largely the location of existing trees.

This site does not form part of any strategic identified for development in ADCs adopted Local Plan 2011-2031 (July 2018) It would therefore be assumed that **CIL contributions would be sought** accordingly, these will need to include contributions towards playing pitches, sport, leisure, pools, halls and ancillary facilities as set out in ADC SPD Open Space, Playing Pitches, Indoor and Built Sports Facilities January 2020.

The design of the site should promote a high-quality development that respects, maintains and enhances the local landscape character. This new development should consider the character and distinctiveness of the area reflecting local design characteristics where possible and its setting with the surrounding countryside and rural fringe. All nature conservation features within the development site including existing habitats, trees, hedges, watercourses and other features should be incorporated into the site design and protected from change.

Quality, well-designed Public Open Space will be fundamental to any proposal submission, these will need to accord with Arun District Councils OS SPD January 2020. There would be requirement for confirmation of the areas of public open space being proposed with this development, and clarification re quantum. The Concept Masterplan indicates where the areas of POS are being proposed for this development which is

good to see. Our SPD January 2020 would require 12,788m² as a minimum of well connected, usable, quality POS provision within this development.

POS areas will need to connect within and beyond the development site promoting and enhancing footpath and cycle links and their use within the wider area. Consideration should be made to the siting of open space and buffer areas and their use in softening and integrating the proposals with any existing residential development on this fringe. POS should be considered not only for any larger open character areas but also any perimeter buffer areas. These would be required to enhance the setting, to create sense of place, desirable living areas and distinctiveness within the plot areas. A design intent for tree planting to retain and enhance woodland within the site, and not just limit it to the boundaries would be encouraged. Planting within the boundaries will improve the species composition and diversify the age structure, woodland belt deepening will improve screening properties and to neighbouring dwellings.

This development will trigger the requirement for play in the form of onsite LAPs LEAP/NEAP provision, which would need to be suitable for location in material choice and play experience offer. Off-site allotment contribution would also be triggered from this development.

A detailed landscape scheme will be required to be submitted in plan form and detail planting species, quantities, planting densities and size at time of planting.

SuDS Policy W DM3 of the Arun Local Plan requires development to integrate SuDS into the overall design of the development. The primary purpose of SuDS is to minimise the impact of urban development on the water environment, reduce flood risk and provide habitats for wildlife. SuDS should increase the levels of water capture and storage. It is essential that SuDS do not impact on the usable levels of public open space whilst providing benefit in the correct capacity within the development and should not be included in the 'usable open space calculations'

Impact

The potential impact on the location would require that Landscaping be provided as mitigation towards screening and softening of the development. Consideration will be required re the access into the site and the impact this may have on existing trees and hedges on any boundaries. The interface this site has in its semi-rural location and interface with existing trees should require that due consideration of the design ensures the existing trees are given protection and space to mature.

Mitigation/requirements

Existing green vegetation is evident along the boundaries of this site and further enhancement and improvement would be required. A robust and detailed landscape scheme will be required within these proposals for all areas of development and POS to increase biodiversity net gain and habitat within this rural fringe site. Opportunities to enhance the landscape in association with any development of the site, by implementing an ambitious soft landscape and tree planting programme would be sought. A detailed landscape scheme which would incorporate a good selection of native tree species in conjunction with suitable ornamentals would be required.

All greenspaces should be considered and valued and their connection for biodiversity and habitat explored. Tree specification should be at a size which allows instant impact, but which will establish and mature as the site develops.

There is a requirement for any scheme, in accordance with policy to be of High-Quality Design. The emerging landscape design aims should be:

- To design and implement a scheme that reflects and incorporates elements of its surroundings and enhances the atmosphere of local distinctiveness.

- To create a visually pleasing and interesting landscape for owners, employees and visitors to the development.
- To enhance the landscape quality of the site when viewed from the surrounding area.
- To provide a planting scheme that includes native species to blend with the surrounding location, enhance biodiversity and create enhanced wildlife corridor opportunity.
- To provide a sense of flow and cohesion between the different elements of the landscape, buildings, open areas and surrounding environment

A clear indication of the proposed future management of the open space areas will be required to be submitted. A clear directive of responsibility should be set out explaining how the differing typologies will be maintained ie responsibility of play and public realm areas.

Recommendation/Conclusion

I would have no landscape objection to the outline proposals as presented based on the Concept Masterplan submitted with this application. A landscape led development in this location would be advised in order to blend this development proposal into the character of this local area.

Sue Howell

Leisure and Landscape Officer,
Greenspace + Emergency Planning

T: 01903 737943

E: sue.howell@arun.gov.uk



Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 13 October 2020 16:06

To: Tree Landscape [REDACTED]

Subject: Planning Consultation on: WA/68/20/OUT

To: **Parks and Landscapes**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town & country Planning (Development Management Procedure) (England) Order 2015 - Article 5

Outline Consent

Application No: WA/68/20/OUT
Registered: 7th October 2020
Site Address: Land west of Tye Lane Walberton
Grid Reference: 496879 106315
Description of Works: Outline application with all matters reserved, other than means of access, for the construction of up to 155 No. dwellings (30% affordable homes) & amendment to boundary of garden land to serve adjoining property. This application affects the character & appearance of the Walberton Village Conservation Area, may affect the setting of listed buildings & is a Departure from the Development Plan.

The Council have received the above application.

[Click here to view the application details](#)

Should you have any comments to make, these should be sent by replying to this email by 12th November 2020 . You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website <https://www.arun.gov.uk/development-plan> as can the the leaflet how to respond to planning applications <https://www.arun.gov.uk/planning-application-comments> which deals with material planning considerations.

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://www.planningportal.co.uk/info/200207/appeals> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Mrs A Gardner

Planning Officer- Arun District Council

Telephone: 01903 737529

Email: Anita.Gardner@arun.gov.uk

