



FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

REFER TO CSA/3823/105

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

MANSER ROAD

LEGEND

APPLICATION SITE

Planting Proposals

TREE PLANTING
Various sizes

AMENITY GRASS SEEDING/TURFING

ORNAMENTAL SHRUBS

HEDGEROW

NB: For details of planting refer to CSA/3823/107-110

Hardworks

BITUMINOUS MACADAM SURFACE - to vehicular areas /

to engineers details.

BITUMINOUS MACADAM SURFACE - to footpaths/cycleways

to engineers specification.

POROUS CONCRETE BLOCK PAVING - to shared surfaces /

parking courts.

Porofix porous block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, ribbed block, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required).

POROUS CONCRETE BLOCK PAVING - to private drives.

Porofix porous block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, ribbed block, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required).

CONCRETE BLOCK PAVING - to shared surfaces / parking

courts.

Keyhole block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required).

CONCRETE BLOCK PAVING - to private drives.

Keyhole block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required).

CONCRETE BLOCK PAVING - to build-outs and to demarcate

parking bays.

Keyhole block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required).

CONCRETE SETT PAVING - to ramps.

Conservation concrete block paving by Marshalls Ltd, 100 x 100

x 100mm, laid black bond, natural finish, silver grey colour.

NB: Kerts to be 'Conservation' kerts (250mm x 140mm) by

Marshalls Ltd, silver grey colour, laid flush with kerb side of kerb

strip.

CONCRETE PAVING SLABS - to foot paths

Porofix porous block paving by Marshalls Ltd, 400

x 400 x 50mm thick, buff colour, natural finish, laid black bond.

CONSERVATION KERB - to transition between surface

materials.

Joint flush to demarc transition between surfaces, supplied by

Marshalls Ltd, 145 x 255mm, silver grey.

NB: In some locations an upstand is specified on the drawing.

Boundary Treatment

BRICK WALL -

1800mm high, 215mm wide brick wall, brick on edge coping,

incorporating drainage lines, brick type to match adjacent

dwellings.

DRYBRICK WALL -

1800mm high, 215mm wide brick wall, brick on edge coping,

incorporating drainage lines, brick type to match adjacent

dwellings. 1000 x 442 x 442mm brick pair at ends to match

adjacent.

CLOSE BOARD FENCING -

1800mm high close-boarded timber fence, treated softwood

(min. 15yr life span).

REAR ACCESS GATE -

Treated softwood timber gate (min. 15yr life span),

incorporating steel hinges and hook latch and padlock bar.

ESTATE RAILING -

1200mm high steel estate railing in black.

SQUARE TIMBER ROLLER -

175 x 175 x 900mm long square timber roller

by Jackson Fencing Ltd, treated 40mm

above ground, or equal and approved.

Notes:

1) All surface materials are to be installed as specified of equal or approved

specification.

2) All kerbs to bituminous macadam areas to be British Standard concrete kerbs (by

Marshalls or equal and approved) with chamfer to kerb face to engineers

specification (internally 100mm) or laid flush where different paving types meet

(eg. driveway).

3) All block paved shared surfaces to receive York Small unit kerbs by Marshalls

or similar, colour to engineers details (internally 250mm square).

4) Visitor and parking court bays demarcated with a soldier course of natural colour

'Keyhole'.

5) The extent and specification of porous paving surfaces is subject to detailed

drainage design.

6) For earth Landscapes Proposals refer to CSA/3823/101-103.

7) For Public Open Space Proposals refer to CSA/3823/107-110.

B 11/02/19 (AM) Updated to latest Site Layout

A 18/07/19 (LE) Amended to suit latest Site Layout

Rev Date By Description

CSA

environmental

Dolvis Barns, High Street,

Ashwell, Hertfordshire SG7 5NT

T 01442 743447

E ashwell@csaenvironmental.co.uk

W csaenvironmental.co.uk

Project Land East of Tye Lane, Walberton

Title Soft Landscape Proposals

Sheet 3 of 3

Client Linden Homes

Scale 1:250 @ A0

Drawn LR

Date October 2018

Checked GC

Drawing No CSA/3823/106

Rev B