



FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

REFER TO CSA/3823/105

REFER TO CSA/3823/105

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

FOR PUBLIC OPEN SPACE
PROPOSALS REFER TO
CSA/3823/107-110

LEGEND

APPLICATION SITE

Planting Proposals

TREE PLANTING
- Various sizes

AMENITY GRASS SEEDING/TURFING

ORNAMENTAL SHRUBS

HEDGEROW

NB: For details of planting refer to CSA/3823/107-110

Hardworks

BITUMINOUS MACADAM SURFACE - to vehicular areas /

to engineering details

BITUMINOUS MACADAM SURFACE - to footpaths/cycleways

to engineering specification

POROUS CONCRETE BLOCK PAVING - to shared surfaces /

parking bays

Private porous block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, ribbed block, with smooth finish, chamfered.

Chamfered, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required)

POROUS CONCRETE BLOCK PAVING - to private drives

Private porous block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, ribbed block, with smooth finish, chamfered.

Blonde, laid herringbone pattern, 200mm soldier course to

peripheral edge (where required)

CONCRETE BLOCK PAVING - to shared surfaces / parking

bays

'Keyhole' block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered. Blonde, laid

herringbone pattern, 200mm soldier course to peripheral edge

(where required)

CONCRETE BLOCK PAVING - to private drives

'Keyhole' block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered. Blonde, laid

herringbone pattern, 200mm soldier course to peripheral edge

(where required)

CONCRETE BLOCK PAVING - to build-outs and to demarcate

parking bays

'Keyhole' block paving by Marshalls Ltd, concrete block, 200 x

100 x 40mm, with smooth finish, chamfered. Blonde, laid

herringbone pattern, 200mm soldier course to peripheral edge

(where required)

CONCRETE SETT PAVING - to ramps

'Conservator' concrete block paving by Marshalls Ltd, 100 x 100

x 100mm, laid black bond, natural finish, silver grey colour

NB: Kerts to be 'Conservator' kerts (200mm x 140mm) by

Marshalls Ltd, silver grey colour, laid flush with kerb side of kerb

strip

CONCRETE PAVING SLABS - to foot paths

'Pavlo' Slabs 150/150 concrete paving slabs by Marshalls Ltd, 400

x 400 x 30mm thick, buff colour, natural finish, laid black bond

CONSERVATION KERB - to transition between surface

materials

Joint flush to demarc transition between surfaces, supplied by

Marshalls Ltd, 145 x 255mm, silver grey

NB: In some locations an upstand is specified on the drawing

Boundary Treatment

BRICK WALL -

1800mm high, 215mm wide brick wall, brick on edge coping,

incorporating drainage fins, brick type to match adjacent

dwellings

DRYBRICK WALL -

1800mm high, 215mm wide brick wall, brick on edge coping,

incorporating drainage fins, brick type to match adjacent

dwellings, 1000 x 440 x 440mm brick piers at ends to match

drainage

CLOSE BOARD FENCING -

1800mm high close-boarded timber fence, treated softwood

(min. 15yr life span)

REAR ACCESS GATE -

Treated softwood timber gate (min. 15yr life span),

incorporating steel hinges and hook latch and padlock bar

ESTATE RAILING -

1200mm high steel estate railing in black

SQUARE TIMBER ROLLER -

175 x 175 x 900mm long square timber roller

by Jackson Fencing Ltd, treated 40mm

above ground, or equal and approved

Notes:

1) All surface materials are to be installed as specified or equal or approved

specification

2) All kerbs to bituminous macadam areas to be British Standard concrete kerbs (by

Marshalls or equal and approved) with constant to foreways to engineering

specification (internally 100mm) or laid flush where different paving types meet

(eg. driveways)

3) All block paved shared surfaces to receive York Small unit kerbs by Marshalls

or similar, colour to engineering details (internally 200mm square)

4) Visitor and parking court bays demarcated with a soldier course of natural colour

'Keyhole'

5) The extent and specification of porous paving surfaces is subject to detailed

landscape design

6) For Public Open Space Proposals refer to CSA/3823/107-110

7) For Public Open Space Proposals refer to CSA/3823/107-110

F	24/10/19	AL	Golf fence netting shown in PDS for
E	13/09/19	AL	context
D	13/09/19	AL	PDS updated for context
C	13/07/19	ST	Amended for new refuse collection points
B	11/02/19	AM	Updated to latest Site Layout
A	18/01/19	L.E.	Amended to full Site Layout

Rev	Date	By	Description
-----	------	----	-------------

CSA
environmental

Dolvis Barns, High Street,
Asthall, Northamptonshire NN7 5NT

T 01442 743447
E asthwell@csaenvironmental.co.uk
W csaenvironmental.co.uk

Project: Land East of Tye Lane, Walberton

Title: Hard Landscape Proposals

Sheet 3 of 3

Client: Linden Homes

Scale: 1:250 @ A0

Date: October 2018

Drawing No: CSA/3823/106

Drawn: LR

Checked: GC

Rev: E