



Sussex Catering Equipment (SCE) Limited
Unit E Ford Industrial Estate
Ford Lane
Ford BN18 0DF

FAO: Sam Smith
Maypole Inn
Maypole Lane
Yapton BN18 0DP



Date/Tax Point: 23rd January 2019

Dear Sam

Further to my recent site visit, I have pleasure in enclosing the following technical specification working off of the drawings supplied by yourselves.

To Supplying and fitting 1 off 2000mm long x 900mm deep x 600mm high stainless steel wall hung extraction canopy fabricated from 304 grade 0.9 DP1 stainless steel containing 3 off stainless steel baffle filters.

To Supplying and fitting stainless steel wall cladding beneath the extraction canopy.

To Supplying and fitting 1 off 450mm canopy spigot.

To Supplying and fitting 1 off 450mm diameter single phase 4 pole 230V cased axial fan. This fan will be connected to the duct by means of flexible connections and anti-vibration mounts. The fan will be located inside the building in the kitchen area, within the high pitch of the ceiling. The maximum duty of this fan is 6810 m³/hr. Noise level at 2 metres is 41dba.

To Supplying and fitting 2 metres of 450mm diameter duct. The duct will be taken through the proposed pitched roof of the new kitchen.

To Supplying and fitting 1 off high velocity jet cowl. The duct and cowl will terminate level with the apex of the roof.

The price for the above will be: £2,375.00 + VAT

Registered Office: 29 Cuckfield Crescent, Worthing, BN13 2ED
VAT Registration No: GB 197 5218 71
Company No: 10161846



If you have any queries or would like to discuss this quotation further, please do not hesitate to contact me on [REDACTED]

Yours sincerely [REDACTED]
for and on behalf of Sussex Catering Equipment (SCE) Ltd

[REDACTED]