SURFACING LEGEND

- Access road construction Type 1
- Block paved private drive and parking construction Type 2
- Permeable block paving Type 3
- Bridleway-TBA

KERBING LEGEND

- Type HB2 125x255 Half battered kerb with 100 mm upstand and Type CS2 Channel Block (where gradient >0.667%)(Extent of kerb indicated)
- Type HB2 125x255 Half battered kerb with 100mm upstand. (Extent of kerb indicated)
- PCC 125x50 Type BN Bullnosed kerb 25mm upstand. All kerbs to be cut into half lengths. (Extent of kerb indicated)
- Type EF to BS EN 1340 50x150 Precast concrete edging. (Extent of edging indicated)

SAFETY, HEALTH & ENVIRONMENTAL INFORMATION
CDM Regulations 2015

In addition to the hazards/risks normally associated with the type of work detailed on this drawing note should be made of the following:

- Working in vicinity of live highway
- Services to be located prior to any excavation work being undertaken
- Working on live foul sewers
- Deep excavations

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement. Contractor is not relieved of any of his obligations under all applicable health and safety regulations.

Rev.	Date	Details	Initials
A	14.10.20	First issue	KN

Drawing Status
PRELIMINARY FOR TENDER

Project
CINDERS NURSERY: Phase 2
YAPTON

Client
Crayfern HOMES

KAZYS NARBUTAS CONSULTING
Civil Engineering Consultant
Unit 5B, Tanners Court, Tanners Lane, East Wellow, Romsey, Hants. SO51 6DP
Telephone: 01794 522903 Email: kazys.n@knc.email

Drawing Title
Engineering Details
Surfacing & Kerbing Details

Drawn	Checked	Scales	Paper Size	Date
KN		1:250	A1	10.20

Job No.	Drawing No.	Revision
KNC2006	507-01	A

This drawing is the copyright of Kazys Narbutas Consulting and may not be copied, altered or reproduced in any form or passed to a third party without the consent of Kazys Narbutas Consulting. Do not scale from this drawing, use figured dimensions only.
Dimensions should be checked and verified on site and any discrepancies should be reported to Kazys Narbutas Consulting as soon as possible.

ARUN DISTRICT COUNCIL Y/140/20/DOC