




Code Specification

ASD Lighting Clarity Portrait Louvre, Black, Premium Opal, IP65, 4000K. 125mm Depth, 276mm Height, 190mm Width, Fascia Ring: Vandal resistant polycarbonate with self-extinguishing fire properties, Diffuser: Vandal resistant polycarbonate opal with self-extinguishing fire properties.
Applications not limited to: Commercial, Education, Footpath, Healthcare, Hotels, Residential, Social Housing.
CE, BS EN 60598, Class 1

Technical Information

Colour	Black
Diffuser	Premium Opal
CCT	4000K
System Power	7.8W
Delivered Lumens	342lm
Efficacy	43.8lm/W



Dimensions

Depth	125mm
Height	276mm
Width	190mm



C2P/BLL4LED600



Range Information

The Clarity Portrait Louvre is a robust high performance exterior luminaire from our Clarity Range.

Range Specification

Ceiling & wall mounted portrait or landscape

5 Year LED guarantee

Black, white, titanium and satin aluminium colour finishes available

Vandal resistant polycarbonate body and diffuser

Louvre, Eyelid, Cage or Plain Ring trims

Simple installation

Fast fit base and gear tray

Single screw fixing front trims

Interchangeable trims

IP65

Range Options

HI-LO PIR (luminaire at 10% during periods of inactivity, 100% light output when HI-LO PIR detects movement)

Fluorescent options available

PIR / Photocell options available

