

Code Specification


ASD Lighting ENSO Post-Top, Offset Mount, 2 Quadrant Adjacent, Black, Clear, IP66/IK10, 4000K. 670mm Diameter, 96mm Height 1, 170mm Height 2, Diffuser: Vandal resistant clear polycarbonate Materials. Applications not limited to: Car Parks, City Centres, Footpath, Healthcare, Parks & Amenities, Pedestrian Crossing, Rail, Traffic Routes. CE, BS EN 6098, Class 1.

Technical Information

Colour	Black
Diffuser	Clear
CCT	4000K
System Power	61.3W
Delivered Lumens	5786lm
Efficacy	94.4lm/W

Dimensions

Diameter	670mm
Height (1)	96mm
Height (2)	170mm



ENPO2QA/B4K4050-SM2



Range Information

The ENSO Post-Top luminaire is a Modular, Architectural Street Lighting Collection from our ENSO family.

Range Specification

UK designed, developed and manufactured

100,000 hours (L90, F10)

Tool free maintenance

IP66 protection using bespoke poured gaskets

IK10+ impact resistance, marine grade, LM6 aluminium and polycarbonate body

1000+ hours salt spray using environmentally friendly Metavate pre-treatment

Range Options

60 - 76mm Post top mounting

Offset post top mounting and suspension options

Customisable quadrant blanking available

Clear and opal diffusers available

Mini Cell option available

NEMA Socket option available

PIR option available

