

Code Specification

ASD Lighting ENSO Post-Top Central Spigot, 4 Quadrant, Lensed, Black, Clear, IP66/IK10, 4000K. 670mm Diameter, 96mm Height 1, 170mm Height 2, Body: Powder coated LM6 marine grade aluminium, Diffuser: Clear vandal resistant polycarbonate.

Applications not limited to: Car Parks, City Centres, Footpath, Healthcare, Parks & Amenities, Pedestrian Crossing, Rail, Traffic Routes.


CE, BS EN 6098, Class 1

Technical Information

Colour	Black
Diffuser	Clear
CCT	4000 K
System Power	51.5 W
Delivered Lumens	4584 lm
Efficacy	89 lm/W

Dimensions

Diameter	670mm
Height (1)	96mm
Height (2)	170mm



ENPC4Q/B4K4835-SM2



Range Information

The ENSO Post-Top luminaire is a Modular, Architectural Street Lighting Collection from our ENSO family.

Range Specification

100,000 hours (L90, F10)

Tool free maintenance

UK designed, developed and manufactured

IP66 protection using bespoke poured gaskets

IK10+ impact resistance, marine grade, LM6 aluminium and polycarbonate body

1000+ hours salt spray using environmentally friendly Metavate pre-treatment

Range Options

Clear and opal diffusers available

60 - 76mm Post top mounting

Mini Cell option available

NEMA Socket option available

Offset post top mounting and suspension options

PIR option available

Customisable quadrant blanking available

