

The Steddles

NOTES
1. ALL AS BUILT INFORMATION SUPPLIED BY THE CLIENT.

- AREAS WHERE SUB-GRADE LEVEL DISCREPANCY IS LESS THAN 50mm IN RELATION TO THE APPROVED DESIGN
- AREAS WHERE SUB-GRADE LEVEL DISCREPANCY IS MORE THAN 100mm IN RELATION TO THE APPROVED DESIGN
- LOCATION OF DESIGN WEIRS / CHECK DAMS. REFER TO CONTRACTOR DOCUMENTS FOR EVIDENCE OF AS-BUILT WEIRS
- AS BUILT SUB-GRADE LEVEL
- LEVEL OF DESIGN SUB-BASE / PERMAVOID BASE (WHERE APPLICABLE)
- * NOTE FOR ROAD TYPES WITH SUB-BASE INCORPORATING GEOCELLULAR UNITS: FOR SUB-GRADE DESIGN LEVEL DEDUCT 0.4m FROM THE INDICATED SUB-BASE LEVELS

P:\119-156 - Land at Stakers Farm, Yapton\Tech\Acad\Figures\YAP-130-SK008.dwg

HATCHED AREA TO HAVE EXTENDED SUB-BASE 2m BEYOND KERBLINE AS PER YAP-180-035 ROAD TYPE 3 DETAIL TO AID IN HALF-DISCHARGE TIMES FROM THE PERMEABLE PAVING SYSTEM.

Rev	Amendments	Dm	Chk	App	Date
 ODYSSEY					
Tuscany House White Hart Lane Basingstoke Hampshire RG21 4AF					
Telephone: 01256 331144 Fax: 01256 331134 E: info@odysseyconsult.co.uk W: www.odysseyconsult.co.uk					
Job Title LAND AT STAKERS FARM, YAPTON					
Drawing Title AS-BUILT (38 UNITS) PERVIOUS PAVEMENT SUB-GRADE					
Client DANDARA LIMITED (SOUTHERN)					
Scale 1:250 @A1	Date JAN 22	Designed AK			
Drawn AK	Checked SW	Approved SW			
Job No 19-156	Drawing No YAP-130-SK008	Rev -			