



Notes			
1	This drawing to be read in conjunction with all relevant Architects and Engineers drawings and specifications.		
2	Dimensions are in millimetres unless noted otherwise.		
3	Original topographic survey undertaken by Kings Shaw Architects.		
4	For full topographic survey information see Kings drawing No. 99906.0001.		
5	All levels based on O.S. Datum by GPS.		
6	Existing levels shown thus: +6.77		
7	Before excavation commences, the Contractor shall ascertain the depths, sizes and locations of all services to be crossed. Any conflicts in levels between new works and existing services shall be notified to the Engineer.		
8	Keel types are shown thus:		
9	+/-115mm Face Keel (See STD.02.25)		
10	+/-6mm / 25mm Dropped Keel (See STD.02.25)		
11	+/- Flush Keel (See STD.02.25)		
12	+/- Transition Keels (See drawing STD.02.25)		
13	+/- Precast Concrete Slipping 50 x 150mm EF		
14	For keel types within adopted areas see Agreement Drawing 28854-105		
15	Finishers Schedule (Private Works):		
16	BITUMINOUS MACADAM ACCESS ROAD		
17	Construction: 30mm 0/10mm Close Graded Asphalt Concrete Surface Course		
18	100/150 Binder Grade (AC10 does surf)		
19	60mm 0/20mm Dense Asphalt Concrete Binder Course		
20	100/150 Binder Grade (AC20 dense bit)		
21	75mm 0/20mm Dense Asphalt Concrete Base Course		
22	100/150 Binder Grade (AC22 base)		
23	255mm Type 1 Sub - Base		
24	to S.H.W. - Chaise 803		
25	450mm Total		
26	Anticipated Formation: Make Ground		
27	PERMEABLE PARKING BAYS & ACCESS (also Serving Road Areas)		
28	Construction: 80mm Forpave Aquilator Concrete Blocks, or equivalent		
29	Hermipore Bond (Block Type to be confirmed)		
30	30mm of firm Normal Stated Basalt Aggregate, or Equivalent		
31	75mm 0/20mm Dense Asphalt Concrete Base Course		
32	100/150 Binder Grade (AC22 base)		
33	255mm Type 3 Sub - Base		
34	Thick T4160 Graded by Tensar or equivalent		
35	150mm FFS Course Clipping Material		
36	600mm Total		
37	Anticipated Formation: Make Ground		
38	Anticipated Method of Working (Permeable Block Paving):		
39	Phase 1		
40	Lay curbing, gapped and porous sub-base.		
41	Lay 75mm of dense road base over sub-base		
42	Phase 2: After building work is completed		
43	Clean Masticated Surface.		
44	Cut 75mm diameter holes at 1.5m centres through the asphalt surface into the sub-base.		
45	Heavy roll to remove local heave.		
46	Lay Stone and Block Pavers		
47	PERMEABLE PARKING BAYS		
48	Construction: 80mm Forpave Aquilator Concrete Blocks, or equivalent		
49	Hermipore Bond (Block Type to be confirmed)		
50	30mm of firm Normal Stated Basalt Aggregate, or Equivalent		
51	75mm 0/20mm Dense Asphalt Concrete Base Course		
52	100/150 Binder Grade (AC22 base)		
53	255mm Type 3 Sub - Base		
54	Thick T4160 Graded by Tensar or equivalent		
55	450mm Total		
56	Anticipated Formation: Make Ground		
57	Anticipated Method of Working (Permeable Block Paving):		
58	Phase 1		
59	Lay gapped and porous sub-base.		
60	Lay 75mm of dense road base over sub-base		
61	Phase 2: After building work is completed		
62	Clean Masticated Surface.		
63	Cut 75mm diameter holes at 1.5m centres through the asphalt surface into the sub-base.		
64	Heavy roll to remove local heave.		
65	Lay Stone and Block Pavers		
66	BITUMINOUS MACADAM FOOTWAY		
67	Construction: See drawing STD.02.25 Type 1A		
68	over FFS capping fill as required		
69	PRIVATE FOOTWAYS		
70	Construction: See drawing STD.02.25		
71	over FFS capping fill as required		
72	HYDRAULIC BREAK		
73	Construction: See Sections FF and GG		
74	Section 278 Highway Works:		
75	Carriageway		
76	See Drawing 28854-105		
77	Footway		
78	HYDRAULIC BREAK ON WEST BOUNDARY ACCESS SPEED TABLE ADDED.		
79	ACCESS ROAD TO FRONT OF PLOT 9 INDICATED.		
80	PF-20-05-18		
81	PF-20-05-18		
82	PF-20-05-18		
83	PF-20-05-18		
84	PF-20-05-18		
85	PF-20-05-18		
86	PF-20-05-18		
87	PF-20-05-18		
88	PF-20-05-18		
89	PF-20-05-18		
90	PF-20-05-18		
91	PF-20-05-18		
92	PF-20-05-18		
93	PF-20-05-18		
94	PF-20-05-18		
95	PF-20-05-18		
96	PF-20-05-18		
97	PF-20-05-18		
98	PF-20-05-18		
99	PF-20-05-18		
100	PF-20-05-18		

Archibald Shaw			
Consulting Civil & Structural Engineers			
One Little London, Chichester, West Sussex, PO19 1PP			
Telephone: 01243 798471 Facsimile: 01243 779346			
mol@archibaldshaw.co.uk www.archibaldshaw.co.uk			
CLIENT			
Pcille			
PROJECT			
Housing Development			
Kings Close, Yapton			
Pavement Construction			
DRAIN BY		DESIGNED BY	
PF		PF	
CHECKED BY		STATUS	
VC		Preliminary	
SCALE @ A1		@ DATE	
1:200		Jan. 2018	
JOB NO.		DRAWING NO.	
28854		102	
REVISION		REVISION	
		P3	