



NOTES

- 1.All levels are in metres above Ordnance Datum.
- 2.All slab levels shown are for guidance only and may need to be adjusted on site, subject to approval by the engineer.
- 3.Do not scale from this drawing, work only from stated dimensions or setting out details.

SYMBOL KEY

	Part M entrance
	Secondary entrance with 165mm drop from FFL to FGL
	Step (with number of)
	Plot number
	Finished floor level
	Proposed levels
	Gradient
	Retaining wall

SAFETY, HEALTH & ENVIRONMENTAL INFORMATION
CDM Regulations 2015

In addition to the hazards/risks normally associated with the type of work detailed on this drawing note should be made of the following:

- Working in vicinity of deep excavations.
- Working in live Highway
- Connection to live foul sewer
- Existing Services across site and in Highway

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement.

Contractor is not relieved of any of his obligations under all applicable health and safety regulations.

C	10.12.18	Retaining wall and levels amended.	HN
B	07.12.18	Impermeable crossover amended.	HN
A	05.12.18	Initial issue	HN
Rev.	Date	Details	Initials

Drawing Status
PRELIMINARY

Project
**ORCHARD BUSINESS PARK
NORTH END ROAD, YAPTON**



Engineering Details Levels Layout				
Drawn HN	Checked KN	Scales 1:200	Paper Size A1	Date 12.18
Job No. ES1801	Drawing No. 509-01	Revision C		