



British
Geological Survey

NATURAL ENVIRONMENT RESEARCH COUNCIL

Version 2.0.6

BGS ID: 434405 : BGS Reference: SU90SE27
British National Grid (27700) : 496380,101330

[Report an issue with this borehole](#)

<<

< Prev

Page 1 of 1

Next >

>>

East

SU 90 SE 27

9638 0133

Flansham

Block 2

Surface level +3.7 m
Water struck at -0.8 m
October 1981

Waste 4.7 m
Bedrock 1.5 m+

LOG

Geological classification	Lithology	Thickness m	Depth m
	Soil	0.4	0.4
Brickearth	Clay, silty, brown and mottled grey-brown	2.4	2.8
Raised Beach Deposits (younger)	Silt, very sandy, chalky, with chalk pebbles	1.9	4.7
Upper Chalk	Chalk, soft, weathered at top	1.5+	6.2

OS spot level in
off road - in lane
granite outcrops
meadow,
+ 2.8m. AOD.



British
Geological Survey

NATURAL ENVIRONMENT RESEARCH COUNCIL

Version 2.0.6

BGS ID: 434408 : BGS Reference: SU90SE30

British National Grid (27700) : 497030,102140

[Report an issue with this borehole](#)

<<

< Prev

Page 1 of 1

Next >

>>

North
East

SU 90 SE 30

9783 8214

William Farm

Block 2

Surface level +5.1 m

Water not struck

October 1981

Waste

4.0 m

Bedrock

1.0 m+

LOG

Geological classification

Lithology

Thickness
m

Depth
m

Soil

0.4

0.4

Brickearth

Clay, silty, brown and mottled grey brown

2.0

2.4

Raised Beach Deposits
(younger)

Silt, very sandy, chalky, with chalk and some flint
pebbles

1.6

4.0

Upper Chalk

Chalk, soft, with nodular flints

1.0+

5.0



British
Geological Survey

NATURAL ENVIRONMENT RESEARCH COUNCIL

Version 2.0.6

BGS ID: 434401 : BGS Reference: SU90SE23

British National Grid (27700) : 495420,101550

[Report an issue with this borehole](#)

<<

< Prev

Page 1 of 1

Next >

>>

W576

SU 90 SE 23

9542 0155

Bee Farm, Flansham

Block 8

Surface level +3.7 m

Water not struck

September 1981

Waste 1.6 m
Bedrock 3.2 m+

LOG

Geological classification

Lithology

Thickness
m

Depth
m

Soil		0.2	0.2
Brickearth	Clay, brown, very silty, with peat particles and a few small angular flint pebbles	1.4	1.6
Upper Chalk	Chalk, rubbly near top, soft and crumbly below, with nodular flints	3.2+	4.8



British
Geological Survey

NATURAL ENVIRONMENT RESEARCH COUNCIL

Version 2.0.6

BGS ID: 434404 : BGS Reference: SU90SE26

British National Grid (27700) : 496180,102490

[Report an issue with this borehole](#)

<<

< Prev

Page 1 of 1

Next >

>>

North

SU 90 SE 26

9618 0249

Hams, Tipton

Block 8

Surface level +3.5 m

Water not struck

September 1981

Waste 4.0 m
Bedrock 2.2 m+

LOG

Geological classification

Lithology

Thickness
m

Depth
m

	Soil and made ground	0.5	0.5
Brickearth	Clay, silty, brown and mottled brown on grey, with some peat particles and rare angular flint pebbles	1.8	2.3
Raised Beach Deposits (younger)	Silt, olive and olive brown, very sandy and chalky, with abundant chalk and a few angular flint pebbles	1.7	4.0
Upper Chalk	Chalk, soft, with nodular flints, weathered at top	2.2+	6.2