

VELUX conservation roof windows

For traditional buildings



- Available in either centre-pivot or top-hung.

- Available in either centre-pivot or top-hung.
- Black external profiles and glazing bar. RAL 9005.
- Recessed installation for slate and tiled roofs.
- Top-hung roof windows listed below are suitable for emergency escape.
- Other sizes and glazing options available – contact us for further information.



Conservation packages include:

- Roof windows with laminated glazing as standard for safety.
- Recessed flashings available for a more streamlined external appearance.
- Insulation collar and underfelt collar provided for a weathertight and energy efficient installation.

Conservation roof windows

External frame size (nominal W x H) cm						
Code	Description	CX04	CX06	FX06	MK06	MK08 UK04
Cante-pivot white painted						
GRL SDSN2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDN recessed flashing for tiles up to 8mm thick (min 20° roof pitch)	E438	E455	E495	E558	E601 E726
GRL SDSP2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDP flashing for plain tiles up to 13mm thick (min 25° roof pitch)	E400	E416	E453	E514	E554 E673
GRL SDSW2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch)	E400	E416	E453	E514	E554 E673
GRL SDSL2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDL recessed flashing for tiles up to 90mm in profile (min 20° roof pitch)	E438	E455	E495	E558	E601 E726
Topping white painted. For roof pitches of 25°-75°. Always specify special springs when ordering.						
GRL SDSEN2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20° roof pitch)	-	-	-	-	E725 -
GRL SDSEP2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDP flashing for plain tiles up to 13mm thick (min 25° roof pitch)	-	-	-	-	E678 -
GRL SDSWE2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15° roof pitch)	-	-	-	-	E678 -
GRL SDSLE2 U-value 1.3 W/m ² K	GRL 2570 roof window + EDL recessed flashing for tiles up to 90mm in profile (min 20° roof pitch)	-	-	-	-	E725 -

- ▶ All roof windows have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 3pm (NI).

Optional glazing bars for standard VELLUX roof windows



The requirements from conservation officers throughout the county differ and the black finish featured within our conservation roof window packages may not be required in your area.

Consult your local conservation officer and find out if you can create a traditional

appearance by adding a glazing bar to a standard VELUX roof window with grey exterior. This will allow you to take advantage of all roof window styles and sizes available (except triple glazed roof windows).

Recessed flashing



As well as the addition of a glazing bar, your local conservation officer may request that your roof window be installed deeper into the roof than can be achieved with a standard installation. To do this you should select a recessed flashing kit, which will provide a sleek, streamlined finish as less of the roof window protrudes above the roofline. Recessed flashings are also available with insulation and underfelt collars and are recommended for optimum energy efficiency.

Our full range of recessed flashings are available as part of our conservation roof window packages and help you comply with local conservation requirements.

To create your grey conservation package:

- Select your preferred VELUX roof window. This includes white painted, white polyurethane, pine and all operating methods (pages 20-25).
 - Choose a flashing kit suitable for your specific roof pitch and roofing material – a recessed flashing kit is recommended (pages 50-51).
 - Use VELUX installation products for optimum energy efficiency (pages 48-49).
- Add one or more conservation glazing bars in the corresponding size to your roof windows.

Grey glazing bar to match grey exterior (nearest RAL 7043) finish of standard VELUX roof windows.

We recommend the use of two glazing bars for our wider roof windows such as SK06, UK04 and UK08.

[illegible]

- ▶ Glazing bars are not available for -60 and -62 triple glazing variants.
- ▶ Prices above are for 1 glazing bar only.
- ▶ All glazing bars have a delivery time of 2 days.
- ▶ Delivery time is in working days from receipt of orders placed before 4pm (UK) and 3pm (NI).