



Christopher Hoare Tree Services Ltd

Arboricultural Contracting & Consultancy

TREE SURVEY SCHEDULE			
Client:	Persimmon Homes South Coast	Site:	Burndell Road, Yapton, West Sussex
Date:	14th February 2013	Consultant:	Alex Monk (<i>Tech Cert Arbor A, NCH Arb</i>)
Tagged:	No	Weather:	Sunny & Dry

Tree No	Species	H't (m)	Single/ Multi- Stemmed (S or MS)	Stem Diam (mm)	Branch Spread (m)				H't of Crown AGL (m)				Age	Physio-logical Condition	Structural Condition and Relevant Comments	Preliminary Management Recommendations	Est. Rem. Contrib. (Yrs)	Cat
					N	E	S	W	N	E	S	W						
1	Scots Pine		S	230	3.0	1.0	2.0	3.0	4.0	4.0	4.0	4.0	SM	Good	Off site tree. Bifurcated at 1.7m above ground level. Minor dead wood in crown.	None required at time of survey.	20+	C1
2	Common Sycamore		S	300	4.0	3.0	4.0	3.0	3.0	2.0	2.0	4.0	SM	Fair	Three trees grow as one crown. Off site trees. Previously pollarded and multi-stemmed at 3.5m above ground level.	None required at time of survey.	20+	C1
3	Lawson Cypress		S	620	3.0	4.0	4.0	4.0	1.0	1.0	1.0	1.0	M	Good	Ivy on trunk and in crown. Low hanging branches. Minor dead wood in crown.	None required at time of survey.	20+	C1
4	Pedunculate Oak		MS	1320 930	12.0	11.0	15.0	12.0	8.0	5.0	2.0	3.0	M	Good	Bifurcated at 1.1m above ground level. Dead wood in crown. Damaged limbs on east side.	Remove major dead wood within 12 months.	40+	A1
5	Pedunculate Oak		S	1420	8.0	9.0	10.0	11.0	6.0	6.0	3.0	4.0	M	Good	Multi-stemmed at 2m above ground level. Cavity extends through stem from north to south orientation, 330mm high & 240mm wide. Dead wood in crown. Previously crown deduced on south side.	Remove major dead wood within 12 months.	40+	B1

6	Monterey Cypress	12	S	1310	5.0	5.0	5.0	6.0	7.0	3.0	2.0	0.0	1.0	M	Fair	Trunk and crown shape distorted. Leans north-east. Multi-stemmed at 2m above ground level. Tight forks with included bark. Storm damage in crown with snapped out and hanging limbs. Dead wood in crown. Poor quality tree.	Advise removal within 12 months	<10	U
7	Monterey Cypress	13	S	640	4.0	3.0	4.0	2.0	5.0	5.0	4.0	0.0	0.0	M	Poor	Ivy on trunk and in crown. Low crown density with storm damage in crown leaving snapped out and hanging limbs. 50% dead, poor quality tree.	Advise removal within 12 months	<10	U
8	Monterey Cypress	9	S	570	0.0	5.0	6.0	0.0	0.0	-	2.0	2.0	-	M	Dead	Dead tree.	Advise removal within 12 months	-	U
9	Monterey Cypress	12	S	560	2.0	4.0	2.0	3.0	3.0	3.0	3.0	3.0	3.0	SM	Poor	Ivy on trunk. Trunk and crown shape distorted. Cavities and decay at 0.5m above ground level on west side, decaying wound upto 2m above ground level on west side. Poor quality tree.	Advise removal within 12 months	<10	U
10	Monterey Cypress	13	S	790	3.0	7.0	5.0	5.0	5.0	3.0	3.0	1.0	4.0	M	Fair	Vertical wound on east side up to 1.5m above ground level with decay. Trunk and crown shape distorted. Storm damage in crown. Decaying limbs collapsing in crown. Poor quality tree.	Advise removal within 12 months	<10	U
11	Monterey Cypress	8	S	850	0.0	0.0	9.0	2.0	2.0	-	-	0.0	3.0	M	Poor	Root plate lifted with tree lying on ground.	Advise removal within 12 months	<10	U
12	Common Hawthorn	6	MS	310 130	0.0	2.0	4.0	3.0	3.0	-	3.0	1.0	3.0	SM	Poor	Decaying stem at base. Bifurcated at ground level. Suppressed and stunted. Limb from T11 damaging crown, poor quality tree.	Advise removal within 12 months	<10	U

13	Common Beech	11	S	500 over ivy	5.0	5.0	5.0	3.0	5.0	2.0	2.0	2.0	2.0	3.0	SM	Good	Unable to verify health and safety of stem due to ivy smothering stem. Bifurcated at 2.5m above ground level.	Sever and remove ivy and re-inspect within 12 months.	40+	A1 interim
14	Common Sycamore	5	S	460	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	SM	Fair	Decaying stem. Previously pollarded at 2m above ground level with decaying pollard points. Poor quality tree.	Advise removal within 12 months	<10	U
15	Common Elder	4	MS	120 150	3.0	2.0	1.0	1.0	1.0	2.0	2.0	2.0	2.0	2.0	SM	Fair	Bifurcated at ground level. Ivy on trunks.	None required at time of survey.	10+	C1
16	Lawson Cypress	13	S	850	3.0	5.0	3.0	3.0	3.0	2.0	2.0	2.0	2.0	2.0	M	Good	Ivy on trunk. Multi-stemmed at 2m above ground level. Minor dead wood and stubs in crown.	None required at time of survey.	20+	C1
17	Silver Birch	7	S	130	2.0	1.0	1.0	1.0	1.0	2.0	2.0	2.0	2.0	2.0	Y	Good	Developing tree.	None required at time of survey.	40+	C1
18	Silver Birch	8	S	130	3.0	1.0	1.0	1.0	1.0	3.5	3.5	3.5	3.5	3.5	Y	Good	Developing tree.	None required at time of survey.	40+	C1
19	Wild Cherry	8	S	330	4.0	4.0	4.0	4.0	5.0	3.0	3.0	3.0	3.0	3.0	SM	Good	Bifurcated at 3m above ground level. Minor dead wood in crown. Bramble in crown.	None required at time of survey.	40+	B1
20	Leyland Cypress	6	MS	120 90 90 110	3.0	1.0	2.0	1.0	1.0	4.0	4.0	4.0	4.0	4.0	SM	Fair	Off site tree. Multi-stemmed at 1m above ground level.	None required at time of survey.	20+	C1
21	Bay	7	MS	90 x 6	3.0	2.0	3.0	3.0	3.0	2.0	2.0	2.0	2.0	2.0	SM	Good	Off site tree. Multi-stemmed at ground level.	None required at time of survey.	40+	C1
22	Pedunculate Oak	13	S	Est 690	7.0	8.0	7.0	6.0	6.0	6.0	5.0	3.0	4.0	4.0	M	Good	Off site tree. Unable to verify health and safety due to no access. Multi-stemmed at 4-5m above ground level. Dead wood in crown.	None required at time of survey.	40+	A1 Interim
23	Common Hornbeam	13	S	Est 490	4.0	4.0	6.0	6.0	6.0	6.0	7.0	5.0	3.0	3.0	SM	Good	Unable to verify health and safety due to dense vegetation. Multi-stemmed at 3m above ground level.	Clear vegetation and re-survey within 12 months.	40+	B1 Interim
24	Common Sycamore	20	S	600	4.0	7.0	5.0	7.0	7.0	9.0	4.0	12.0	4.0	4.0	M	Good	Off site tree. Bifurcated at 6m above ground level, then again at 8m above ground level. Minor dead wood in crown.	None required at time of survey.	40+	B1

25	Common Hornbeam	19	S	410	6.0	5.0	3.0	5.5	3.0	5.0	7.0	8.0	SM	Good	Bifurcated at 4m above ground level. Tight forks with included bark. Minor dead wood in crown.	None required at time of survey.	40+	B1
26	Common Hornbeam	17	S	400	1.0	6.0	7.0	6.0	2.0	0.0	2.0	2.0	SM	Good	Trunk and crown shape distorted due to group pressure. Trifurcated at 1.5m above ground level with bark wounds in crown. Minor dead wood in crown.	None required at time of survey.	40+	B1
27	Common Hornbeam	16	S	490	6.0	6.0	2.0	5.0	2.0	3.0	8.0	3.0	EM	Good	Trunk and crown shape distorted due to group pressure. Multi-stemmed at 2m above ground level. Dead ivy on trunks. Minor dead wood in crown.	None required at time of survey.	40+	B1
28	Common Hornbeam	17	S	430	7.0	7.0	4.0	3.0	4.0	4.0	3.0	2.0	EM	Good	Ivy on trunk. Leans north. Trunk and crown shape distorted due to group pressure. Minor dead wood in crown.	None required at time of survey.	40+	B1
29	Monterey Cypress	17	S	430	3.0	3.0	2.0	0.0	2.0	6.0	6.0	-	EM	Dead	Dead tree.	Advise removal within 12 months	-	U
30	Monterey Cypress	18	S	540	3.0	4.0	6.0	0.0	6.0	6.0	4.0	-	EM	Poor	Decayed subsidiary stem at base. Multi-stemmed at 2m above ground level. Leans south east with dead wood in crown. Low crown density	Advise removal within 12 months	<10	U
31	Monterey Cypress	16	MS	310 470	0.0	4.0	4.0	0.0	4.0	7.0	3.0	-	EM	Dead	Dead tree, leans into T30.	Advise removal within 12 months	<10	U
32	Monterey Cypress	19	S	730	6.0	4.0	5.0	2.0	4.0	6.0	5.0	5.0	M	Fair	Ivy on trunk. Decaying subsidiary stem on south side at 2-3m above ground level. Multi-stemmed at 6-7m above ground level.	None required at time of survey.	10+	C1
33	Monterey Cypress	17	S	880	7.0	1.0	2.0	7.0	2.0	8.0	6.0	6.0	M	Fair	Decaying stubs on south side. Bifurcated at 3m above ground level. Dead ivy on trunks. Minor dead wood in crown.	None required at time of survey.	20+	C1

34	Monterey Cypress	13	S	1080	5.0	5.0	2.0	9.0	8.0	7.0	8.0	1.0	M	Fair	Bifurcated at 2m above ground level. Tight forks with included bark. Major storm damage in crown leaving snapped out and hanging limbs. Lost leader.	Advise removal within 12 months	<10	U
35	Monterey Cypress	13	S	440	0.0	9.0	0.0	0.0	-	9.0	-	-	EM	Poor	Ivy on trunk. Decaying stem. Heavily weighted east. Trunk and crown shape distorted. Poor quality tree.	Advise removal within 12 months	<10	U
36	Lawson Cypress	7	MS	100 x 6	2.0	2.0	2.0	2.0	3.0	3.0	3.0	3.0	SM	Good	Off site tree. Multi-stemmed at 1m above ground level.	None required at time of survey.	10+	C1
37	Common Hawthorn	6	S	240	2.0	2.0	1.0	1.0	3.0	3.0	3.0	3.0	SM	Good	Trunk and crown shape distorted. Multi-stemmed at 2m above ground level.	None required at time of survey.	20+	C1
38	Common Hawthorn	6	S	250	2.0	1.5	1.0	1.0	2.5	2.5	2.5	2.5	SM	Good	Trunk and crown shape distorted. Bifurcated at 2m above ground level.	None required at time of survey.	20+	C1
Gp 1	Lawson Cypress	6	S	150	-	-	-	-	-	-	-	-	Y	Good	Off site group. Crowns extend into site by 3m in places.	None required at time of survey.	20+	C2
Gp 2	Common Hawthorn Common Blackthorn	4	S	120	-	-	-	-	-	-	-	-	Y	Good	Mixed species group with low hanging branches. Understory of bramble encroaching into site.	None required at time of survey.	10+	C2
Gp 3	Common Hawthorn Common Elder	4	MS	100 x 6	-	-	-	-	-	-	-	-	SM	Fair	Group of 4 trees. Multi-stemmed at ground level.	None required at time of survey.	20+	C2
Gp 4	Hawthorn Elder Blackthorn	6	S	120	-	-	-	-	-	-	-	-	SM	Good	Mixed species group to north of site forming good visual separation to and from site.	None required at time of survey.	20+	C2
Gp 5	Hawthorn Elder	5	S	140	-	-	-	-	-	-	-	-	SM	Good	Mixed species group to east of site, sporadic in places.	None required at time of survey.	20+	C2
Gp 6	Hawthorn Elder Goat Willow Bramble	6	S	220	-	-	-	-	-	-	-	-	SM	Good	Mixed species group to centre of site. Minor dead wood in crowns.	None required at time of survey.	20+	C2

Gp 7	Monterey Cypress	10	S	500	-	-	-	-	-	-	-	-	-	-	-	-	-	EM	Dead	Six dead and failed stems	Advise removal within 12 months	-	U
Gp 8	Hawthorn Blackthorn Elm	6	S	120	-	-	-	-	-	-	-	-	-	-	-	-	-	Y	Fair	Mixed species group. Ivy on trunks with bramble understorey.	None required at time of survey.	10+	C1