

Appendix H Stockpile Register

Form SF003 Soil Stockpile Audit Sheet

Project Address: Kings. Close, Yapton

Contract No: C411

Stockpile Ref.	Dated Stockpile Started	Description of Material	Origins of Material	Date Stockpile Sampled (and volume of stockpile)	Treatment	Final Sentencing	Final Destination including Dates and Volumes
Original Stockpiles							
SP1			Onsite prior to Soilfix Site works				Removed prior to Soilfix Site works
SP2		Brown sandy soil with brick, concrete, plastic, metal and ACM samples		24/02/2017 20m3 TP SP2	Segregated with excavator and handpicking including removal of all visible ACM	Non Hazardous	Placed in SP01 for removal offsite
SP3		Brown sandy soil with brick, concrete, plastic, metal and ACM samples	Onsite prior to Soilfix Site works	10m3	Segregated with excavator and handpicking including removal of all visible ACM	Non Hazardous	Placed in SP01 for removal offsite
Soilfix Stockpiles							
SP01	18/04/18	Brown gravelly, clayey sand, gravel of flint, brick and concrete, occasional ash	Across site, including SP2, SP3, SP02, SFTP2, SFTP3, SFTP6 and SFTP7	As per trial pits 1910m3	Segregated as excavated (inc handpicking) prior to being placed in stockpile	Non Hazardous	Removal offsite: Airlinks Golf Club, Southall Lane, Hounslow
SP02	19/04/18	Brown gravelly clayey sand, gravel of brick, flint and concrete, some organic matter	South east corner	20m3 25/04/18	Segregated as excavated (including handpicking) prior to being placed in stockpile	Non Hazardous	Placed in SP01 for removal offsite

Form SF003 Soil Stockpile Audit Sheet

Project Address: Kings. Close, Yapton

Contract No: C411

Stockpile Ref.	Dated Stockpile Started	Description of Material	Origins of Material	Date Stockpile Sampled (and volume of stockpile)	Treatment	Final Sentencing	Final Destination including Dates and Volumes
SP03	23/04/18	Black ashy gravelly sand, with gravel of mainly red brick, glass and metal	Across site including SFTP1, SFTP4, TP4, TP6 and TP7	80m3 As per trial pits	Segregated as excavated (including handpicking) prior to being placed in stockpile	Hazardous	Removed offsite: Mick George, Mepal Soil Waste Treatment Centre, Mepal
SP04	26/04/18	Brown orange clayey sandy silt	Plots 9, 10 and 11	80-100m3 09/05/18 SP04 S1 SP04 S2	Visually checked and segregated as excavated	Suitable for reuse onsite	Remained on site.
SP05	23/05/18	Brown gravelly sand with gravel of frequent solid black coal tar containing material	Plot 2	10m3 23/05/18 SP05 S1 – soil SP05 S2 black gravel	Segregated and handpicked of ACM	Hazardous	Mick George, Mepal Soil Waste Treatment Centre, Mepal