



KEY:

	Tarmac surface finish to roads and drives		900mm wide path formed using 450mm x 450mm buff riven slabs
	Brindle Permeable Concrete Block Paving 60mm		1.8m x 1.8m patio formed using 450mm x 450mm buff riven slabs
	1.8m high brick screen wall		1.2m x 1.2m paved area for bin storage formed using 450mm x 450mm buff riven slabs
	1.8m high close-boarded fence		Proposed streetlighting positions 5m column height
	1.8m high larch lap perimeter fencing		Rotary washing line
	1.2m rustic post & 3 rail fence		Postal numbers
	1.2m treated timber post and 2 wire fence		
	200 litre water butt on stand with tap on paving slab base		
	2.1m x 1.5m shed on concrete base with cycle lock-down point		

D	21.10.14	Rented and shared plots amended.	TC
C	08.10.14	Fencing amended.	KT
B	14.08.14	Street lighting amended.	TC
A	01.05.14	Drawing updated to suit revised group specification.	KT
REV. No.	DATE	DESCRIPTION	INITIALS
Client			
PERSIMMON HOMES (Part of Persimmon Ltd)		MJA CONSULTING CIVIL AND STRUCTURAL ENGINEERS 58-62 Oak Street, Abingdon Oxon. OX14 5BZ Tel: 01235 555173 Fax: 01235 523226	
Project Goodchew Close Phase 2, Yapton		Scale 1:250 Checked @ AO Date June '13 Drawn JOK	
Title External Works Sheet 3		Drawing No. 4822:42 Rev D	