


Existing Tree Schedule

Little Meadow



Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 01	<i>Betula pendula</i> (Silver Birch); (3.0m Radius of nominal circle; RPA 28m²)	239 mm	13.0 m Clear Stem Height 2.0 m	N: 2.0 m E: 4.0 m S: 4.0 m W: 3.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Slightly uneven due to hedge. Limited value.	C 1	Retain
T 02	<i>Betula pendula</i> (Silver Birch); (2.1m Radius of nominal circle; RPA 14m²)	159 mm	10.0 m Clear Stem Height 1.5 m	N: 0.0 m E: 2.0 m S: 3.0 m W: 2.0 m	Semi-Mature Estimated Remaining Contribution <10 Years	Major damage at the base and dieback to main stem.	U	Retain
TG 03	<i>Cupressus x leylandii</i> (Leyland Cypress); (3.6m Radius of nominal circle; RPA 41m²)	300 mm	6.0 m Clear Stem Height 1.0 m	N: 1.0 m E: 1.0 m S: 1.0 m W: 1.0 m	Over-Mature Estimated Remaining Contribution <10 Years	Topped with very little live growth left.	U	Retain
TL 04	<i>Cupressus x leylandii</i> (Leyland Cypress); (4.2m Radius of nominal circle; RPA 55m²)	340 mm	15.0 m Clear Stem Height 1.0 m	N: 2.0 m E: 1.0 m S: 3.0 m W: 1.0 m	Early Mature Estimated Remaining Contribution 10 + Years	Good dense line of trees with some dieback from shading.	C 2	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 05	<i>Fraxinus excelsior</i> (Ash) (10.8m Radius of nominal circle; RPA 366m²)	900 mm	18.0 m Clear Stem Height 10.0 m	N: 7.0 m E: 8.0 m S: 7.0 m W: 7.0 m	Mature Estimated Remaining Contribution 20 + Years	Multistemmed at 2m. Limited inspection. Hangs over the leyland treeline	B 2	Retain
T 06	<i>Cupressus x leylandii</i> (Leyland Cypress); (12m Radius of nominal circle; RPA 452m²)	1000 mm	16.0 m Clear Stem Height 0.0 m	N: 3.0 m E: 6.0 m S: 7.0 m W: 6.0 m	Over-Mature Estimated Remaining Contribution 10 + Years	Large multistem with lots of dieback.	C 1	Remove
T 07	<i>Cupressus x leylandii</i> (Leyland Cypress); (9.6m Radius of nominal circle; RPA 290m²)	800 mm	15.0 m Clear Stem Height 2.0 m	N: 2.0 m E: 7.0 m S: 3.0 m W: 1.0 m	Over-Mature Estimated Remaining Contribution 10 + Years	Large multistem with lots of dieback. Part topped at 6m.	C 1	Remove
T 08	<i>Cupressus x leylandii</i> (Leyland Cypress); (12m Radius of nominal circle; RPA 452m²)	1000 mm	16.0 m Clear Stem Height 0.0 m	N: 3.0 m E: 6.0 m S: 7.0 m W: 6.0 m	Over-Mature Estimated Remaining Contribution 10 + Years	Large multistem with lots of dieback.	C 1	Remove

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 09	<i>Fraxinus excelsior</i> (Ash) (4.8m Radius of nominal circle; RPA 72m²)	380 mm	14.0 m Clear Stem Height 2.5 m	N: 3.0 m E: 3.0 m S: 4.0 m W: 5.0 m	Semi-Mature Estimated Remaining Contribution 20 + Years	Damage to exposed roots and heavy ivy.	B 2	Retain
T 10	<i>Corylus avellana</i> (Hazel); (2.1m Radius of nominal circle; RPA 14m²)	158 mm CSD	8.0 m Clear Stem Height 0.0 m	N: 6.0 m E: 6.0 m S: 6.0 m W: 6.0 m	Early Mature Estimated Remaining Contribution 20 + Years	Large coppice stool providing good screening.	B 2	Retain
T 11	<i>Fraxinus excelsior</i> (Ash); (3.9m Radius of nominal circle; RPA 48m²)	320 mm	15.0 m Clear Stem Height 4.0 m	N: 5.0 m E: 5.0 m S: 4.0 m W: 4.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Even but sparse.	C 2	Retain
T 12	<i>Chamaecyparis lawsoniana</i> (Lawson's Cypress); (6.0m Radius of nominal circle; RPA 113m²)	488 mm CSD	13.0 m Clear Stem Height 2.0 m	N: 2.0 m E: 2.5 m S: 2.0 m W: 2.0 m	Early Mature Estimated Remaining Contribution 10 + Years	Twin stems, heavy ivy.	C 1	Retain

Tree No.	Species	Diameter @1.5m	Height (approx.)	Spread (approx.)	Age	Condition/Preliminary Recommendations	Category	Status
T 13	<i>Chamaecyparis lawsoniana</i> (Lawson's Cypress) (4.2m Radius of nominal circle; RPA 55m²)	346 mm CSD	8.0 m Clear Stem Height 1.0 m	N: 3.0 m E: 2.0 m S: 2.0 m W: 2.0 m	Semi-Mature Estimated Remaining Contribution 10 + Years	Typical Ellwoodii cypress. Bare to south.	C 1	Retain