




From: Laura Gibbons <Laura.Gibbons@arun.gov.uk>
Sent: 15 February 2022 08:40
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Simon Davis <Simon.Davis@arun.gov.uk>
Subject: RE: Planning Consultation on: Y/3/22/OUT

Engineers Comments Regarding Surface Water Drainage

Some groundwater monitoring has been completed at the site, as has some infiltration testing. The groundwater monitoring completed to date was completed between May and December 2021, this does not meet our requirements for winter groundwater monitoring. Monitoring should be completed October to March inclusive. Groundwater was observed to be relatively shallow. Further targeted shallow winter infiltration testing should be completed.

If on-site infiltration is not possible, drainage via a restricted discharge to main river may be acceptable. Any discharge should be restricted to the mean QBAR greenfield run-off rates for all design storm events. This rate is derived from only the impermeable area of the development, including any permeable areas that are positively drained. A minimum allowable rate of 2 l/s is generally considered to avoid blockage risk of flow control devices, however, lesser rates can be achieved if adequate blockage prevention measures are incorporated.

We note that the current strategy proposes underground storage crates for the first phase of development. Open features are preferred due to their ability to achieve necessary capacity, water quality improvements, offer amenity and biodiversity value, as well as ease of on-going maintenance. We also note that trees are proposed in close proximity of the crates in this area, existing and proposed root potential areas must not conflict with SuDS features.

The hierarchy for sustainable drainage must be followed with infiltration fully investigated. Winter infiltration testing and winter groundwater monitoring must be undertaken, it is advised that the applicant discusses the extent of this monitoring with us at the earliest opportunity. Infiltration tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm event plus 40% on stored volumes, between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year storm event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location.

Adequate treatment of surface water must be ensured prior to discharge.

If you are minded to approve the application please ensure that the drainage strategy is NOT listed as approved and please apply the following conditions to ensure that the development is adequately drained and does not increase flood risk elsewhere.

PCENGD2

“Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

“Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm event plus 40% on stored volumes (allowance for climate change) between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year storm event plus 40% on stored volumes. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here [Drainage Planning Consultations | Arun District Council](#) on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application.”

PCENGD4

“Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

ENGD1

“Immediately following implementation of the approved surface water drainage system and prior to occupation of any part of the development, the developer/applicant shall provide the local planning authority with as-built drawings of the implemented scheme together with a completion report prepared by an independent engineer that confirms that the scheme was built in accordance with the approved drawing/s and is fit for purpose. The scheme shall thereafter be maintained in perpetuity.”

Reason : To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan.

And the accompanying informative:

INFORMD4

A surface water drainage verification condition guidance note is available at <https://www.arun.gov.uk/drainage-planning-consultations>, this clearly sets out our requirements for discharging this condition.

Kind regards,

Laura Gibbons

Drainage Engineer

Engineering Services

Please note that I work Tuesdays 08:00-16:00 for Arun only.



T: 01903 221374

E: laura.gibbons@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF

From: Planning.Responses <Planning.Responses@arun.gov.uk>
Sent: 24 January 2022 16:49
To: Land Drainage <Land.Drainage@arun.gov.uk>
Subject: Planning Consultation on: Y/3/22/OUT

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town & Country Planning (Development Management Procedure) (England) Order 2015 - Article 5

Outline Consent

Application No: Y/3/22/OUT
Registered: 14th January 2022
Site Address: Land West of Bilsham Road Yapton
Grid Reference: 497488 102433
Description of Works: Hybrid Application comprising of: Outline planning application for further phases of up to 110 No dwellings and associated infrastructure (with all matters reserved) and Full application for Phase 1 for 30 No residential dwellings, new access from Bilsham Road, public open space, landscaping, sustainable urban drainage and associated works.
This application is a Departure from the Development Plan and is in CIL Zone and is CIL Liable as new dwellings.

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liable. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for onsite mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. "Off" Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for "off" site infrastructure mitigation schemes. Therefore if this proposal triggers the need for "off" site mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 24th February 2022 . You can also monitor the progress of this application through the Council web site:

<https://www.arun.gov.uk/planning-application-search>

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website

<https://www.arun.gov.uk/development-plan> as can information on what comments we can consider

<https://www.arun.gov.uk/planning-application-comments>

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://app.planninginspectorate.gov.uk/> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Mr S Davis

Planning Officer- Arun District Council

Telephone: 01903 737874

Email: Simon.Davis@arun.gov.uk

PLCONSULT (ODS) 2020