



NORTH END ROAD

NORTH END ROAD

CHURCH LANE

YAPTON COE
PRIMARY SCHOOL

VISIBILITY SPLAY OF 2.4 x 76 METRES TO THE LEFT BASED ON
MIS2 / TD9-93 REQUIREMENTS.

EXISTING ACCESS STOPPED UP.

5.5 METRE ROAD ACCESS ROAD WIDTH WITH A 8.0 METRE
BELLMOUTH RADII. ACCESS ROAD TO HAVE A 1:20 GRADIENT
FOR THE FIRST 25 METRES TO BRING UP TO SITE LEVELS.

PROPOSED 2.0 METRE WIDE FOOTWAY SITUATED ON EITHER SIDE
OF ACCESS ROAD. PEDESTRIAN CROSSING POINT ACROSS ACCESS
ROAD WITH DROP KERBS AND TACTILE PAVING.

VISIBILITY SPLAY OF 2.4 x 67 METRES TO THE RIGHT BASED ON
MIS2 / TD9-93 REQUIREMENTS.

PROPOSED 2.0 METRE WIDE FOOTWAY FROM ACCESS TO TIE-IN
WITH EXISTING FOOTWAY.

LEGEND



GRADED BANK (1:3) TO MEET
SITE LEVELS



Transport Planners and Infrastructure Design Consultants
The Old Stables, Fry's Yard, Bridge Street, Godalming, Surrey, GU7 1HP
Tel: 01483 861681 Fax: 01483 861682 www.russelgillespie.com

Client

David Robinson

Project

North End Road, Yapton

Drawing Title

Proposed Access Arrangement

Scale	Drawn By	Checked By	Approved By
1:500 @ A3	GSE	ALB	PMR
Drawing No.	Date	Rev.	

2014/2270/001 October 2014 C

This map is based on or reproduced from Ordnance Survey material with the
permission of Ordnance Survey on behalf of the controller of Her Majesty's
Stationary Office (c) Crown Copyright.
Licence Number: AL100037123
This drawing is based upon Ordnance Survey mapping - RGP accept no liability
for any inaccuracies with the data.